



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Project: Main Building, 3rd Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
3rd Floor, rooms C3-01A (on plans as C3-72L) and C3-01B						
Floor	12' X 12" floor tile	160 ft ² /area	N/A	N/A	7-58	15 % Chrysotile
	Floor tile mastic	160 ft ² /area	N/A	N/A	7-59	10% Chrysotile
Mechanical room	Pipe insulation	12 linear ft	Good	N/A	N/A	Assumed
Univents	Transite panels	16 – 32 ft ² /area	Damaged	N/A	N/A	Assumed
3rd Floor, vertical chase East of stair # 1						
Pipe riser	Pipe insulation (mastic over cork)	12 linear ft	Good	N/A	6-96	8% Chrysotile
3rd Floor, room C3-2						
Pipes – removed	Pipe insulation -removed	N/A	N/A	N/A	N/A	Assumed
3rd Floor, room C3-4 (can't find room in field or drawings)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-5						
Floor	12" X 12" floor tile (off-white w/tan & dark tan mottles)	200 ft ²	N/A	3-167	N/A	None detected
	Floor tile mastic	200 ft ²	N/A	3-168	N/A	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-6						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	150 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	150 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16 -32 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-03						
Univents	Transite panels	12-24 ft ²				Assumed
Floor	Rug over concrete					
3rd floor. Corridor C3-09						
Floor	12" X 12" floor tile – green	550 ft ²	Good			15% Chrysotile
	Mastic	550 ft ²				10% Chrysotile
Univent -SW Wall		12-24 ft ²				Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-7						
Floor	12" X12" floor tile (white w/black streaks)	150 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor mastic	150 ft ²	N/A	N/A	8-029	5 % Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	16 -32 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-8						
Floor	12' X 12" floor tile (white w/black streaks)	200 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor mastic	200 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/worm marks)	200 ft ²	N/A	3-169	N/A	None detected
Univents	Transite panels	28-56 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, Room C3-10						
Floor	12" X 12" floor tile (tan w/white and dark tan mottles)	150 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	150 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	56 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, rooms C3-11, C3-12, C3-13						
Floor	12" X 12" floor tile (off-white w/ tan & dark tan mottles)	150 ft ²	N/A	N/A	3-167	None detected
	Floor tile	150 ft ²	N/A	N/A	3-168	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16 -32 ft ²	Damaged	N/A	N/A	Assumed
Comments: C3-13 has ACM pipes in N and E wall. 20-30 LF damage.						
3rd Floor, room C3-14						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/worm markings)	100 ft ²	N/A	N/A	3-170	10% Chrysotile
3rd Floor room C3-14A						
Floor	Rug over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/worm markings – similar to Liberty Hall)	150 ft ²	N/A	30170	N/A	10% Chrysotile
Univents	Transite panels (front panels missing)		N/A	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-15						
Floor	12"X 12" floor tile 9off-white w/tan & dark tan mottles)	40 ft ²	N/A	N/A	3-167	None detected
	Floor tile mastic	40 ft ²	N/A	N/A	3-168	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/worm markings)	40 ft ²	N/A	N/A	3-170	10% Chrysotile
3rd Floor, room C3-16						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Chase at S wall	Pipe insulation	15-20 LF	Damage	N/A	N/A	Assumed
3rd Floor, room C3-18						
Floor	12" X 12" floor tile/mastic	300 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 – 64 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-19 (3 rooms)						
Floor	12" X 12 floor tile (tan w/white 7 dark tan mottles)	340 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	340 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 -64 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-20 (3 rooms C3-20, 20A and 20B)						
Floor	12" X 12" floor tile (off-white w/tan & dark tan mottles)	340 ft ²	N/A	N/A	3-167	None-detected
	Floor tile mastic	340 ft ²	N/A	N/A	3-168	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile/Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	33-64 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, rooms C3-21 and C3-22						
Floor	12" X 12" Floor tile (chocolate w/white & dark brown marble effect)	192 ft ² C3-21 160 ft ² C3-22	Good	N/A	7-86	None detected
	Floor tile mastic	192 ft ² C3-21 160 ft ² C3-22	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster/tile`	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ² /area	Damaged	N/A	N/A	Assumed
C3-22 bathroom- in E wall	Pipe insulation	>10 linear ft	Good	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, W wing, main hall						
Floor	12" X 12" floor tile (light green w/white & dark green mottle)	1100 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	1100 ft ²	N/A	N/A	7-59	10 % Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	Previously tested	None detected
3rd Floor, rooms C3-23 and C3-24						
Floor	12" X 12" Floor tile (tan w/white and dark tan mottles)	190 ft ² /area	Good	N/A	8-039	None detected
	Floor tile mastic	190 ft ² /area	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster (C3-23)	N/A	N/A	N/A	N/A	Non-suspect
	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ² /area	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-25 (suite, 3 rooms)						
Floor	12' X 12" floor tile (tan w/white & dark tan mottles)	300 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	300 ft ²	N/A	N/A	8-040	2% Chrysotile
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A		Non-suspect
Univents	Transite panels	28-56 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, Room C3-26						
Floor	Flooring re-done –					Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32- 64 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-27						
Floor	Flooring re-done					Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 -64 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, room C3-29 – Indeterminate amount of asbestos insulation in S wall. (30-40 LF – some ACM on chase ground damaged)						
3rd Floor, room C3-30						
Floor	12' X 12" Floor tile (light green)	40 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	40 ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' X 4' ceiling tile (worm markings) Appear to be same as ones tested 10% Chrysotile (?)	40 ft ²	N/A	3-164	N/A	<1% Amosite <1% Chrysotile
3rd Floor, room C3-31 (Not labeled in field)						
Floor	Rug over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In wall	Pipe insulation	20-30 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-31A						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock/ joint material	N/A	N/A	3-163	N/A	None detected
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tiles in walls	Pipe insulation	20 LF	N/A	N/A	N/A	Assumed
3rd Floor, room C2-32 and C3-33						
Floor of C3-32	Replaced w/ new		N/A	N/A		Non-suspect
Floor of C3-33	Replaced w/new					Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In wall	Pipe insulation (Assumed in chases)	20-30 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	20 -40 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, rooms C3-34 and C3-35						
Floor	Floor tile removed – carpet C3-34, concrete C3-35)					Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ² /area	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, rooms C3-37						
Floor	Floor tile removed - carpet	150 ft ² /area	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile in wall	Pipe insulation - removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels	28 -56 ft ² /area	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-38						
Floor	Floor tile removed - carpet	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-40 and C3-39						
Floor	Floor tile removed - carpet	150 ft ² /area	N/A	N/A	3-167	Non-suspect
Univents	Transite panels	16-32 ft ² /area	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-42						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8 -16ft ft ²	Damaged	N/A	N/A	Assumed



**Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN**

3rd Floor, room C3-43 (vertical chase)						
Pipes	Pipes/ fitting insulation (mastic) - removed	4 linear ft	Damaged	N/A	6-96	8% Chrysotile - removed
3rd Floor, chase W of stair #2						
Pipe riser	Pipe insulation (black mastic on cork)	10 linear ft	Good	N/A	6-96	8% Chrysotile
3rd Floor. Room C3-44						
Floor	Replaced w/new 12" X 12" floor tile (tan w/ brown mottles)	150 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	150 ft ²	N/A	N/A	8-040	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 -64 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-45 (Cardiology suite – eight rooms and small hall) (C3-45 A,B,C,D,E,F,G,H)						
Floor	All replaced –hall 12" X 12" floor tile Rooms - carpet	800 ft ²				Non-suspect
	Floor tile mastic	800 ft ²				Non-suspect
Walls	Tile/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (except for below)	N/A	N/A	N/A	N/A	Non-suspect
	2' X 4' ceiling tile (rooms C3-45B, C3-45C, C3-45D)	100 ft ²	N/A	3-162	N/A	15% Chrysotile
Univents	Transite panels	130-260 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, C3-46 and C3-47						
Chase in E & W walls (C3-46)	Pipe insulation	12 LF E wall 6 LF W wall	Damaged	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, vertical chase N of main elevators in C3-73 electrical closet						
Pipe riser	Pipe insulation (mastic over cork)	10 linear ft	Good	N/A	6-96	8% Chrysotile
Under floor	Pipe/fitting insulation	10 linear ft	Good	N/A	N/A	Assumed
3rd Floor, room C3-53						
Floor	12" X 12" floor tile (white w/ black streaks) - Removed	160 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor tile mastic - Removed	160 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A			Assumed
Comment: Chase access door has 20 LF of S. damage piping insulation						
3rd Floor, rooms C3-55 and C3-54 (same room now)						
Floor	Floor tile - removed					Non-suspect
	Mastic- Removed					
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Univents	Transite panels	16-32 ft ²	Damaged			Assumed
In W wall (C3-55)	Pipe insulation – Asbestos pipe insulation can be seen running down in W wall of C3-55 and into E wall and over bathroom ceiling in C3-54	Can't see - assume	Damaged			Assumed
E wall (C3-54)	Pipe insulation	20 linear ft	S. Damage	N/A	N/A	Assumed
3rd Floor, room C3-56A and C3-56B (service elevator hall)						
Floor	12" X 12" floor tile(green mottle)	360 ft ²	Good	N/A	7-58	15% Chrysotile
	Mastic	N/A	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/ceramic tile/brick	N/A	N/A	N/A	N/A	N/A
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	Previously tested	<1%
(56A)NW Chase Above ceiling tile	Pipe insulation	20 LF	Damaged	N/A	N/A	Assumed
3rd Floor, room C3-57A						
Floor	Pipe insulation	1 LF	Significantly damaged	N/A	N/A	Assumed
3rd Floor, hall be elevators (C3-57)						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	1000 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	1000 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
3rd Floor, room C3-58A – no exposed suspect asbestos material observed. C3-58A Door not labeled						



**Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN**

3rd floor, room C3-58 (as labeled in field but is C3-059 on drawings)						
Floor	12" X 12" floor tile (tan w/white & dark brown marbling)	120 ft ²	N/A	N/A	7-86	None detected
	Floor tile mastic	120 ft ²	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Wall between 58 & 59	Pipe insulation	>30 linear ft	Good	N/A	N/A	Assumed
3rd Floor, room C3-59 (as labeled in field but is C3-060 on drawings)						
Floor	12" X 12" floor tile (off-white w/tan & dark tan mottles)	N/A	N/A	N/A	3-167	None detected
	Floor tile mastic	N/A	N/A	N/A	3-168	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
E wall	Pipe insulation – can be seen running down into E wall	20-30 LF	Good	N/A	N/A	Assumed
3rd Floor, room C3-61 bathroom (as labeled in field but is C3-61A on drawings) – pipe insulation inside N wall – not accessible 20-30 LF						
3rd Floor, rooms C3-60 and C3-62 (C3-60 as labeled in field but is C3-061 on drawings)						
Floor	12"X 12" floor tile (off-white w/tan & dark tan mottles)	150 each room	N/A	N/A	3-167	None detected
	Floor tile mastic	150 each room	N/A	N/A	3-168	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect
3rd Floor, rooms C3-63, C3-64, C3-65 and C3-68 – No exposed suspect asbestos material observed.						
3rd Floor, room C3-67 – Tan (with mottles) 12" X 12" floor tile and mastic are suspected asbestos-containing materials. No other suspect asbestos materials observed in this room.						



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-69						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Brick	N/A	N/A	N/A	N/A	Non-suspect
	Tar paper/flashing	20 LF	Damaged	01-3	N/A	2% Chrysotile
Ceiling	Concrete	N/A	N/A	N/A	N/A	Non-suspect
W wall above access	Pipe insulation	20 LF	Damaged	N/A	N/A	Assumed
3rd Floor, rooms C3-71						
Floor	12" X 12' floor tile and mastic	50 ft ²	Good	N/A	N/A	Assumed
West wall	Pipe insulation	12 LF	Good	N/A	N/A	Assumed
3rd Floor, rooms C3-70 and 70A						
Floor	12" X 12" floor tile (off-white w/ tan & dark tan mottles)	200 ft ²	N/A	N/A	3-167	None detected
	Floor tile mastic	200 ft ²	N/A	N/A	3-168	10% Chrysotile
Walls	Sheetrock/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect
W wall Chase	Pipe insulation	6 LF	Good			Assumed
Univents	Transite panels (front panels missing)	20 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, room C3-72 Suite						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	1500 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	1500 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	v N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
3rd Floor, hall to room C3-72						
Floor	12" x12" floor tile (light green w/white & dark green mottles)	1440 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	1440 ft ²	N/A	N/A	7-59	10 % Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
3rd Floor, N wing, N3-69 – no exposed suspect materials, but entire area was not accessible. Possible pipes above plaster						
3rd Floor, N wing, N3-74						
Floor	12" X 12" floor tile (chocolate w/white & dark brown marbling)	150 ft ²	N/A	N/A	7-87	None detected
	Floor tile mastic	N/A	N/A	N/A	7-87T	5% Chrysotile
	Floor tile and mastic	<10 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	V	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-75						
Floor	12" X 12" floor tile	140 ft ²	N/A	N/A	3-173T	None detected
	Floor tile mastic	140 ft ²	N/A	N/A	3-173M	8% Chrysotile
3rd Floor, N wing, N3-78, 78A, 79, 79A, 80						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	80 –160 ft ²	N/A	N/A	N/A	Assumed
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
N3-79 – small piece (2-3 ft²) of cork insulation above ceiling and 8-10 ft of mag above ceiling.						
3rd Floor, N wing, rooms N3-76 and N3-77A (sterilizer area)						
Floor	12" X 12" floor tile	600 ft ² (N3-76) 160 ft ² (N3-77A)	N/A	3-173	N/A	None detected
	Floor tile mastic	600 ft ² (N3-76) 160 ft ² (N3-77A)	N/A	3-173	N/A	8% Chrysotile
Walls	Tile (ceramic)	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft ² /area	N/A	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-81						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile (NW corner -Removed)	Pipe insulation – not found or removed					
3rd Floor, N wing, hall from room N2-82 to N3-112						
Floor	12' X 12" floor tile (light green w/white & dk green mottles)	600 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	600 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Duct insulation (black Mastic over cork) Not found	60 linear ft	N/A	N/A	6-96	8% Chrysotile
3rd Floor, women's room (N3-82)						
Above ceiling tile	Pipe insulation	10-15 linear ft	Good	N/A	N/A	Assumed
	Duct insulation (mastic over cork)	6 linear ft	Good	N/A	6-96	8% Chrysotile
3rd Floor, N wing, room N3-83						
Floor	Ceramic tile`	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panel	20-40 ft ²	Good	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-85						
Floor	12" X 12" floor tile (white w/black streaks)	35 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor tile mastic	35 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Above plaster ceiling	Pipe insulation aircell (cementitious and black mastic on cork)	12 linear ft	Good	N/A	N/A	Assumed
3rd Floor N wing, room N3-88						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect
3rd Floor, N wing, room N3-86						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
Wall chase	Pipe insulation	30 – 40 LF	Good and S.Damaged	N/A	N/A	Assumed
3rd Floor, N wing, room N3-91						
Pipe riser	Pipe insulation (black mastic over cork)	12 linear ft	Good	N/A	6-96	8% Chrysotile
Duct	Duct insulation (black mastic over cork)	150 ft ²	Good	N/A	6-96	8% Chrysotile



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-92						
Floor	12' X 12" floor tile (off-white w/white & dark gray mottles)	170 ft ²	N/A	N/A	6-105	None –detected
	Floor tile mastic	170 ft ²	N/A	N/A	6-106	5% Chrysotile
Ceilings	2' X 4' Ceiling tile (off-white w/ worm markings)	N/A	N/A	3-172	N/A	None detected
Univents	Transite panels – front panels gone	16-32 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-93						
Floor	12" X 12" floor tile - gray	350 ft ²	N/A	3-180	N/A	5% Chrysotile
	Floor tile mastic	350 ft ²	N/A	3-181	N/A	<1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile –new	N/A	N/A	N/A	N/A	Non-suspect
Under sink	Pipe insulation– can't see	4 linear ft	Damaged	N/A	N/A	Assumed
Above trap in plaster ceiling – Removed	Pipe insulation - Removed					
Univents	Transite panels	40 – 80 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, N wing, room N3-94						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4-12 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-95						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels – front panels removed	24 ft ²				Assumed
3rd Floor, N wing, rooms N3-96 & N3-98						
Floor	12" X 12 Floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	N/A
Under W sink	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-97						
Floor	12" X 12' floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-99 (chemical storage)						
Floor	Terrazzo Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/a	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed (still possibly in chase)	N/A	N/A	N/A	N/A	N/A
	N/A	N/A	N/A	N/A	6-96	N/A
Univents	Transite panels (front panels missing)		N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-103 (lounge)						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	N/A
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Duct insulation	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels (front panel missing)	32 ft ²	Damaged	N/A	N/A	Assumed
3rd Floor, N wing, rooms N3-104 and N3-105						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Duct insulation – removed	N/A	N/A	N/A	6-96	N/A
Univents	Transite panels (front panels missing)	24 ft ² /ea	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-106						
Floor	12" X 12" Floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	N/A
Above plaster	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
3rd floor, N wing, room N3-107						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels (front panels missing)	16 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-109						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile – new	150 ft ²	N/A	3-183	N/A	Non-detected
Univents	Transite panels (front panels missing)	16 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

3rd Floor, N wing, room N3-110						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Duct Insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels –front panels removed	24 ft ²				Assumed
3rd Floor, N wing, room N3-111						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
In wall under sink	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels	24 - 48 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-112 and small hall						
Floor	12" X 12" floor tile (off-white w/gray & olive stripes) – Replaced – New	740 ft ²	N/A	N/A		Non-suspect
	Floor tile mastic	740 ft ²	N/A	N/A		Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Univents	Transite panels (front panel missing)	24 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-113						
Floor	Terrazzo Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' Ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Running into S wall	Pipe insulation (wrapped paper) – removed above ceiling	N/A	N/A	N/A	N/A	Assumed
All still running inside of wall	Pipe insulation (black mastic over cork) – removed above ceiling	N/A	N/A	N/A	N/A	Assumed
	Duct insulation (black mastic over cork) – removed above ceiling	N/A	N/A	N/A	N/A	Assumed
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
3rd Floor, N wing, room N3-114 – Asbestos insulation runs into walls						
3rd Floor, N wing, room N3-115						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
Duct insulation – removed	N/A	N/A	N/A	N/A	N/A	N/A



**Building 1, Floor 3 - Specific Survey Findings
Project No. VAMC:10013.00-IN**

3rd Floor, N wing, room N3-116 (corridor) – Newly renovated – no exposed suspect materials observed						
3rd Floor, main hall (lab area)						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	900 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	900 ft ²	N/A	N/A	7-59	10 % Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
3rd Floor, room C3-119						
Floor	12" X 12" floor tile (off-white w/sparse light tan marks)	200 ft ²	N/A	3-165	N/A	None detected
	Floor tile mastic	200 ft ²	N/A	3-166	N/A	5% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect

NOTE:

Rooms C3-70 through C3-71 are all new. A chase in the mechanical room contains suspect pipe insulation in NE corner (approximately 12 linear feet). This material, however, is in good condition.

No suspect asbestos containing materials were observed in the following areas: main hall (from C3-53 to C3-45, C3-57B, C3-58, janitor's closet (N of short procedure), men's room (N wing), N3-89, and the chase w of C3-56.