



Building 1, Floor 4 Specific Survey Findings
Project No. VAMC:10013.00-IN

1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Project: **Main Building, 4th Floor**
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
4th Floor, room C4-2						
Pipes	Pipe insulation (black mastic over cork) - Removed					N/A
4th Floor, Chase E of stair #1						
Pipe Riser	Pipe insulation (black mastic over cork)	12 LF	N/A	N/A	6-96	8% Chrysotile
4th Floor, room C4-14						
Floor	Terrazzo tile - Now non-suspect 12" x12" floor tile	N/A	N/A	N/A	N/A	Non- Suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
N Wall	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
4th Floor, room C4-15 – No access, but asbestos pipe insulation can be seen running down into S wall (from C4-14) – gone? - Removed						
4th Floor, room C4-16						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Wall chase	Pipe insulation –Can't see, chase is blocked	N/A	Damaged	N/A	N/A	Assumed



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, room C4-43A						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	8% Chrysotile
4th Floor, room C4-47A – May be asbestos insulation in brick wall						
4th Floor, room C4-73 (Electrical)						
Pipes	Pipe insulation (black mastic over cork)	15 LF	Good	N/A	6-96	8% Chrysotile
4th Floor, hall by main elevators and stair 3 to operating room doors. C4-74A and C4-57						
Floor	12" X 12" floor tile/mastic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation (black mastic over cork)	>100 LF	Good	N/A	6-69	8% Chrysotile
	Cork Duct w/tar	>160 ft ²	Good	N/A		Positive
4th Floor, room C4-74						
Floor	12" X 12" floor tile (brown w/white/dark brown & white marble effect)	150 ft ²	N/A	N/A	7-86	None detected
	Floor tile mastic	150 ft ²	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A		28-147	N/A	None detected
Above ceiling tiles	Pipe insulation (MAG/cork/aircell)	23 LF	Damaged & Good (cork)	N/A	N/A	Assumed
Univents	Transite panels	16 32 ft ²	Good	N/A	N/A	Assumed



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, room N4-127, 127A 127B - Remnant black mastic from ductwork above ceiling tile						
4th Floor, room N4-124 – Above ceiling tile: tar on old ductwork (~50 ft) and remnant tar on ceiling tile (<2 ft)						
4th Floor, room C4-130 (N4-130 on CADD)						
Floor	Rig over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock/ joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
4th Floor, room C4-131						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12"X12 " floor tile (tan)	190 ft ²	N/A	4-161T	N/A	<1% Chrysotile
	Floor tile mastic	190 ft ²	N/A	4-161M	N/A	None detected
Walls	Sheetrock / joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Chase	Pipe/fitting insulation on fiberglass	2 LF	Good	N/A	N/A	Assumed
4th Floor, room C4-132						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (green)	300-400 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	300-400 ft ²	N/A	N/A	N/A	Assumed
In S wall	Pipe insulation	30 LF	Good	N/A	N/A	Assumed
Floor of closet	12" X 12' Floor tile mastic	50 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, hall by service elevator						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	170 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	170 ft ²	N/A	N/A	7-59	10% Chrysotile
4th Floor, N4-77 (corridor)						
Floor	12" x 12" floor	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation – black mastic over cork	>1000 ft	Good	N/A	N/A	Assumed
4th Floor, room N4-78						
Floor	12" X 12" floor tile (off-white w/tan & brown mottles) and mastic	N/A	N/A	N/A	N/A	>1%
Walls	Sheetrock/ joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	20-40 ft ²	Damaged	N/A	N/A	Assumed
4th Floor, rooms N4-85 and N4-86 all new except – N4-86 chases contain pipe insulation						
4th Floor, room N4-84						
Floor	12" X 12" floor tile (off-white w/tan & brown mottles)	170 ft ²	N/A	N/A	7-58	Non-suspect
	Floor tile mastic	170ft ²	N/A	N/A	7-59	>1 %
Chases	Pipe insulation	N/A	N/A	N/A	N/A	Assumed
4th Floor, rooms N4-88 and N4-90 – all new						



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, room N4-92 – GUT REHAB ALL NEW						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	130 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	130 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	Previously tested	<1%
4th Floor, room N4-95 – GUT REHAB ALL NEW						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	130 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	130 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	Previously tested	<1%
4th Floor, hall by elevator and N4-86 (N4-133 and N4-133A)						
Floor	12" X 12" floor tile/mastic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' / 2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation (black mastic over cork)	400 ft ²	Significant damage	N/A	6-96	8% Chrysotile
Above ceiling tile	Pipe insulation (black mastic over cork) – NOT FOUND	>40 LF	N/A	N/A	6-96	8% Chrysotile
4th Floor, N4-91 (electrical closet) – *Debris on floor*. Pipe insulation (black mastic over cork) in NW chase. NOT FOUND - Aircell and black mastic over cork insulation at E wall.						
4th Floor, N4-93, N4-97, N4-100, N4-107, N4-110, N4-111, N4-115, N4-124, N4-125 – No exposed suspect asbestos materials observed.						
4th Floor, N4-96 – Damaged duct insulation in NE chase. Amount indeterminate - Gut Rehab						
4th Floor, N4-102, N4-103, N4-105 – Pipe insulation runs over ceilings. – Gut Rehab						



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, N4-112, N4-113, N4-114 – Pipe insulation runs over ceilings and in chases -> 30 LF – some damaged - Gut Rehab						
4th Floor, room N4-118						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X2' / 2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
E chase	Pipe insulation	30-40 LF	Significant damage	N/A	N/A	Assumed
Univent	Transite panel	16-24 ft ²	Good			Assumed
4th Floor, room 117						
Univents	Transite panels	16 – 32 ft ²	N/A	N/A	N/A	Assumed
4th Floor, electrical closet W of N stairwell						
S room	Pipe insulation (white) Removed	N/A	N/A	N/A	N/A	N/A
	Pipe insulation (black mastic over cork) Removed	N/A	N/A	N/A	N/A	N/A
N room	Pipe insulation (black mastic over cork) Removed	N/A	N/A	N/A	N/A	N/A
Chase	Pipe insulation (black mastic over cork)	12 LF	Good	N/A	6-96	8% Chrysotile
4th Floor, OR suite & associated rooms – PART OF GUT REHAB						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Sterilizer room – above plaster ceiling	Pipe fitting insulation	N/A	N/A	N/A	N/A	Assumed
NE Chase in N4-96	Duct insulation (black mastic over cork)	N/A	N/A	N/A	N/A	8% Chrysotile
NE Chase in N4-96	Duct insulation (cementitious)	N/A	N/A	N/A	N/A	8% Chrysotile



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, room N4-120 – pipe insulation in NW chase – assume, not visible. Cork duct in NW corner – Significant damage under fiberglass.						
4th Floor, room N4-101 – PART OF GUT REHAB						
Floor	12" X 12" floor tile (off-white w/short brown streaks)	120 ft ²	N/A	4-192	N/A	10% Chrysotile
	Floor tile mastic	120 ft ²	N/A	4-193	N/A	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	16-32 ft ²	N/A	N/A	N/A	Assumed
Above ceiling	Pipe insulation	N/A	N/A	N/A	N/A	Assumed
Above ceiling	Duct insulation	N/A	N/A	N/A	6-96	8% Chrysotile
4th Floor, N4-104 & sterilizer room – PART OF GUT REHAB						
Above ceiling & in chase	Pipe insulation	12-15 LF	N/A	N/A	N/A	Assumed
Sterilizer room	Pipe fitting insulation	3 fittings	Significantly damaged	N/A	N/A	Assumed
	Pipe insulation	6 LF	N/A	N/A	N/A	Assumed
	Sterilizer insulation	12 ft ²	4-194	N/A	N/A	None detected
4th Floor, N4-106 – PART OF GUT REHAB						
SE Chase	Duct insulation (black mastic over cork)	12 LF	N/A	N/A	6-96	8% Chrysotile
4th Floor, N4-114 & Sterilizer room – PART OF GUT REHAB						
Sterilizer room	Pipe fitting insulation	3 fittings	Significantly damaged	N/A	N/A	Assumed
Sterilizer room – against N-wall	Pipe insulation	7 ft	Significantly damaged	N/A	N/A	Assumed
Above ceiling	Pipe insulation	10-15 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor 4 - Specific Survey Findings
Project No. VAMC:10013.00-IN

4th Floor, rooms N4-107, N4-110, N4-111 – PART OF GUT REHAB						
4th Floor, room 115 – high ceiling – no access – may be pipe insulation above. – PART OF GUT REHAB						
4th Floor, N4-122, bathroom, mechanical room						
Above ceiling & in walls	Pipe insulation – Not Found	N/A	N/A	N/A	N/A	Assumed
Comments: Cork duct – Significant damage 150 ft ² . Mastic on concrete beam between 122 and N4-62A						
4th Floor, main hall – OR suites – ALL REMOVED						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation (black mastic over cork)	~400 ft ²	N/A	N/A	6-96	8% Chrysotile
Above ceiling tile	Pipe insulation	~100 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
Above plaster ceilings in suite. May also be in walls.	Pipe insulation	N/A	N/A	N/A	N/A	Assumed

NOTE: 4E and Center – were all recently renovated. No suspect asbestos-containing materials, unless noted.