



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Project: Main Building, 5th Floor and Interstitial Space
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
Interstitial Space under the 5th Floor and above the 4th floor						
Duct under fiberglass	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Pipe – in floor, far W section – against S wall	Pipe insulation – These risers are mostly insulated with fiberglass, but asbestos insulation can be seen extending into floor (goes into ceiling of 4 th floor).	N/A	N/A	N/A	N/A	Assumed
Comments: Pipes which penetrate floor and ceiling have ACM between floors. ~ 3LF MAG along W wall – Significant damage (interstitial)						
5th Floor, C5-01 and C5-01A						
Floor	12" X 12" floor tile (tan w/light & dark tan mottles)	~200 ft ²	N/A	N/A	N/A	Assumed
	Mastic	~200 ft ²	N/A	N/A	N/A	Assumed
Walls	Sandwich-type metal with insulation in center	140 ft ²	Good	01-5	N/A	None detected
	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents (in 01)	Transite panels	32-64 ft ²	N/A	N/A	N/A	Assumed
5th Floor, C5-03						
Floor	12" X 12" floor tile (tan w/light & dark tan mottles)	~200 ft ²	N/A	N/A	N/A	Assumed
	Mastic	~200 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings Project No. VAMC:10013.00-IN

Ceiling	2' x 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	N/A	N/A	N/A	Assumed
Above ceiling – W wall	Pipe insulation	10-20 LF	N/A	N/A	N/A	Assumed
5th Floor, room C5-2						
Pipe - Removed	Pipe insulation (black mastic over cork)	2 LF	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-4 – Can't Find						
Floor	12" X 12" floor tile (light gray w/white & dark gray mottles)	150 ft ²	N/A	N/A	6-105	Non-detected
	Floor tile mastic	150 ft ²	N/A	N/A	6-106	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
Above plaster ceiling & in W wall	Pipe insulation	8 LF	Good	N/A	N/A	Assumed
5th Floor, room C5-7						
Floor	12"X12" floor tile /mastic (off-white w/olive & gray streaks)	160 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, main hall (MICU door to fire door by room C5-20)						
Floor	12" X 12" floor tile / mastic (off-white w/olive and gray streaks)	960 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster /tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile	N/A		28-147	N/A	None-detected
Above ceiling tile	Duct insulation (black mastic over cork)	300 LF	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-10						
Floor	12" X 12" floor tile (light tan w/white & dark tan mottles)	160 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	160 ft ²	N/A	V	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	None detected
Univents	Transite panels	24-48 ft ²	N/A	N/A	N/A	Assumed
Bathroom (in E wall)	Pipe insulation	N/A	Significant damage	N/A	N/A	Assumed
5th Floor, rooms C5-13, C5-11, C5-8, C5-6 and C5-5						
Floor	12" X 12" floor tile (white w/light & dark tan mottle)	100-150 ft ² /area	N/A	N/A	5-69	None detected
	Floor tile mastic	100-150 ft ² /area	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
Bathroom in E wall	Pipe insulation	N/A	Significant damage	N/A	N/A	Assumed
5th Floor, room C5-12						
Floor	12" X 12" floor tile (white w/gray & olive stripes)	160 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	160 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, hall (C5-14 to S end)						
Floor	12" X12" floor tile (off-white w/ olive & gray streaks)	560 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	560 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (white w/ small pinhole perforations & worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
Above ceiling tile	Duct insulation (black mastic over cork)	140 -160 LF	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-14						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (perforations w/worm markings)	100 ft ²	N/A	N/A	N/A	Non-suspect
In wall (NE Corner)	Pipe insulation	16 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	12-24 ft ²	N/A	N/A	N/A	Assumed
	Pipe insulation (in univent)	4 LF	Damaged	N/A	N/A	Assumed
5th Floor, room C5-14A						
In N wall	Pipe insulation	30-45 LF		N/A	N/A	Assumed
Comment: Can only see at top - inside of wall						



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, room S of C5-14 – Does not make sense – this would be C5-13						
Floor		N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile	100 ft ²	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4-8 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room C5-15						
Floor	9" X 9" floor tile (gray w/white & black markings) and mastic	150 ft ²	N/A	N/A	N/A	Assumed
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
5th Floor, room C5-16 – Pipe insulation in cavity at S wall. 50- 60 LF - Damaged						
5th Floor, Corridor C5-17						
Floor	12" X 12" floor tile (light tan w/white & dark tan mottles)	550 ft ²	N/A	N/A	5-69	None detected
	Floor tile mastic	550 ft ²	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster/ ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile (white w/dot perforations & worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation (black mastic over cork)	1000 ft ²	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-18						
Floor	Rug over 12" x12" floor tile (light tan w/white & dark tan mottles)	340 ft ²	N/A	N/A	5-69	None detected
	Floor tile mastic	340 ft ²	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile – new	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room C5-19						
Floor	12" X 12" floor tile (off-white w/olive & dark gray streaks)	340 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	340 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room C5-20						
Floor	12" X 12" Floor tile (white w/light tan & dark tan mottles)	340 ft ²	N/A	N/A	5-69	None detected
	Floor tile mastic	340 ft ²	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damage on W end	N/A	N/A	Assumed
5th Floor, room C5-43A						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	8% Chrysotile
C5-22, 23, 24, 25, 26, 29, 29A, 29B, 30, 31, 32, 33, 34, 35, 37, 38, 40, 41, 42, 43, 44B, 44C, 45, 46, 47, 47A, 48B, 53, 54, 57A, 57B, 58, 68, 78, 79 (room sign shows C5-77) – no suspect materials observed						



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, hall by service elevator C5-56C						
Floor	12' X 12" floor tile/mastic (white w/brown & gray streaks)	190 ft ²	N/A	N/A	N/A	Suspect – same as white w/gray streaks which is positive
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
5th Floor, vertical chase N of main elevator						
Pipe riser	Pipe insulation (black mastic over cork)	12 LF	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-59						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling & in S wall	Pipe insulation	20 LF	Damaged	N/A	N/A	Assumed
5th Floor, room C5-55						
Floor	12" X 12" floor tile (tan w/white & mottles)	N/A	N/A	N/A	8-033	None detected
	Mastic	N/A	N/A	N/A	8-034	<1%
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In S wall	Pipe insulation	10-20 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, room C5-56 – Duct insulation (black mastic over cork) ** Room not found						
5th Floor, hallway by main elevators						
Floor	12: x 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" floor tile –N end of hall	4 ft ²	Good	N/A	N/A	Suspect
Walls	Plaster/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation (black mastic over cork)	1200 ft ²	N/A	N/A	6-96	8% Chrysotile
5th Floor, room C5-60						
Floor	12"x12" Floor Tile (white w/black streaks)	150 ft ²	N/A	N/A	N/A	10% Chrysotile
	Floor Tile Mastic	150 ft ²	N/A	N/A	N/A	5% Chrysotile
5th Floor, room C5-60A and 61A – Pipe insulation in and above E wall of 60A and W wall of 61A C5-62A and 63A – assumed to be similar. In walls						
5th Floor, room C5-61						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	150 ft ²	N/A	N/A	7-58	15 % Chrysotile
	Floor tile mastic	150 ft ²	N/A	N/A	7-59	10 % Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	None detected
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, rooms C5-62 and C5-63						
Floor	12" X 12" floor tile (white w/ light & dark tan mottles)	150 ft ² /area	Good	N/A	5-69	None detected
	Floor tile mastic	150 ft ² /area	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room C5-64						
Floor	12" x12" floor tile (white w/black streaks)	136 ft ²	Good	N/A	8-028	10% Chrysotile
	Floor tile mastic	136 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
In E wall	Pipe insulation	16 LF	Good	N/A	N/A	Assumed
5th Floor, room C5-65						
Floor	12" X 12" floor tile (white w/ black streaks)	150 ft ²	Good	5-69	N/A	None detected
	Floor tile mastic	150 ft ²	N/A	5-70	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ²	N/A	N/A	N/A	Assumed
	Pipe insulation (in bathroom)	1 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, room C5-69 – pipe insulation in wall cavity at W wall above access door – damaged. Appears removed. May still be more but pipes have been replaced and mortar filled into wall.						
C5-68 – No suspect material observed						
5th Floor, room C5-66 (behind W nurses' station)						
Floor	12" X 12" Floor tile (tan w/white & dark tan mottles)	140 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	140 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (white w/dot perforations & worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4-8 ft ²	N/A	N/A	N/A	Assumed
	Pipe insulation	5 LF	Significant damage	N/A	N/A	Assumed
In wall behind sink	Pipe insulation	20 LF	N/A	N/A	N/A	Assumed
5th Floor, pipe chase across from room C5-68						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	8% Chrysotile
5th Floor, room C5-71						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile /plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
	Pipe insulation	6 LF	Good	N/A	N/A	Assumed
In center wall, above ceiling & in walls	Pipe insulation – removed	N/A	N/A	N/A	N/A	N/A
	Soapstone bench	N/A	N/A	N/A	N/A	Assumed



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

5th Floor, room C5-72 (old MICU and associated rooms)						
Floor	12" X 12" floor tile (tan w/light & dark tan mottles)	2000 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	2000 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	200-400 ft ²	N/A	N/A	N/A	Assumed
E wall, S of door	Pipe insulation	8 LF	N/A	N/A	N/A	Assumed
5th Floor, room C5-70 (mechanical room)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls - Removed	Transite panels - Removed	N/A	N/A	5-68	N/A	30% Chrysotile
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
5th floor, room behind C5-71						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Transite panels	150 -160 ft ²	Good	5-68	ft ²	30 % Chrysotile
Ceilings	Plaster/concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room C5-73 – Pipe insulation (black mastic over cork) – in chase E of C5-73 - 10 LF.						
5th Floor, room C5-74						
Floor	12" X 12" floor tile (chocolate w/white & dark brown marbling)	120 ft ²	N/A	N/A	7-86	None detected
	Floor tile mastic	120 ft ²	N/A	N/A	7-87	5% Chrysotile



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	N/A	N/A	N/A	Assumed
5th Floor, room immediately N of room C5-74 (C5-74A)						
Floor	Carpet over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In vertical chase	Pipe insulation	10 LF	Damaged	N/A	N/A	Assumed
Above ceiling tile	Duct insulation (cementitious) – located around cork insulation in center of room – painted brown	60-80 ft ²	Significant damage	02-5	N/A	35% Chrysotile
	Pipe insulation above drop ceiling	20-30 LF	Significant damage	N/A	N/A	Assumed
5th Floor, room C5-75						
Duct	Duct insulation (cementitious)	15-20 ft ²	Damaged	N/A	N/A	Assumed
5th Floor, room C5-77 (drawing shows this as C5-57)						
Floor	12" X 12" floor tile (white w/gray & olive streaks)	200 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	200 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile /plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings Project No. VAMC:10013.00-IN

5th Floor, room C5-81						
Wall	Cork insulation adhesive	N/A	N/A	03-5	N/A	None detected
5th Floor, mechanical room, W end						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Duct work	Vibration damper – removed	N/A	N/A	N/A	N/A	N/A
	Mastic spots (under cork insulation)	N/A	Damaged	5-54	N/A	None detected
	White mastic – on fiberglass insulation	N/A		5-55	N/A	None detected
5th Floor, mechanical room – East and Center						
Pipes	Pipe fitting insulation – 8"	6 fittings	Good	N/A	N/A	Assumed
	Pipe insulation – tar on cork	400 LF	Good	N/A	6-96	8% Chrysotile
Pipes against N wall	Pipe fitting insulation @ O column	6 fittings – 6LF	Significant damage	N/A	N/A	Assumed
Pipes	Cementitious insulation under strap hanger saddles	12 each	Good	5-56	N/A	20% Amosite/ 10% Chrysotile
Ducts	Vibration dampers	6	N/A	N/A	N/A	Assumed
5th Floor, room N5-74						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal/concrete	N/A	N/A	N/A	N/A	Non-suspect
Duct	Duct insulation (black mastic over cork)	120 ft ²	Good	N/A	6-96	% Chrysotile



Building 1, Floor 5 and Interstitial Space - Specific Survey Findings
Project No. VAMC:10013.00-IN

Valve	Insulation (cementitious)	1	Damaged	N/A	N/A	Assumed
Pipe	Pipe insulation (pre-formed)	6 LF	Significant damage	N/A	N/A	Assumed
	Pipe fitting insulation (Big ones)	4-6 LF	Good	N/A	N/A	Assumed
	Pipe fitting insulation (cementitious)	6 LF	Damaged	N/A	N/A	Assumed
Under metal grate	Possible residual asbestos insulation materials					Assumed
Comment: Piece of MAG ACM pipe insulation on fiberglass						
5th Floor, AC shop office (off mechanical room)						
Floor	9" x9" floor tile (black)	225 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	225 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect

NOTE:

No suspect asbestos containing materials were observed in the following areas: C5-16, C5-58, C5-57A, C5-57B and C5-68.