



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Project: Main Building, 7th Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
7th Floor, room C7-01A (Labeled on Drawings as C7-01)						
Floor	12" X 12" floor tile (off-white w/light olive & dark mottles)	280 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	280 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	36-72 ft ²	N/A	N/A	N/A	Assumed
Comments: No ACM ins. Above plaster. Has mastic on exterior wall fascia (typical of all exterior walls).						
7th Floor, room C7-02, Electric						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal	N/A	N/A	N/A	N/A	Non-suspect
Pipe- Removed	Pipe fitting insulation (tar over cork)	2-LF	Damaged	N/A	6-96	8% Chrysotile
7th Floor, room C7-03 **Room has been abated and no longer exists as listed						
Floor	12" x 12" floor tile (light gray w/white & dark gray mottles)	~150 ft ²	Good	7-62	N/A	10% Chrysotile
	Floor tile mastic	~150 ft ²	Good	7-63	N/A	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
Above ceiling	Pipe insulation above window and NW and SW corners					Assumed
7th Floor, room C7-4A **Room has been abated and no longer exists as listed						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	80 ft ²	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation	16 LF	Good	N/A	N/A	Assumed
7th Floor, rooms C7-05, C7-06 and C7-10 **Room has been abated and no longer exists as listed						
Floor	12" X 12" floor tile (light green w/white/green)	160 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	160 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
Above plaster ceiling	Pipe insulation	N/A	N/A	N/A	N/A	Assumed
Comments: In room C7-10 there was access to area above the ceiling. Suspect asbestos-containing pipe insulation materials were observed in this area. The pipe materials were in good condition, but the amount of material was indeterminate.						



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, rooms C7-07 and C7-11 **Room has been abated and no longer exists as listed						
Floor	12" X 12" floor tile (tan w/white/light brown & dark brown mottles)	160 ft ²	Good	N/A	8-039	None detected
	Floor tile mastic	160 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
Above ceiling C7-11	Pipe insulation above bathroom ceiling	N/A	N/A	N/A	N/A	Assumed
7th Floor, room C7-08 **Room has been abated and no longer exists as listed						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile	160 ft ²	N/A	7-64	N/A	None detected
	Floor tile mastic	160 ft ²	N/A	7-65	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile (gray w/rough surface & foil backing)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-09 **Room has been abated and no longer exists as listed						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (green)	160 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	160 ft ²	N/A	N/A	7-59	10% Chrysotile
	Walls	Plaster	N/A	N/A	N/A	Non-suspect



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	2'X2' ceiling tile (gray w/rough surface & foil backing)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16—32 ft ²	N/A	N/A	N/A	Assumed
Above ceiling C7-09	Pipe insulation above bathroom ceiling	N/A	N/A	N/A	N/A	Assumed
7th Floor, room C7-10 **Room has been abated and no longer exists as listed						
Floor	12" X 12" floor tile	160 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	160 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-12 **Room has been abated and no longer exists as listed						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	Good	N/A	7-57	None detected
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-13A						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	120 ft ²	N/A	N/A	7—57	None detected
Pipe insulation N wall	Can't see into wall	40 LF				Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, rooms C7-01b and C7-01c (not labeled at all on drawings but marked this in the field; was once one room now partition has been added)						
Floor	12"x12" Floor Tile (lt green w/dark green/white mottles)	200 ft ² / room	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	200 ft ² / room	Good	N/A	7-59	10% Chrysotile
Univents	Transite Panels	32 ft ² / room	damaged	N/A	N/A	Assumed
7th Floor, rooms Bed 1 – Bed 10 and associated hallway C7-08A (it is assumed these rooms are what was once the eleven rooms not found in field but listed)						
Floor (Hallway C7-08A only)	Carpet over top of 12"x12" Floor Tile (green)	500 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	500 ft ²	Good	N/A	7-59	10% Chrysotile
Above Plaster Ceiling	Pipe Insulation (Bed 2 and Bed 9; no access above C7-08A Ceiling)	12 LF (Bed 2) 35 LF (Bed 9)	Good	N/A	N/A	Assumed
7th Floor, room C7-14						
Floor	12" X 12" tile (lt green w/dark green/white mottles)	44 ft ²	Good	N/A	N/A	15% Chrysotile
	Floor tile mastic	44 ft ²	Good			10% Chrysotile
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2 X 4 acoustic tile	N/A	N/A	N/A	N/A	Non-suspect
Comments: Pipes in wall between C7-14 and C7-13A – listed on C7-13A						
7th Floor, room C7-15						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
In S wall	Pipe insulation	20-30 LF	Significant damage	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, rooms C7-17 and C7-18						
Floor	12" X 12" floor tile (off-white w/ lt & dark olive mottles))	380 ft ² /each	Good	N/A	7-58	>1% Chrysotile
	Floor tile mastic	380 ft ² /each	Good	N/A	7-59	>1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-57	None detected
Univents	Transite panels	16-32 ft ² /room	N/A	N/A	N/A	Assumed
7th Floor, room C7-19						
Floor	12" X 12" floor tile(lt green w/dark green/white mottles)	340 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	340 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster and ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-57	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
7th Floor, hallway C7-16 (From C7-66 to C7-59)						
Floor	12" X 12" floor tile – (lt green w/dark green/white mottles)	528 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	528 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster and ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (white w/dot perforations & worm like markings)	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-20						
Floor	12" X 12" floor tile (off-white /tan w/brown & dark brown mottles)	176 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	176 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	7-82	N/A	None detected
Univents	Transite	16-32 ft ²	N/A	N/A	N/A	Assumed
7th Floor, electrical closet N of elevator # 4						
Pipe riser	Pipe insulation (tar over cork)	8 LF	Good	N/A	6-96	8% Chrysotile
7th Floor, room C7-21A						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
In east wall	Pipe insulation	10-20 LF	Good	N/A	N/A	Assumed
7th Floor, room C7-21						
Floor	12" X 12" floor tile (off-white w/gray & tan mottles)	313 ft ²	Good	N/A	7-58	None
	Floor tile mastic	313 ft ²	N/A	N/A	7-59	>1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/pock markings)	N/A	N/A	N/A	7-58	None detected
Above ceiling	Pipe insulation at deck penetration	One LF	Good	N/A	N/A	Assumed
Univents	Transite panels	24-48 ft ²	Good	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-22						
Floor	12"X 12" floor tile (off-white w/gray & tan mottles same as C7-21)	250 ft ²	N/A	N/A	7-58	None
	Floor tile mastic	250 ft ²	N/A	N/A	7-59	>1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile(off-white w/small pock markings)	N/A	N/A	N/A	N/A	None detected
Univents	Transite panels	32-64 ft ²	N/A	N/A	N/A	Assumed
7th Floor, hallway by main elevators C7-48A						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	1070 ft ²	N/A	N/A	Previously tested positive	>15% Chrysotile
	Floor tile mastic	1070 ft ²	N/A	N/A	Previously tested positive	>10% Chrysotile
Walls	Plaster /tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles(white w/ small dots & pinholes w/worm markings)	N/A	N/A	N/A	7-82	None detected
7th Floor, room C7-23						
Floor	12" X 12" floor tile (Same as C7-22)	136 ft ²	N/A	N/A	7-58	None
	Floor tile mastic	136 ft ²	N/A	N/A	7-59	>1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	7-95	N/A	None detected
Ceilings	2' X 4' ceiling tile	136 ft ²	N/A	N/A	7-89	None detected
Univents	Transite panels	8-16 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7TH Floor, room C7-24						
Floor	12" 12" floor tile (lt green w/dark green/white mottles)	294 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	294ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-95	None detected
Ceilings	2' X 4' ceiling tiles (small pock markings)	N/A	N/A	N/A	7-89	None detected
Univents	Transite panels	32-64 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-25						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	165 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	165 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-95	None detected
Ceilings	2' X 4' ceiling tile (small pock markings)	N/A	N/A	N/A	7-89	None detected
Univents	Transite panels	32-64 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-26						
Floor	12" x12" floor tile (lt green w/dark green/white mottles)	172 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	172 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-95	None detected



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile (small pock markings)	N/A	N/A	N/A	7-89	None detected
Univents	Transite panels	16-32 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-27						
Floor	12" X12" floor tile (lt green w/dark green/white mottles)	174 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	174 ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' X 4' ceiling tiles (small pock marking)	N/A	N/A	N/A	7-89	None detected
Univents	Transite panels	24-48 ft ²	N/A	N/A	N/A	Assumed
7th Floor, room C7-28						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
In S wall & above plaster ceiling	Pipe insulation	20-30 LF	Significant damage	N/A	N/A	Assumed
7th Floor, room C7-29						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-30						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	280 ft ²	Good	N/A	7-58	15 % Chrysotile
	Floor tile mastic	280 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	7-82	None detected
In pipe chase	Pipe insulation	27 LF	N/A	N/A	N/A	Assumed
7th Floor, room C7-31						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	138 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	138 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	7-82	None detected
In vertical pipe chase	Pipe insulation	15-30 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	8-16 N/A ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-32						
Floor	12" X 12' Floor tile (lt green w/dark green/white mottles)	320 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	320ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-95	None detected
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-33						
Floor	12" X 12" floor tile (off-white w/tan & dark tan mottles) under carpet	968 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	968 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-95	None detected
Univents	Transite panels	80-160 ft ²	Damaged	N/A	N/A	Assumed
7th floor, room C7-34						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	360 ft ²	N/A	N/A	7-58	15 % Chrysotile
	Floor tile mastic	360 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-67	None detected
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	7-82	None detected
Univents	Transite panels	32-64ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-35						
Floor	12" x12" floor tile (lt green w/dark green/white mottles)	150 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	150ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tiles	1 ½ " Pipe insulation	25-30 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	8- 16 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-35A						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Pipe - Removed	Pipe insulation (tar over cork)	3 LF	N/A	N/A	6-96	8% Chrysotile
7th Floor, room C7-36						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	400 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	400 ft ²	Good	N/A	7-59	10% Chrysotile
Ceilings	2' X 4' ceiling tile	N/A	Good	N/A	7-82	None detected
Univents	Transite panels	32-64 ft ²	Good	N/A	N/A	Assumed
7th Floor, room C7-37 includes C7-37 A,B,C,D, (suite)						
Floor	12" X 12" floor tile under carpet (lt green w/dark green/white mottles)	600 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	600 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint materials	N/A	N/A	N/A	7-67	None detected
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tile	Pipe insulation – Removed	100-150 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	200ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-38						
Floor	12' X 12" floor tile - Removed	976 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic - Removed	976 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-67	None detected
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tiles	1 1/4 – 1 1/2 Pipe insulation - Removed	~60 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	80-160 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-39						
Floor	12" X 12" floor tile under carpet (lt green w/dark green/white mottles)	390 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	390ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-67	None detected
Ceilings	2' X 4' ceiling tile	N/A	Damaged	N/A	7-82	None detected
Above ceiling tile	Pipe insulation	25-30 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	40-80 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-40						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/dot perforations & pock markings) with plaster above	432 ft ²	N/A	7-91	N/A	None detected
Shower area Above ceiling tiles & plaster	4" Pipe insulation	72 LF	Good	N/A	N/A	Assumed
7th Floor, room C7-41 – No suspect materials observed						
7th Floor, room C7-42 and C7-42A						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	180 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	180 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	N/A	7-67	None detected
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	7-82	None detected
7th Floor, room C7-43						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	132 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	132ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tile & in wall	Pipe insulation	46-60 LF	Good	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-44 and C7-44A						
Floor	12" X 12" floor tile (light gray)	216 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	216 ft ²	N/A	N/A	Previously tested positive	>1%
Walla	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tiles	Mastic dots	N/A	N/A	7-93	N/A	None detected
7th Floor, room C7-45						
Floor	12"X12" floor tile (lt green w/dark green/white mottles)	517 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	517 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling	Pipe insulation from S chase to N chase	60 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	48-96 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-46						
Floor	12' x12" floor tile (lt green w/dark green/white mottles)	192 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	192 ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' x 4' ceiling tile	N/A	N/A	N/A	7-89	None detected
Above ceiling	Pipe insulation in chase at SW corner	10-20 LF	N/A	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
In univents	Pipe insulation	8 LF	Good	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7- 46A Electric Closet						
Floor	Metal grating	N/A	N/A	N/A	N/A	Non-suspect
Walls	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal grating	N/A	N/A	N/A	N/A	Non-suspect
7th Floor, hallway by service elevator						
Floor	12" X 12" floor tile (off-white w/tan/dark tan/white mottles)	208 ft ²	N/A	7-94	N/A	None detected
	Floor tile mastic	208 ft ²	Good	N/A	N/A	Assumed
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	7-82	None detected
Comments: A sample of the floor tile mastic could not be collected within this area. Material was assumed positive. A spray-on fireproofing material was observed above the ceiling tile. This material was sampled in other areas and analysis showed no asbestos was detected.						
7th Floor, main hallway (E section)						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	1618 ft ²	good	N/A	7-58	15% Chrysotile
	Floor tile mastic	1618 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
7th Floor, vertical chase W of stair 2 – 7E030-1 on plans						
Pipe riser	Pipe insulation (tar over cork)	8 LF	Good	N/A	6-96	8% Chrysotile



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-47A						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	90-100 ft ²	N/A	N/A	N/A	Non-suspect
Above ceiling	4 LF pipe insulation on pipe above HVAC duct. Sections of insulation lying on top of duct and ceiling tiles. (aircell)	15-20 LF	Significant damage	N/A	N/A	Assumed
Comments: Debris on duct and ceiling tiles - Needs attention						
7th Floor, room C7-48						
Floor	Metal grating	N/A	N/A	N/A	N/A	Non-suspect
Walls	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Open	N/A	N/A	N/A	N/A	Non-suspect
In common space chase	Pipe insulation – mastic over cork	10 LF	Good	N/A	N/A	Assumed
7th Floor, room C7-50						
Floor	12" X 12" floor tile (brown w/white/gray/dark brown marble effect)	128 ft ²	N/A	7-86	N/A	None detected
	Floor tile mastic	128 ft ²	N/A	7-87	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-49						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	80 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	80ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling	N/A	N/A	N/A	7-82	None detected
7th Floor, room C7-51 Suite (and 51A as in prints)						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X12" floor tile (51 and 51A)	280 ft ²	N/A	7-84	N/A	None detected
	Floor tile mastic	280 ft ²	N/A	7-85	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tiles	280ft ²	N/A	N/A	7-82	None detected
Univents	Transite panels	64-128 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-52						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	90-100 ft ²	N/A	N/A	7-82	None detected
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-53						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	Non-suspect
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-54						
Floor	12" X 12" Floor tile (off-white w/gray & tan mottles)	162 ft ²	N/A	7-83	N/A	None detected
	Floor tile mastic	162ft ²	N/A	7-82	N/A	<1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7- 55						
Floor	12" X 12" floor tile (lt green w/dark green/white mottles)	60 -70 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	60 -70 ft ²	N/A	N/A	7-59	10% Chrysotile
7th Floor, room C7-56						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-57						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2 x 4 acoustic tile below plaster	N/A	N/A	N/A	N/A	Non-suspect
7th Floor, room C7-58						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2X4 ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
7th Floor, C7-61						
Floor	12" X 12" Floor tile (white w/black streaks)	112 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor tile mastic	112 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation	20 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-62						
Floor	12" X 12" floor tile (tan/off-white w/white/gray/dark tan mottles)	130 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	130 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Above ceiling tiles	Pipe insulation	11 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-63						
Floor	12" X 12" floor tile (light gray w/white & dark gray mottles)	120 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	120 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tiles (perforated w/dots & worm markings)	N/A	N/A	N/A	7-82	None detected
	Plaster deck	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-65						
Floor	12" X 12' floor tile (light green w/white & dark green mottles) under carpet	165 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	165 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-66 Nursing Care Coordinator						
Floor	12" X 12" floor tile (light gray w/white & dark Gray mottles)	120 ft ²	N/A	N/A	6-105	None detected
	Floor tile mastic	120 ft ²	N/A	N/A	6-106	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
In E wall	Pipe insulation	10-20 LF	Damaged	N/A	N/A	Assumed
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-67 (the room not hallway; it is labeled twice on the drawings)						
Floor	12" X 12" floor tile)white w/ black streaks)	150 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor tile mastic	150 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	7-82	None detected
Deck	Mastic spots	N/A	N/A	7-61	N/A	None detected



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-68A						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster, GWB, ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling & in S wall	Pipe insulation in wall only	10-20 LF	Good	N/A	N/A	Assumed
7th Floor, room C7-70						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
In W wall	Pipe insulation - Removed	N/A	Damaged	N/A	N/A	Assumed
7th Floor, behind W nurse' stations (Labeled on print as C7-66 – *2 rooms have this label)						
Floor	12' X 12" floor tile (off-white w/light green & olive green mottles)	180 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	180 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	7-57	None detected
7th Floor, vertical chase by door to stair #1 (No door label – on print as 7W036-1) **Mag Insulation debris on floor**						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
E corner riser	Pipe insulation (tar over cork)	10 LF	Good	N/A	6-96	8% Chrysotile



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

7th Floor, room C7-73 (Men's bath)						
Floor	Ceramic tile -Renovated - non-suspect	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/FRP walls	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile Plaster	N/A	N/A	N/A	7-82	None detected
In W wall	Pipe fitting insulation - Abated	2 LF	Significantly damaged	N/A	N/A	Assumed
In center wall	Pipe insulation – can't see - assume	N/A	Damaged	N/A	N/A	Assumed
Univents	Transite panels (removed from front section)	8 – 16 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-74						
Floor	12" X 12" floor tile (light green w/ white & dark green mottles)	280 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	280 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	7-57	None detected
Univents	Transite panels	36 – 72 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, room C7-75						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	760 ft ²	Good	7-58	N/A	15% Chrysotile
	Floor tile	760 ft ²	N/A	7-59	N/A	10% Chrysotile



Building 1, Floor 7 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Concrete deck	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (pinhole perforations & worm like markings Being replaced w/plaster)	N/A	Good	7-57	N/A	None detected
Univents	Transite panels	88-70 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, hallway from C7-75 to C7-70						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	200 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	200 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	Good	N/A	7-57	None detected
7th Floor, C7-60/ men's and women's staff bathrooms (C7-59 has no suspect material. Assume piping in chases.)						
Floor	Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (C7-60)	16-32 ft ²	Damaged	N/A	N/A	Assumed
7th Floor, rooms C7-72, 72A, 72B, is women's bathroom – significant damage pipe ins in W wall. All other is non-suspect						

NOTE: No suspect asbestos-containing materials were observed in rooms C7-29, C7-41 & C7-46A.

Probably suspect pipe insulation in most walls and over most plaster ceilings. Asbestos pipe insulation can be observed in C7-22 where plaster ceiling has been removed.

****DEBRIS LOCATIONS:** C7-47A; on duct and ceiling tiles
 Vertical Chase East of Stairwell #1; Mag pipe insulation on floor