



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Project: Main Building, 8th Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
8th Floor, room C8-01						
Floor	12" X 12' floor tile (white w/black streaks)	225 ft ²	Good	8-028	N/A	10% Chrysotile
	Floor tile mastic	225 ft ²	N/A	8-029	N/A	5%Chrysotile
Walls	Plaster /ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – horsehair	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12 – 24 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-01A						
Floor	12"X 12" floor tile (off-white/tan w/ brown & white mottles)	270 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	270ft ²	Good	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	48 -96 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-01B						
Floor	12" X 12" floor tile (off-white/tan w/white & brown mottles)	300 ft ²	Good	N/A	Previously tested positive	>1%



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
	Floor tile mastic	300 ft ²	Good	N/A	Previously tested positive	>1%



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	48-96 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-76 (Hall between 01A and 01B)						
Floor	12" X 12' floor tile (off-white/ tan w/brown & white mottles)	160 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	160 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster /ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm like markings)	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-02						
Floor	12" X 12" floor tile (gray w/white & dark mottles)	100 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	100 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X2' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-03 - Electrical Closet – Removed; Material is no longer there						
Pipes	Pipe insulation (black mastic over cork)	1/5 LF	Good	N/A	6-96	8% Chrysotile
8th Floor, room C8-05 (in field; the room is note labeled on drawings but it is west of room C8-04)						
In wall	Pipe insulation	12 LF	Damaged	N/A	N/A	Assumed
Univent	Transite Panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-04 – Asbestos transite panels in univents (16-32 ft²)						
8th Floor, room C8-03 - Supply Closet (as labeled in field; on drawings it is room C8-05)						
Floor	9" X 9" floor tile(brown)	45 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	45 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-08 (in field; labeled on drawings as C8-06)						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	48 – 96 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile (top of E wall) -Removed	Pipe insulation – Possibly removed/not found	20 LF-Removed	N/A	N/A	N/A	Assumed
8th Floor, room C8-07						
Floor	Terrazzo flooring	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ sheetrock /tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile/walls	Pipe insulation – Runs vertically in center wall and extends above suspended ceiling to W. Also runs over and is embedded in W wall.	50 LF	Good	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-10 (in field; labeled on drawings as C8-08)						
Floor	Rug over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	18-36 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-09						
Floor	Rug over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	8-015	N/A	None detected
Univents	Transite panels	18-36 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-11B (in field; labeled on drawings as C8-10)						
Floor	Rug over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	30-60 ft ²	Damaged	N/A	N/A	Assumed
Rooms C8-09A and 11A – No exposed suspect materials observed						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-11						
Floor	Carpet over terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-12						
Floor	12" x12" floor tile (off-white w/brown streaks)	25 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	25 ft ²	N/A	N/A	N/A	Assumed
Above ceiling tile – removed Above W wall - present	Pipe insulation – All pipe insulation can be seen above wall between C8-10 and C8-12 in W wall.	5 – 6 LF	N/A	N/A	N/A	Assumed
8th Floor, C8-13						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation	6 LF	Damaged	N/A	N/A	Assumed
In walls	Pipe insulation- can be seen behind walls through access panels.	10 LF	Good	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-15						
Floor	9" X 9" floor tile (dark brown w/white & mauve streaks)	25 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	25 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-16						
Floor	9" X 9" floor tile (gray w/ black & white streaks)	75 -100 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	75-100 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster /tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation – Removed asbestos insulation lying on tops of tiles.	2 LF Debris	N/A	N/A	N/A	Assumed
Comment: Asbestos pipe insulation debris is lying on the drop ceiling; needs immediate attention						
8th Floor, room C8-16A – Transite panels in univents (16-32 ft²)						
8th Floor, C8-18						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	N/A	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation	20-25 LF	Good	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, C8-18A						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above Ceiling	Pipe Insulation	50-60 LF	Good	N/A	N/A	Assumed
8th Floor, room C8-19 – No exposed suspect materials observed; Assume pipes from C8-18A						
8th Floor, area behind nurse' station (C8-69)						
Floor	12" X 12" floor tile (off-white w/brown mottles)	95 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	95 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation	20 LF	Good	N/A	N/A	Assumed
8th Floor, room C8-20						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Chase	Pipe insulation – No hatch	Undetermined	N/A	N/A	N/A	Assumed
8th Floor, hall by service elevator (C8-52A and C8-52B)						
Floor	12" X 12" floor tile (Same as main hall tile)	350 ft ²	Good	N/A	N/A	Chrysotile 10%
	Floor Tile Mastic	350 ft ²	Good	N/A	N/A	Chrysotile 10%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Spray-on fireproofing	200-500 ft ²	N/A	8-035	N/A	None detected
8th Floor, room C8-21						
Floor	12" X12" floor tile (white w/brown streaks)	380 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	380 ft ²	N/A	N/A	Previously tested positive	>1%
Walls/ceilings	Plaster/2' x 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, rooms C8-23						
Floor	12" X 12" floor tile (white w/brown streaks)	380 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	380 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-22						
Floor	12" X 12" floor tile (white w/ light gray & dark gray mottles)	380 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	380 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 -64 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-24						
Floor	12" X 12" floor tile(tan w/white & brown mottles)	376 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	376 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-25						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	120 ft ²	Good	N/A	8-031	None detected
	Floor tile	120 ft ²	N/A	N/A	8-032	5% Chrysotile
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, rooms C8-27, C8-26 and C8-28						
Floor	12" X 12" floor tile (white w/brown streaks)	190 ft ² /area	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	190 ft ² /area	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ² /area	Damaged	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-29						
Floor	12" X 12' floor tile (light green w/white & dark green mottles) under carpet	120 ft ²	N/A	N/A	8-017	10% Chrysotile
	Floor tile mastic	120 ft ²	N/A	N/A	8-018	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 ft ²	N/A	N/A	N/A	Assumed
8th Floor, room C8-30						
Floor	12" X 12" floor tile (same as hall & 50 & 51)	500 ft ²	N/A	N/A	8-017	10% Chrysotile
	Floor tile mastic	500 ft ²	N/A	N/A	8-018	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	36 -72 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-32 – No suspect materials						
8th Floor, room C8-33						
Floor	9" X 9" floor tile (gray w/white & black marks)	80 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	80ft ²	Good	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation – runs over wall and into wall between C8-32 and C8-33	12 LF	Damaged	N/A	N/A	Assumed
8th Floor, room C8-34 – Asbestos insulation can be see running over ceiling from C8-35. ~ 20 LF - Good						
8th Floor, room C8-35						
Floor	12" X 12" floor tile (white w/black streaks)	135 ft ²	N/A	N/A	8-028	10% Chrysotile
	Floor tile mastic	135 ft ²	N/A	N/A	8-029	5% Chrysotile
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-36						
Floor	12" X 12" floor tile (off-white w/light & dark olive mottles)	140 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	140 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation	16 linear feet	Good	N/A	N/A	Assumed
8th Floor, room C8-36A						
Floor	Concrete	30 SF	N/A	N/A	N/A	Non-suspect
Walls	Plaster	120 SF	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	30 SF	N/A	N/A	N/A	Non-suspect
Comment: 3 or more asbestos-insulated pipes in N wall. 65 LF, severely damaged pipe insulation and asbestos debris on junction box above drop ceiling; needs immediate attention						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-37A						
Floor Tile	12" X 12" floor tile (white w/ light tan mottles)	125 ft ²	N/A	8-036	N/A	None- detected
	Floor tile mastic	125 ft ²	N/A	8-037	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-37						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile mastic	604 ft ²	N/A	8-029	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
	Plaster /concrete - Removed	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	150 -300 ft ²	Damaged	N/A	N/A	Assumed
Above plaster ceiling	Pipe insulation - Removed	-	Removed	N/A	N/A	Assumed
8th Floor, room C8-38 (Gym/Recreation Center) and adjoining bathroom C8-38A						
Ceilings	Plaster above 2x4 Ceiling Tiles	900 ft ²	Good	N/A	N/A	Non-suspect
Floor	Ceramic	900 ft ²	Good	N/A	N/A	Non-suspect
Univents	Transite panels	64-128 ft ²	Damaged	N/A	N/A	Assumed
Comment: Damaged pipe insulation can be seen above the bathrooms plaster ceiling from above the ceiling tiles in C8-36A. Assume pipe insulation above the plaster ceiling also in C8-38						
8th Floor, room C8-39 (small corridor) – No exposed suspect materials observed						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-40						
Floor	12" X 12" floor tile (white w/light tan & brown mottles)	228 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	228 ft ²	Good	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	28 – 56 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-42 (electrical closet)						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal	N/A	N/A	N/A	N/A	Non-suspect
Pipe	Pipe insulation (black mastic over cork) - Removed	42 LF	Damaged	N/A	6-96	8% Chrysotile
8th Floor, room C8-43 (employee/staff lounge)						
Floor	12' X 12" floor tile (off-white w/ light & dark brown mottles)	860 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	860 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster /ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	No-suspect
Univents	Transite panels	200-400 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-43A – Severely damaged pipe insulation inside N wall. ~3LF plus 1ft² of debris in wall						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, vertical chase west of door to stairwell #2						
Pipe riser	Pipe insulation (black mastic over cork)	8 LF	Good	N/A	6-96	8% Chrysotile
Comment: Has ACM debris (mag) on duct inside chase; cannot tell where insulation came from but needs immediate attention						
8th Floor, room C8-45						
Floor	12" X 12" floor tile (tan w/white & dark brown mottles)	140 ft ²	N/A	8-029	N/A	None detected
	Floor tile mastic	140 ft ²	N/A	8-040	N/A	2% Chrysotile
Walls	Plaster/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-46 and C8-47 (in field; mislabeled C8-36A on drawings, west of C8-45)						
Floor	Ceramic tile / concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – Runs in vertical chase between C8-46 and C8-45. Also, piece of asbestos insulation laying on top of wall.	N/A	Damaged	N/A	N/A	Assumed
8th Floor, room C8-48 (in field; labeled on drawings as C8-46)						
Floor	12" X 12" floor tile (white w/brown streaks)	185 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	185 ft ²	Good	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-49						
Floor	12" X 12" floor tile (white w/brown streaks)	150 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	150 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-50						
Floor	12" x 12" floor tile (same as hall tile)	290 ft ²	Good	N/A	8-017	10% Chrysotile
	Floor tile mastic	290 ft ²	Good	N/A	8-018	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm marking)	N/A	N/A	N/A	N/A	Non-suspect
	Plaster/concrete	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, room C8-51						
Floor	12" X 12" floor tile (same as hall & C8-50)	510 ft ²	Good	N/A	8-017	10% Chrysotile
	Floor tile mastic	510 ft ²	Good	N/A	8-018	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile(worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	48-96 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-51A – No exposed suspect materials observed.						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-52						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, vertical chase C8-54A Electrical (By Elevator #4) (Insulation is in C8-55 on drawings)						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	V	Non-suspect
Ceilings	Metal	N/A	N/A	N/A	N/A	Non-suspect
Pipe riser	Pipe insulation	10 LF	Good	N/A	N/A	Assumed
8th Floor, rooms C8-54A & C8-54B						
Floor	Concrete – C8-54A	N/A	N/A	N/A	N/A	Non-suspect
	C8-54B -9X9 floor tile (gray w/black& white	~54ft ²	Good	N/A	N/A	Assumed
Walls	Plaster/sheetrock/cinderblock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Valve	Insulation (black mastic)	2 ft ²	Good	8-030	N/A	None detected
Comments: C8-54A has mud insulation inside of steel pipe sleeves at floor (SE Corner)						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C-56						
Floor	12" X 12" floor tile (tan w/white % gray mottles)	150 ft ²	N/A	8-033	N/A	None detected
	Floor tile mastic	150 ft ²	N/A	0-834	N/A	<1% Chrysotile
Walls`	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-58 and C8-57						
Floor	Rug over 9" X 9" floor tile (dark red/brown)	182 ft ² / Room	N/A	N/A	N/A	Assumed
	Floor tile mastic	182 ft ² / Room	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panles	48 – 96 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, rooms C8-59						
Floor	12" X 12" floor tile (light green w/white & dark green mottles)	225 ft ²	N/A	8-031	N/A	None detected
	Floor tile mastic	225 ft ²	N/A	8-032	N/A	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster – no access above, but heater in ceiling – may be asbestos pipe insulation in area	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	30-60 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-59A – Transite panels in univents (12-24 ft²)						
8th Floor, room C8-60						
Floor	Rug over ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 2' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univent	Transite panel	16-32 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-61						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
8th Floor, main hall & hall by main elevators						
Floor	12" X 12' floor tile (off-white/light green w/dark green mottles)	3000 ft ²	Good	N/A	8-017	10% Chrysotile
	Floor tile mastic	3000 ft ²	N/A	N/A	8-018	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Comment: Vibration cloths for air units in ceiling/ducts.						
8th Floor, room C8-64A – No suspect materials observed						



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, rooms C8-64 and C8-63						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ² /area	Damaged	N/A	N/A	Assumed
Above ceiling tile & in chase	Pipe insulation	15 - 20 LF	Damaged	N/A	N/A	Assumed
8th Floor, room C8-65						
Floor	12" X 12" floor tile (off-white w/brown mottles)	192 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	192 ft ²	Good	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, room C8-66						
Floor	12' X 12" floor tile	192 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	192 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
	Partial plaster ceiling w/old 1'X1' glue puck	8 ft ²	Damaged	8-0258	N/A	None Detected
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation	32 LF	Good	N/A	N/A	Assumed
8th Floor, room C8-67						
Floor	12" x 12" floor tile (off-white w/ light & dark olive mottles)	192 ft ²	Good	N/A	Previously tested positive	>1%
	Floor tile mastic	192 ft ²	N/A	N/A	Previously tested positive	>1%
Univents	Transite panels	12 – 24 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Mastic spots	N/A	N/A	8-0258	N/A	None detected
Above e wall	Pipe insulation	>20 LF	Good	N/A	N/A	Assumed
8th Floor, room C-68						
Floor	12" X 12" floor tile (white w/ black streaks)	192 ft ²	Good	N/A	8-028	10% Chrysotile
	Floor tile mastic	192 ft ²	N/A	N/A	8-029	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, room C8-70						
8th Floor, room C8-71 & electrical closet (sealed up)						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
It is probable that asbestos pipe insulation runs vertically in wall – tops of risers have been removed and encapsulated						
8th Floor, vertical chase across from room C8-71 and east of Stairwell #1						
Pipe	Pipe insulation (black mastic over cork)	8 LF	Good	N/A	6-96	8% Chrysotile
On floor	Pipe insulation debris	NA	Significant Damage	N/A	N/A	Assumed
Comment: Debris on floor all over – MAG ACM insulation; needs immediate attention						
8th Floor, room C8-78 Laundry Facilities						
Floor	Composite	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
In W wall	Pipe insulation	20-30 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor 8 - Specific Survey Findings
Project No. VAMC:10013.00-IN

8th Floor, hall in sleep lab area (C8-75 on Drawings)						
Floor	Rug over 12 x 12" floor tile (off-white)	375 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster / ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
8th Floor, C8-78 Patient Restroom						
Floor	Composite	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	18 – 36 ft ²	N/A	N/A	N/A	Assumed
Chase & over wall	Pipe insulation	25 LF	N/A	N/A	N/A	Assumed
N wall, above ceiling	Tar coat on fascia	20 – 30 ft ²	Good	8-016	N/A	5% Chrysotile