



1511 Route 22, Suite C24, Brewster, NY 10509  
Phone: 845.278.7710 Fax: 845.278.7750

**Building 1, Floor 9 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

**Project:** Main Building, 9<sup>th</sup> Floor  
VA Medical Center  
Wilkes-Barre, PA

**Inspector(s):** James Reber  
Thomas Ferro  
**Date(s):** 2/2010-3/2010

**NOTE:**

The ninth floor was recently renovated. Rooms in which no suspect materials were observed may not be listed.

Despite recent renovations, suspect pipe and/or duct insulation is known to be present in chases, behind walls, and above ceilings in some areas and is likely to be present in others.

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
<b>9<sup>th</sup> Floor, room C9-34</b>						
Vertical chase	Pipe insulation -removed	1 LF	N/A	N/A	N/A	
<b>9<sup>th</sup> Floor, room C9-39</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4-8 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>9<sup>th</sup> Floor, rooms C9-40 and C9-41</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>

**VA Medical Center, Building No. 1, 9<sup>th</sup> Floor**

Adelaide Environmental Health Services, Inc. – Project No. VAMC:10013.00-IN



**Building 1, Floor 9 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

<b>9<sup>th</sup> Floor, rooms C9-65, C9-64, C9-66, C9-63, C9-62 and C9-01</b>						
Floor	12' X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Deck (extends into)	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>9<sup>th</sup> Floor, room C9-27 (storage room with vertical chase)</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Pipe fittings	Tar over cork	2 LF	N/A	N/A	6-96	<b>8% Chrysotile</b>
Pipes	Tar over cork	12-15 LF	N/A	N/A	6-96	<b>8% Chrysotile</b>
<b>9<sup>th</sup> Floor, rooms C9-28, C9-29, C9-25, C9-31, C9-32, C9-64, C9-63, C9-62, C9-61, C9-60, C9-52, C9-51, C9-50, C9-49, C9-48, C9-47, C9-46</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X2' ceiling tile/plaster/concrete deck	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 9 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

<b>9<sup>th</sup> Floor, rooms C9-24, C9-22, C9-21, C9-19, C9-18, C9-17, nurses' station, C9-15, C9-14, C9-12, C9-11, C9-10, C9-9, C9-8, C9-7, C9-5, C9-4, C9-1 and C9-66</b>						
Floor	Rug	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Deck	Plaster	N/A	N/A	9-09 9-010	N/A	None detected
<b>9<sup>th</sup> Floor, hall by service elevator</b>						
Floor	12' X 12" floor tile (off-white w/ lt. green mottles) - removed					N/A
	Floor tile mastic - removed					N/A
Walls	Sheetrock joint material	N/A	N/A	9-013	N/A	None detected
Ceilings	2' X 4' ceiling tile	N/A	N/A	9-014	N/A	None detected
	Metal Deck	N/A	N/A	N/A	N/A	Non-suspect
	Spray on fireproofing	200-220 ft <sup>2</sup>	Damaged	9-012	N/A	None detected
<b>9<sup>th</sup> Floor, room C9-44</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 9 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

<b>9<sup>th</sup> Floor, room C9-45 (mechanical)</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
On floor	Pipe insulation (debris) –Gone					N/A
<b>9<sup>th</sup> Floor, electrical rooms (C9-26, C9-34, C9-37, C9-03, C9- 60A)</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Pipes(C9-26) removed	Pipe insulation (tar over cork)					N/A
Pipes (C9-26) - removed	Pipe / fitting insulation (tar over cork)					N/A
Vertical chase (C9-03)	Pipe insulation (tar over cork). Also damaged cementitious insulation in chase.	4 LF	Damaged	N/A	6-96	<b>8% Chrysotile</b>
Pipes (C9-37)	Pipe insulation (tar over cork)	N/A	N/A	N/A	6-96	<b>8% Chrysotile</b>
<b>9<sup>th</sup> Floor, electrical rooms (C9-43A) – Pipe insulation in toilet wall chases and ceiling. Also above C9-43</b>						