



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Project: Main Building, 11th Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
11th Floor, room C11-4 Electric Room						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Above plaster ceiling	Pipe insulation at chase at SE corner	3 LF above ceiling and more in chase	Good	N/A	N/A	Assumed
11th Floor, room C11-05						
Floor	12" X 12" Floor tile	213 ft ²	N/A	N/A	N/A	Same as closet
Walls	Plaster	213ft ²	N/A	N/A	N/A	Suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (bathroom also)	24-40 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-5 Closet						
Floor	12" X 12' Floor tile	10 ft ²	Good	N/A	N/A	Suspect
	Floor tile mastic	10 ft ²	N/A	N/A	N/A	Suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, room C11-9 (not labeled on prints)						
Floor	Rug over 9x9 floor tile and mastic	120 ft ²	N/A	N/A	N/A	Assumed
Walls	Wood panel over plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile, plaster above	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4 - 8 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-13						
Floor	Rug over 12" X 12' floor tile over 9x9 tile	>240 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (bathroom also)	12 – 24 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-13 Closets (2)						
Floor	12' X 12" floor tile over 9X9 tile	30 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
11th Floor, room C11-21						
Floor	Rug over ceramic floor tile	70 ft ²	Good	N/A	N/A	Non-suspect
Walls	Plaster/ tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/dot perforations & worm markings)	36 ft ²	Good	11-75	N/A	None detected



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, room C11-19						
Floor	Carpet	1100 ft ²	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	11-75	None detected
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	24-48 ft ²	Significant damage	N/A	N/A	Assumed
Comment: Univent – piece of panel broken and resting inside left end.						
11th Floor, rooms C11-17 and C11-16						
Floor	Carpet over wood (w/black mastic)	700 ft ²	N/A	N/A	N/A	Mastic Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	11-75	None detected
Univents	Transite panels (bathroom also in C11-17)	48 -96 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, hall by service elevator						
Floor	12" X12" floor tile/mastic	300 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Brick / tile/ plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Spray-on fireproofing	N/A	N/A	N/A	8-035	None detected



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, main hall, E end						
Floor	12' X 12" floor tile	1000 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	1000 ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	128 - 252 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-15						
Floor	Rug over 12 X 12 floor tile (Same tile as in corridor)	150 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster /Sheetrock/ joint compound	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univent	Transite panels	24 – 48 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-14						
Floor	Rug over 12X12 floor tile (Same tile as in corridor)	135 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster /sheetrock /joint compound	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile (dot perforations w/small worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, bathroom next to C11-14 (C11-14A) (Now C11-13A on door and 14A on prints)						
Floor	12" X 12" floor tile	60 ft ²	N/A	01-C11	N/A	None detected
	Floor tile mastic	60 ft ²	Good	02-C11	N/A	5% Chrysotile
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12 – 24 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-14A						
Floor	Rug over 12 X 12 tile (Same tile as in corridor)	216 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-22						
Floor	Rug over beige self stick linoleum tile over wood	200-250 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (bathroom also)	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, room C11-23						
Floor	Rug over Green 9 x 9 tile on wood	200-250 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-24						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile and Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
11th Floor, room C11-25						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation - only 5 LF above plaster, maybe more in walls	12 LF	N/A	N/A	N/A	Assumed
11th Floor, room C11-29						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2 X 4 tile Plaster above	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4 – 8 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, room C11-31 Electric Room						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
In Floor	Pipe insulation(inside steel sleeve in concrete)	1 LF	Significant damage	N/A	N/A	Assumed
11th Floor, room C11-33						
Floor	12 X 12 floor tile /mastic (Same tile as in corridor)	50 ft ²	N/A	N/A	N/A	Assumed
Walls	Tile and Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16 – 32 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, electrical room just N of elevator (Not labeled on door but is C11-31 on prints? C11-31 is mismarked on prints)						
Floor	Metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal	N/A	N/A	N/A	N/A	Non-suspect
Pipe	Cork / tar	18 LF	Good	N/A	9-96	8% Chrysotile



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, Chief Executive Office suite by main elevator (C11-34, C11-22A and C11-30A)						
Floor	Rug over concrete (C11-34) (C11-30A)	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile (C11-22A) under rug	N/A	N/A	N/A	N/A	Assumed
Walls	Plaster/ sheetrock/ joint compound	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	72 -144 ft ²	Damaged	N/A	N/A	Assumed
Univents C11-34	Pipe insulation	2 LF	Good	N/A	N/A	Assumed
11th Floor, room C11-32						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ dot perforations & crate-like worm markings)	24 ft ²	Good	11-77	N/A	None detected
Univents	Transite panels	16 – 32 ft ²	Damaged	N/A	N/A	Assumed
Riser	Pipe insulation – exposed and then goes into plaster ceiling and runs E for about 10 LF	18+ LF	Significantly damaged	N/A	N/A	Assumed
11th Floor, hall by main elevator						
Floor	12" X 12' floor tile (olive mottles)	700 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	700 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Tile /plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Pipe	Cork	40 LF	N/A	N/A	N/A	Chrysotile 8%



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, main hall from rooms C11-14 through 16						
Floor	12" X 12" floor tile/mastic (olive mottles)	500 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Tile / plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation (cork & tar)	50 LF	Good	N/A	N/A	Assumed
11th Floor, rooms C11-11 and C11-10						
Floor	Carpet over leveling compound over wood	730 ft ²	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (in bathroom also)	24-48 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-8						
Floor	Carpet over wood w/ suspect mastic from old tiles on wood	N/A	N/A	N/A	N/A	Assumed
Walls	Paneling over sheetrock / joint compound	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/dots & crater-like worm markings)	608 ft ²	N/A	11-81	N/A	None detected
Univents	Transite panels	32- 64 ft ²	Damaged	N/A	N/A	Assumed
11th Floor, room C11-6						
Floor	Carpet over wood w/suspect mastic from old floor tiles on wood	274 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (bathroom also)	24 - 40 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 11 - Specific Survey Findings
Project No. VAMC:10013.00-IN

11th Floor, main hall, W end						
Floor	12" X 12" floor tile (olive mottles)	1037 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	1037 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	360 -640 ft ²	Damaged	N/A	N/A	Assumed

NOTE:

Chase may contain asbestos-containing material.

The following areas were inspected but no suspect asbestos-containing materials were observed.

- Janitors closet
- Room C11-7