



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 1, Floor 12 - Specific Survey Findings
Project No. VAMC:10013.00-IN

Project: Main Building, 12th Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
12th Floor, room below mechanical room for elevators 7 & 8						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal Deck	N/A	N/A	N/A	N/A	Non-suspect
	Spray-on fireproofing	750 -900 ft ²	Damaged	12.5 -04	N/A	None detected
12th Floor, machine room (12C-001)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ducts	Vibration dampers	19	Good	N/A	N/A	Assumed
Pipe fitting	Tar cover (over cork)	10-12 LF	Damaged	N/A	6-96	8% Chrysotile
Pipe insulation	Tar cover (over cork)	20-25 LF	Damaged	N/A	6-96	8% Chrysotile
Vertical chase	Pipe fitting insulation	5+ LF	Significant damage	N/A	N/A	Assumed
Vertical chase	Aircell pipe insulation	Undetermined	Damaged	N/A	N/A	Assumed



Building 1, Floor 12 - Specific Survey Findings
Project No. VAMC:10013.00-IN

12th floor, mechanical room (12C-002)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Comments: Non-asbestos containing pipe insulation was observed within this area						
12th Floor, room 12E001-1 (E mechanical room) and SP12E002-1 (machine room)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU /brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Duct work	Vibration dampers	10	N/A	N/A	N/A	Assumed
SW corner of machine room (in wall)	Pipe insulation	<1ft	Damaged	N/A	N/A	Assumed
12th Floor, room 12W001-1						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU /brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ducts	Vibration dampers	10	N/A	N/A	N/A	Assumed
Under floor – NE corner by door	Pipe insulation (pre-formed	Undetermined	N/A	N/A	N/A	Assumed