



Building 1, Floor 13 and Stairwells - Specific Survey Findings
Project No. VAMC:10013.00-IN

1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Project: Main Building, 13th Floor and all Stairwells
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 20102/2010-

3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
Mechanical room						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ducts	Vibration dampers	2	N/A	N/A	N/A	Assumed
Pipe fitting insulation	Plaster ("T")	1ft ²	Damaged	13-01	N/A	None detected
Elevator equipment	Pads / brake shoes	8-10 ft ²	Good	N/A	N/A	Assumed
Comments: Inspector was not able to sample the suspect elevator equipment. Non-asbestos-containing pipe insulation materials are located within this area.						
Bio-med						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	CMU /sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Ceiling panels /concrete	N/A	N/A	N/A	N/A	Non-suspect
Pipe	Pre-formed insulation – Goes into chase in SE corner – seems to run South	?	Significantly damaged material on floor	N/A	N/A	Assumed



Building 1, Floor 13 and Stairwells - Specific Survey Findings Project No. VAMC:10013.00-IN

Stairwell #3						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Rubber	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8 - 16 ft ² (per floor from 2nd through 12th	N/A	N/A	N/A	Assumed
Comments: Univent on 1 st floor has no front panels, possibly present in rear and if so 16ft.						
Stairwell #2						
Floor	Concrete /rubber	N/A	N/A	N/A	N/A	Non-suspect
	12 X 12" floor tiles (black w/streaks) and mastic and treads for B & 1 st Floor	200 ft ²	N/A	N/A	N/A	Assumed
Univents	Transite panels	192 – 256 ft ²	N/A	N/A	N/A	Assumed
Comments: Possible transite panels in univents. Floor tile in basement threshold new – tan mottles.						
Stairwell #1						
Floor	Concrete (rubber steps)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 – 48 ft ²	N/A	N/A	N/A	Assumed
Comments: 8 th floor possible transite panels in univents at rear – 24-32 ft ² . The 11 th floor has univent over steps – 8-6 ft ²						
Stairwell #4						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	64-96 ft ²	N/A	N/A	N/A	Assumed