



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 12, Specific Survey Findings
Project No. 05-033-01

Project: **Building No. 12**
VA Medical Center
1111 East End Blvd.
Wilkes-Barre, PA

Inspector(s): James Reber

Date(s): Thomas Ferro
2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
Level B, throughout warehouse storage area						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal	N/A	N/A	N/A	N/A	Non-suspect
Comments: No suspect asbestos-containing materials were observed in this area.						
Level B, engineering shop section (all areas)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-Suspect
	9"X9" Floor tile (dark brown), men's locker room (G-3)	120 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic, men's locker room (G-3)	120 ft ²	N/A	N/A	N/A	Assumed
	12" X12" Floor tile (light green w/white & dark green mottles) (G-7)	200 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic (G-7)	200 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Block/concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tiles (in G-7)	200 ft ²	N/A	N/A	N/A	Non-suspect
Note: Piping in walls of toilets/showers may contain asbestos insulation						



Building 12, Specific Survey Findings
Project No. 05-033-01

Level B, electric shop						
Floor	12" X 12" Floor tile (off-white w/tan /gray mottles)	720 ft ²	N/A	N/A	10-44	None detected
	Floor tile mastic	720 ft ²	N/A	N/A	N/A	Assumed
Walls	Block	N/A	N/A	N/A	N/A	Non-Suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-Suspect