

Statement of Work

Primary and Specialty Medicine Service Line Replace and Install Patient Recliners

I. Purpose of Project: Replace Patient Recliners in VA Medical Center Omaha and Grand Island.

II. Statement of Work

a. Description of Work: Contractor must provide a recliner meeting the below specifications and quantities specified below. Contract includes installation in patient rooms.

b. Quantities Required/Shipment Information/Installation

1. 87 recliners are required for Omaha V.A. Medical Center, delivered to 4101 Woolworth, Omaha, NE 68105, dock. Receiving and unpackaged and delivered to rooms as provided by VA after award of contract.
2. 15 recliners are required for Grand Island V.A. Medical Center, delivered to 2201 No. Broadway Avenue, Grand Island, NE 68803-2196 , dock and shall be unpackaged and delivered to locations provided by VA after award of contract.
3. Packaging materials shall be disposed of by installer in government furnished containers.

c. Salient Characteristics:

1. Recliners shall be contemporary in appearance to either Steelcase Empath, Wieland Accord or Nemschoff Ava or equal.
2. Recliners shall be upholstered in COM.
 - a. Eight Seven (87) Omaha recliners shall be upholstered in Mayer, Dande, DN014, Color Aqua or Coral, Velocity, Color Bermuda or equal.
 - b. Fifteen (15) Grand Island recliners shall be upholstered in Trove, 3839-401, Color Patina or equal.
3. A removable headrest will not be required but if standard with product will be acceptable.
4. Open arms are acceptable.
5. Ava recliner shall be quoted with both straight back (Arcade) and Wingback options.
6. Finish selections shall be as selected by Technical Representative at time of award.
7. All upholstery and exposed surfaces shall be approved for use of cleaner 3M™ HB Quat Disinfectant Cleaner Concentrate 25H/L.
8. The recliner seat shall contain a moisture barrier.
9. Added antimicrobial treatments on seating is advantageous. Include complete specification information regarding treatment available.

10. Arm caps/arm rests shall be molded urethane and must be replaceable.
11. Recliner shall include transfer arm (flip up or flip down arms) on both left and right sides.
12. Chairs must have a static load of 500 lbs.
13. Chair must contain central locking brake and steer with locking pedals on both sides of the chair at the front for easy/safe access and system shall allow for a zero turning radius.
14. Backrest and footrest adjustment controls shall allow easy access to both user and caregiver.
15. Backrest and footrest adjustments must be independent of one another and shall have infinite recline stops from upright to full recline.
16. Recliner shall include a push bar for easier movement and directional steering.
17. The back includes infinite back recline stops from upright to recline position.
18. Recliner must be able to lay flat.
19. Seat cushion and back are upholstered with no piping or welts at seams to collect contaminants.
20. Seams on back and seat are located away from wear points to extend the life of upholstery. Recliner shall include bumpers along the bottom edge to prevent damage to recliner when collisions with walls and equipment occur.
21. Seat and back cushions must be attached. Cushions must be able to be easily removed with simple tool for cleaning or replacement.
22. Frame shall be constructed of steel and components shall be attached with metal to metal connections.
23. Pedals and levers shall be tucked in to prevent damage to or from them or prevent from items getting caught in them and the clearance under recliner and the pedal locations shall allow for existing overbed tables (Hill Rom, Model Art of Care with Tuning Fork Base) to slide behind the front wheels of the recliner so that patient can eat comfortably.
24. Seat design shall include gap between seat and back (crumb sweep gap).
25. Recliner shall include a push bar on back of chair for ease of mobility.
26. Due to the size of patient rooms, the overall dimensions shall not exceed 31 5/8" W, 35 D, 46 3/4" H.
27. Seat Width shall be a minimum of 23". Seat depth shall not exceed 22". Seat Height shall be 20" H (In Upright Position).
28. Arm height shall be between 24 3/4" and 26 1/2" H.
29. Warranty shall be lifetime for defects in materials and workmanship (including shipping, parts, and labor for the repair or replacement of item) with exception of 10 year warranty on foam, casters, upper arms, accessories, and recliner components other than the internal structure and a five year warranty for the central brake system, directional steering including levers and pedals and Trendelenburg.
30. Recliner must meet or exceed ANSI/BIFMA X5.4 Lounge Seating testing to ensure structural quality.
31. Written documentation and all necessary literature must be provided to demonstrate that the salient characteristics listed above have been

met or not by the product specified. Those items which have not met the salient characteristics specified shall be noted as such.

d. Contractor Qualifications:

- 1.** Vendor must supply an electronic service manual.