

FIXTURE SCHEDULE					REMARKS (SEE NOTE)
ITEM	DESCRIPTION	CW	HW	WASTE	VENT
P-101	WATER CLOSET	1"	—	3"	2"
WHITE, WALL MOUNT, ELONGATED, 1.28 GPF, TOP SPUD WITH EXPOSED INFRARED FLUSH VALVE, WALL CARRIER AND ELONGATED OPEN FRONT SEAT.					
P-401	LAVATORY, WALL MOUNTED SLAB TYPE	3/8"	3/8"	1 1/2"	1 1/2"
WALL MOUNTED, SLAB TYPE, VITREOUS CHINA, ELECTRONIC FAUCET					
P-501	MOP SINK	1"	1"	3"	1 1/2"
TERRAZZO MOP SERVICE SINK FITTING WITH VACUUM BREAKER, ADJUSTABLE TOP BRACE, 3/4" HOSE THREAD ON SPOUT W/ BUCKET HOOK, INLETS, 8" O.C., CHROME FINISH					
P-508	SINK, CRS	3/8"	3/8"	1 1/2"	1 1/2"
WRST BLADE HANDLES					
P-508A	SINK, CRS W/ GARBAGE DISP.	3/8"	3/8"	1 1/2"	1 1/2"
SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH SWIRLING GOOSENECK FAUCET W/ 4" WRST BLADE HANDLES WITH GARBAGE DISPOSAL					
P-604	ELECTRIC WATER COOLER	3/8"	—	1 1/2"	1 1/2"
BI-LEVEL HEAVY DUTY 14 GAUGE DRINKING FOUNTAIN, WALL MOUNT, FULLY EXPOSED, BARRIER-FREE ACCESS MODEL (OR APPROVED EQUAL)					
P-701	SHOWER	1/2"	1/2"	2"	2"
SHOWER VALVE AND TRIM WITH 1.5 GPM ROUGH VALVE WITH INTEGRAL STOPS AND TRIM KIT WITH 1.5 GPM HANDSHOWER					
P-801	HOSE BIB	3/4"	—	—	—
STANDARD BRASS, 3/4" WHI, FROSTPROOF WITH VACUUM BREAKER BACKFLOW PREVENTOR					
P-900	ICE MAKER	1/2"	—	—	—
SIOUX CHIEF 696-1000WF OX BOX ICE MAKER OUTLET BOX					
FD	FLOOR DRAIN	—	—	3"	—
SIOUX CHIEF 832-36PFR "FINISH LINE" ADJUSTABLE FLOOR DRAIN W/TRAP PRIMER CONNECTION W/ 45 GPM 4" DEEP SEAL TRAP AND AUTOMATIC TRAP FINING VALVE					
HD	HUB DRAIN	—	—	3"	—
SIOUX CHIEF 832-36PFR/832-4HHD "FINISH LINE" ADJUSTABLE HUB DRAIN					

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION, PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

SOLAR WATER HEATER SCHEDULE							
MARK	STORAGE GALLONS	BACK-UP ELECTRICAL ELEMENTS			RECOVERY @ 70° F RISE	BASIS OF DESIGN	NOTES
		NO.	KW EA.	V			
EW-1	119	1	4.5	240		SUPERSTOR MODEL SSU-119SE	1 REQUIRED

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION, PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

SOLAR PANELS					
DESCRIPTION	QTY.	TRANSPARENT AREA EA.	WORKING PRESSURE	FLOW RATE	BASIS OF DESIGN
SOLAR PANEL COLLECTOR	2	39.7 SF	165 PSI	0.5-1.8 GPM (RECOMMENDED)	SOLAR SPECTRUM MODEL PP-40SC

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION, PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

DRAIN-BACK TANK SCHEDULE					
MARK	DESCRIPTION	QTY.	CAPACITY	BASIS OF DESIGN	NOTES
DB-1	DRAIN-BACK TANK	1	15 GALLON	HPF MODEL NO. SSU-15DB	

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION, PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.



RECIRCULATION PUMP SCHEDULE						
MARK	SERVICE	GPM	ELECTRICAL	HP	BASIS OF DESIGN	REMARKS
RP-1	HOT WATER RECIRCULATION	7	115V, 60Hz, 1 PH	1/40	TACO MODEL 003-ST4	

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION, PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

FINAL SUBMISSION  
APRIL 6, 2012

P011

IF SHEET IS LESS THAN (30"x42") IT IS  
A REDUCED PRINT; SCALE ACCORDINGLY

				NATURAL RESOURCES & ENVIRONMENTAL AFFAIRS		P.W. DWG. NO.		DEPARTMENT OF THE NAVY NAVAL SUPPORT ACTIVITY PANAMA CITY, FLORIDA	
DESIGN/BUILD 286 MOORE ST. PANAMA, FL 32402 251-980-5778		ARCH. & ENGR. SEAL		SAFETY DEPARTMENT		DRAWN BY JLL		PANAMA CITY JOINT OUTPATIENT CLINIC	
				FIRE DEPARTMENT		CHECKED BY WMB		NAVAL GULF COAST HEALTH CARE	
				PUBLIC WORKS SUPERVISOR		SUPERVISOR WMB		PLUMBING SCHEDULES	
						DATE		N.A.V.F.A.C. DRAWING NO.	
						APPROVED		N/A	
				PUBLIC WORKS OFFICE		SCALE NONE		CONSTR. CONTR. NO.	
						IMCC.		T.O.#	
								SHEET 2 OF 8	