

DEMOLITION KEY:

- 1 DEMO & DISPOSE OF GLASS VESTIBULE
- 2 REMOVE PATIO OVERHEAD ENCLOSURE & STRUCTURAL ELEMENTS & PROVIDE FOR TEMPORARY COVERED AWNING. VA TO PROVIDE SPECIFICATIONS ON AWNING UPON CONSTRUCTION.
- 3 DEMO & DISPOSE OF EXTERIOR ENTRYWAY, DOOR & DOOR FRAMES; ABATE AS NEEDED & APPROVED
- 4 DEMO & DISPOSE OF MILLWORK, GLASS PARTITION & WALL
- 5 REMOVE EXISTING VCT/CARPET; LEVEL & PREP FOR NEW FLOORING
- 6 REMOVE & DISPOSE OF INTERIOR DOOR & DOOR FRAME
- 7 DEMO EXISTING BATHROOMS INCLUDING FIXTURES & FLOORING; ABATE AS NEEDED & APPROVED; REMOVE PIPING TO THE SOURCE & DO NOT CAP OFF
- 8 DEMO & DISPOSE OF PARTITION WALL
- 9 DEMO & DISPOSE OF WINDOW; PARTIAL DEMO OF EXTERIOR WALL PREP FOR NEW EXTERIOR DOORWAY; PROVIDE TEMPORARY SHORING AS NEEDED; ABATE AS NEEDED & APPROVED
- 10 DEMO EXISTING MED ROOM INCLUDING FIXTURES, MILLWORK, CEILING & FLOORING; ABATE AS NEEDED & APPROVED
- 11 DEMO EXISTING PARTITION WALL
- 12 REMOVE FIRE DOOR & FRAME; SALVAGE FOR USE IN NEW CORRIDOR LOCATION
- 13 DEMO PARTIAL EXISTING PARTITION WALL ALERT PROJECT ENGINEER OF ANY RISER/CHASE ISSUE THAT WILL CONFLICT WITH DESIGN INTENT
- 14 REMOVE DOOR & DOOR FRAME; SALVAGE FOR USE FOR THE NEW NUTRITION STORAGE ROOM
- 15 DEMO SINK DRAIN & WATER SUPPLY LINES; PATCH & REPAIR WALL AS NEEDED; PREP FOR PAINT
- 16 DEMO EXISTING UTILITY ROOM INCLUDING FIXTURES, MILLWORK, CEILING & FLOORING; ABATE AS NEEDED & APPROVED
- 17 PARTIAL DEMO OF PARTITION WALL; PREP FOR RE--PURPOSED DOOR FROM EXISTING STAFF LOUNGE
- 18 DEMO & DISPOSE OF SHELVING; ABATE AS NEEDED & APPROVED
- 19 RELOCATE PHYSICAL SECURITY ACCESS CONTROL PANEL
- 20 VENDOR FOR "ALADDIN TEMP RITE CONNECT--RITE II DOCKING STATION" WILL RELOCATE DOCKING SYSTEM TO INCLUDE ALL WORK RELATED TO ELECTRICAL, MECHANICAL & PIPING OF THE DOCKING SYSTEM & THE ROOF CONDENSING UNIT

GENERAL DEMOLITION NOTES:

1. ----- DELINEATES ITEMS TO BE DEMOLISHED



Sheet:

SCALE:
1/4" = 1'-0"

ID 1 of 7




VISN1 INTERIOR DESIGN



VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
DEMOLITION PLAN


DRAWN BY: LW



PARTITION TYPES




- GENERAL ARCHITECTURAL NOTES:**
1. DELINEATES NEW WALLS
 2. DELINEATES PARTITION TYPE
 3. CONTRACTORS & SUBCONTRACTORS ARE TO VERIFY ALL DIMENSIONS ON SITE PRIOR TO PROCEEDING WITH THE WORK.
 4. CONTRACTORS & SUBCONTRACTORS ARE TO PROVIDE SHOP DRAWINGS FOR APPROVAL PRIOR TO ANY FABRICATION OF MILLWORK.
 5. INSTALL SIGNAGE AS PER WRITTEN SPECIFICATIONS
 6. VENDOR FOR "ALADDIN TEMP RITE CONNECT-RITE II DOCKING STATION" WILL RELOCATE DOCKING SYSTEM TO INCLUDE ALL WORK RELATED TO ELECTRICAL, MECHANICAL & PIPING OF THE DOCKING SYSTEM & THE ROOF CONDENSING UNIT
 7. VA TO PROVIDE SPECIFICATIONS ON TEMPORARY AWNING UPON CONSTRUCTION.



VISN1 INTERIOR DESIGN
V/A BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
PROPOSED FLOOR PLAN

DATE: 02-13-18
REV: _____
REV: _____
REV: _____
REV: _____
SCALE: 1/4" = 1'-0"
DRAWN BY: LW



- ELECTRICAL / TEL / DATA LEGEND:**
- ⊕ - STANDARD QUAD ELECTRICAL RECEPTACLE
 - ⊖ - STANDARD DUPLEX ELECTRICAL RECEPTACLE
 - ⊖ - FLOOR MOUNTED DUPLEX ELECTRICAL RECEPTACLE WITH BRUSHED STAINLESS STEEL COVER
 - ⊖ - GFI DUPLEX ELECTRICAL RECEPTACLE
 - ▽ - TELEPHONE RECEPTACLE
 - ▷ - DATA RECEPTACLE
 - ▷ - FLOOR MOUNTED DATA RECEPTACLE WITH BRUSHED STAINLESS STEEL COVER

GENERAL ELECTRICAL NOTES:

- ALL RECEPTACLES ARE LOCATED 18" AFF ON CENTER UNLESS OTHERWISE SPECIFIED
- NEW RECEPTACLES ARE TO BE FLUSH WITH THE WALL - NO VISIBLE CONDUIT
- ELECTRICIAN TO RE-LOCATE NUTRITION CART ELECTRICAL PANEL IN NEW NUTRITION STORAGE ROOM; ELECTRICIAN TO VERIFY ELECTRICAL NEEDS FOR 2 NUTRITION CARTS AS PER MANUFACTURERS RECOMMENDATIONS
- RELOCATE EXISTING FIRE ALARM SWITCHES TO INSIDE OF NURSE STATION & NEW ENTRANCE
- RELOCATE EXISTING FIRE ALARM DEVICES/PULL STATIONS TO MAINTAIN COMPLIANCE, INCLUDING THE INSTALLATION OF NEW DEVICES



Sheet:



VISN1 INTERIOR DESIGN
VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
ELECTRICAL PLAN

DATE: 02-13-18
REV:
REV:
REV:
REV:

SCALE:
1/4" = 1'-0"

DRAWN BY: LW




VISN1 INTERIOR DESIGN
VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
REFLECTED CEILING PLAN

DATE: 02-13-18
REV: _____
REV: _____
REV: _____
REV: _____

SCALE:
1/4" = 1'-0"
DRAWN BY: LW



LIGHTING & SWITCHING LEGEND:


- UNDER CABINET LED STRIP LIGHT
- ⊞ — VA SUPPLIED SURFACE MOUNTED LIGHT FIXTURE
 - — RECESSED CALCULITE WHITE FLANGELESS LED 4'DA. DOWN LIGHT WITH 3000K W/90CRI LAMP
 - — RECESSED CALCULITE WHITE FLANGELESS LED 4'DA. ADJUSTABLE ACCENT WALL WASHER WITH 3000K W/90CRI LAMP
 - — NEW SPRINKLER HEAD/SYSTEM
- — 2 X 2 LED RECESSED AMBIENT LIGHT FIXTURES TO MATCH EXISTING CORRIDOR WITH 3500K W/85CRI LAMP
- — 2 X 2 LED RECESSED EMERGENCY POWER LIGHT FIXTURES WITH 3500K W/85CRI LAMP
- — 2 X 2 SUSPENDED ACOUSTICAL CEILING TILE
- Ⓢ — DIMMABLE SWITCH
- Ⓢ — SWITCH

REFLECTED CEILING PLAN NOTES:


- ALL SWITCHES ARE TO BE LOCATED 42" AFF ON CENTER UNLESS OTHERWISE SPECIFIED
- RELOCATE W-FL CEILING DEVICE TO NEW CEILING
- LOCATE ALL SPRINKLER HEADS TO THE CENTER PANELS THROUGHOUT
- RELOCATE EXISTING FIRE SPRINKLERS TO ENSURE ADEQUATE COVERAGE TO INCLUDE INSTALLING NEW ONES
- RELOCATE EXISTING SUPPLY HVAC VENT TO INSIDE OF THE FOOD CART STORAGE AREA



Sheet:



- FINISH PLAN KEY:
- CPT.1 SHAW CONTRACT TERASU 24" X 24" CARPET TILE
KASW 5714 IN ANTEREN 36513 - MONOLITHIC INSTALL
TRANSITION STRIP TO MATCH VCB.1
- LVT.1 MOHAWK 6" X 48" PLANK LIVING LOCAL LVT #123
WESTERN WOODS
- LVT.2 MOHAWK 6" X 48" PLANK LIVING LOCAL LVT #342
DOWN TOWN
- P.1 BENJAMIN MOORE REVERE PEWTER #HC-172
- P.2 SHERWIN WILLIAMS FAWN BRINDLE #SW7640
LOCATION: ACCENT
- P.3 SHERWIN WILLIAMS BREEZY BLUE #SW7616
LOCATION: ACCENT
- P.4 SHERWIN WILLIAMS SKETCH PAD DRY ERASE PAINT ON
3 COATS OF MAGNETIC PRIMER (MATCH P.1 IN COLOR)
- PLAM.1 WILSONART #7941K-18 TAN ECHO - USE
MATCHING HPL "COORDINATED SURFACES" EDGE
BAND 3/8" THICK - RUN GRAIN ON HORIZONTAL
CORIAN LINEN SOLID SURFACE COUNTER &
BACK SPLASH
- VCB.1 6TH JOHNSONITE #280 SHORELINE VINYL COVE BASE
REFER TO INTERIOR ELEVATIONS FOR LOCATIONS
- PAINTING NOTES:
1. ALL WALLS TO BE PAINTED AN EGGSHELL
FINISH
2. ALL TRIMS TO BE PAINTED A SEMI-GLOSS
FINISH
3. DOOR TRIMS TO BE PAINTED SAME COLOR AS
WALLS THEY ARE LOCATED ON
4. WALLS ARE TO BE PREPARED TO A LEVEL 4
OR BETTER CONDITION
5. DOOR & WINDOW FRAMES ARE TO BE
PREPARED TO A LEVEL 5 CONDITION
6. ALL WALL COVERING IS TO BE REMOVED PRIOR
TO WALL PREP & PAINT
7. PROVIDE CORNER GUARDS ON ALL OUTSIDE CORNERS;
COLOR TO MATCH P.1
8. ALL CEILINGS TO BE PAINTED CEILING WHITE WITH FLAT
FINISH
9. PLEASE CONTACT INTERIOR DESIGNER IF ANY
QUESTION, CONCERN OR IF CLARIFICATION IS
NEEDED



Sheet:



VISN1 INTERIOR DESIGN
VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
FINISH PLAN

DATE: 02-13-18
REV:
REV:
REV:
REV:

SCALE:
1/4" = 1'-0"

DRAWN BY: LW



VISN1 INTERIOR DESIGN
VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
FURNITURE & EQUIPMENT PLAN


DATE: 02-13-18
REV:
REV:
REV:
REV:



SCALE:
1/4" = 1'-0"
DRAWN BY: LW

Sheet:




- GENERAL NOTES:
1. VA BOSTON HEALTHCARE SYSTEM TO PROVIDE AND INSTALL ALL FURNITURE






1 INTERIOR ELEVATION
NURSES STATION
A SCALE: 1/2"=1'-0"



1 INTERIOR ELEVATION
AT COPIER
C SCALE: 1/2"=1'-0"



2 INTERIOR ELEVATION
STAFF BREAK ROOM KITCHEN
D SCALE: 1/2"=1'-0"



VISN1 INTERIOR DESIGN
VA BOSTON HEALTHCARE SYSTEM
940 BELMONT ST. • BROCKTON, MA • 02301

SCIU BUILDING #8
8-1-B NURSE STATION
INTERIOR ELEVATIONS

MILLWORK NOTES:

- COUNTER TOPS TO BE BUILT-UP 1 1/2" THICK SSM.1 WITH SLIGHTLY EASED EDGE.
- CABINETS TO BE MIDMARK SYNTHESIS ; COLOR: DUNE; SERENITY PANEL; EDGE HARDWARE WITH KEYED ALIKE LOCKS & BRUSHED SS FINISH
- RECEPTION DESK TO BE FULL OVERLAY MILLWORK WITH PLAM.1 & KEYED ALIKE LOCKS IN BRUSHED SS FINISH
- HARDWARE PULLS TO BE DOUG MOCKET ADA COMPLIANT DP128-6 1 1/8" ROUND TOP PULLS IN SATIN STAINLESS STEEL FINISH
- CONTRACTORS/SUBCONTRACTORS ARE TO VERIFY ALL DIMENSIONS ON SITE PRIOR TO PROCEEDING WITH THE WORK.
- CONTRACTORS/SUBCONTRACTORS ARE TO PROVIDE SHOP DRAWNGS FOR APPROVAL PRIOR TO ANY FABRICATION OF MILLWORK.
- CONTRACTOR TO SUPPLY 8 1/2" X 11" LUMICOR PANEL SAMPLE AS SPECIFIED FOR APPROVAL



DATE: 02-13-18

REV: SCALE: 1/2" = 1'-0"
REV: DRAWN BY: LW
REV:

Sheet: