

IMAGING SOLUTIONS

SHEET INDEX			
SHEET NUMBER	Sheet description		
N1	GENERAL NOTES		
N2	SITE READINESS NOTES		
Al	EQUIPMENT LAYOUT		
A2	TABLE AND STAND MOUNT		
CS1 & CS2	CEILING STRUCTURE		
El	ELECTRICAL REQUIRED		
E2	ELECTRICAL REQUIRED		
E3	ELECTRICAL REQUIRED		

PROJECT TITLE: PRELIMINARY DRAWING: P2 **IMAGING SOLUTIONS** DATE: 6/14/17 **REVISION: 5** HOT SPRINGS, SD 3223 32nd Ave South, Suite 201 SHEET NUMBER: Fargo, North Dakota 58103 S SHEET TITLE: Phone: (701) 297-0305 Fax: (701) 235-4847 SHEET INDEX 1 OF 10 SHEET www.imagingsolutionsinc.com

GENERAL NOTES

- 1. THESE DRAWINGS ARE FOR INFORMATION PURPOSES ONLY. DRAWINGS SUGGESTS LOCATION OF X-RAY EQUIPMENT AND ASSOCIATED DEVICES, ELECTRICAL DETAILS AND ROOM LAYOUT. THE PREPAIRER OF THESE PLANS CANNOT ACCEPT RESPONSIBILITY FOR ANY CHANGES TO THE EQUIPMENT OR THE ROOM OR ANY DAMAGES RESULTING FROM. ACTUAL CONSTRUCTION DRAWINGS SHOULD BE PROVIDED BY CUSTOMERS ARCHITECT OR GENERAL CONTRACTOR. EVERY EFFORT IS MADE TO GIVE ACCURATE DETAIL OF ACTUAL EQUIPMENT TO BE INSTALLED.
- 2. IMAGING SOLUTIONS IS ONLY RESPONSIBLE FOR INSTALLATION OF IMAGING EQUIPMENT PURCHASES FROM OR CONTRACTED FOR IMAGING SOLUTIONS. ROOM PREPARATION INCLUDING NECESSARY CONSTRUCTION, NETWORKING AND SHIELDING TO BE SUPPLIED BY OTHERS.
- 3. CUSTOMER AND GENERAL CONTRACTOR ARE RESPONSIBLE FOR PREPARING THE ROOM AND COSTS INVOLVED.
- 4. CUSTOMER AND GENERAL CONTRACTOR ARE RESPONSIBLE FOR ALL, BUT NOT LIMITED TO, BUILDING, ELECTRICAL, CONTRACTING, PROFESSIONAL FEES AND PERMITS.
- 5. CUSTOMER IS RESPONSIBLE FOR OBTAINING LEAD SHIELDING REQUIREMENTS FROM A LICENSED PHYSICIST PER STATE AND/OR LOCAL REGULATION
- 6. CUSTOMER IS RESPONSIBLE FOR LIGHTING (NOT ON THIS PLAN). DIMMING LIGHTS MUST BE PROVIDED IN X-RAY AND CONTROL ROOMS BY ARCHITECT PLAN OR ELECTRICAL CONTRACTOR.
- 7. CEILING HEIGHT MUST BE MAINTAINED AS INDICATED ON THIS PLAN. IF UNOBTAINABLE CUSTOMER OR CONTRACTOR MUST NOTIFY IMAGING SOLUTIONS
- 8. ALL DIMENSIONS ARE FROM FINISHED SURFACES UNLESS NOTED.
- 9. WALL BAKING FOR EQUIPMENT SUPPORT TO BE MINIMUM OF 1/2" WOOD SECURED TO MINIMUM OF 3 WALL STUDS WITH BACKING FLUSH WITH FACE OF STUDS.
- 10. CONSTRUCTION MUST COMPLY WITH BUILDING CODES.
- 11. CUSTOMER IS RESPONSIBLE FOR FURNISHING AND INSTALLATION AT CUSTOMERS EXPENSE OF ELECTRICAL JUNCTION BOXES, TROUGH, CONDUIT, BUSHINGS, WIRE DUCT, COVER PLATES, MAIN SWITCHES, PANEL BOARDS, WIRES, UNISTRUT (WALL FLOOR OR CEILING), OR ANY SATISFACTORY INSTALLATION OF X-RAYEQUIPMENT.
- 12. IMAGING SOLUTIONS MUST PROVIDE A SIGNED PURCHASE ORDER PRIOR TO ANY WORK OR MATERIALS PROVIDED AT IMAGING SOLUTIONS EXPENSE. IMAGING SOLUTIONS ASSUMES NO RESPONSIBILITY FOR ANY CONSTRUCTION COSTS RELATED OR NOT RELATED TO THE INSTALLATION OF ANY X-RAY EQUIPMENT.



DATE: 6/14/17 REVISION: 5 SHEET NUMBER: N1 2 OF 10 SHEET

SITE READINESS NOTES

- 1. TO ENSURE THE BEST ENSURE THE BEST ENVIRONMENT FOR INSTALLATION AND PROTECTION OF MECHANICAL EQUIPMENT, COMPUTERS, MONITORS, ELECTRICAL DEVICES, X-RAY TUBES, IMAGE INTENSIFIERS, AND CAMERAS THE FOLLOWING GENERAL CONDITIONS ARE REQUIRED PRIOR TO DELIVERY. RESCHEDULING BY IMAGING SOLUTIONS MANAGEMENT COULD BE REQUIRED IF CONDITIONS ARE NOT MET.
- 2. THE CUSTOMER IS REQUIRED TO OBTAIN ALL PERMITTING, SHIELDING AND APPROVALS REQUIRED BY LOCAL OR STATE GOVERNING AGENCIES.
- 3. CONSTRUCTION COMPLETE WITH LEAD BARRIORS INSTALLED, DOORS HUNG, FLOOR COVERING INSTALLED, CEILING COMPLETED, WALLS COMPLETE AND PAINTED.
- 4. A DUST FREE ENVIRONMENT MUST BE KEPT IN THE X-RAY, CONTROL AND SURROUNDING ROOMS.
- 5. HVAC COMPLETED, TESTED AND FUNCTIONING PRIOR TO DELIVERY.
- 6. POWER AT DESIGNATED PANEL AND EQUIPMENT PRIOR TO DELIVERY.
- 7. ALL CONDUIT, TROUGH, JUNCTION BOXES, WIRE RACEWAYS INSTALLED ACCORDINGLY
- 8. LIGHTING TO BE INSTALLED AND FUNCTIONING.
- 9. BASE PLATES, REINFORCEMENT PLATES, OVERHEAD GRID INSTALLED AS DESIGNATED. IT IS THE RESPONSIBILITY OF THE CUSTOMERS DESIGN ENGINEER TO RECOMMEND METHODS OF ANCHORING AND ATTACHING IMAGING SOLUTIONS EQUIPMENT.
- 10. NETWORK, NETWORK DROPS, PACS, ROUTERS, COMPUTERS, PROCESSORS, PRINTERS, LAST IMAGERS, AND/OR CAMERAS ARE INSTALLED AND TESTED FUNCTIONAL PRIOR TO INSTALL. CUSTOMER IS RESPONSIBLE FOR OBTAINING AND MAINTAINING ANY AND ALL BACK-UP POWER, ANTI-VIRUS SOFTWARE, FIREWALLS, OR OTHER SOFTWARE AND HARDWARE. IMAGING SOLUTIONS WILL CONNECT TO CUSTOMERS NETWORK BUT ASSUMES NO RESPONSIBILITY FOR THE NETWORK RELATED PROBLEMS. IMAGING SOLUTIONS IS NOT RESPONSIBLE FOR COMPUTER ISSUES DUE TO CUSTOMER OR PATIENTS UNAUTHORIZED US OR INSTALLATION OF COMPUTER PROGRAMS FOR THE PERSONAL USE.
- 11. IMAGING SOLUTIONS SUPPLIED SERVERS ARE NOT TO HAVE UPDATES INSTALLED WITHOUT IMAGING SOLUTIONS PRIOR CONSENT. VPN AND PHONE SERVICE MUST BE INSTALLED PRIOR TO INSTALL.
- 12. A CLEAR, UNOBSTRUCTED, PATH INCLUDING ROOM ENTRY MUST BE PROVIDED BY THE CUSTOMER FOR DELIVERY.
- 13. REMOVAL OF OLD EQUIPMENT IS A SEPARATE SERVICE. PLEASE CONTACT IMAGING SOLUTIONS FOR ALL YOUR X-RAY NEEDS.

IMAGING SOLUTIONS


3223 32nd Ave South, Suite 201 Fargo, North Dakota 58103 Phone: (701) 297-0305 Fax: (701) 235-4847 www.imagingsolutionsinc.com PROJECT TITLE:

PRELIMINARY DRAWING: P2

DATE: 6/14/17 REVISION: 5 SHEET NUMBER: N2 3 OF 10 SHEET

HOT SPRINGS, SD SHEET TITLE:

SITE READINESS NOTES



IMAGING SOLUTIONS

PROJECT TITLE: PRELIMIN HOT SPRINGS, SD


SHEET TITLE:

PRELIMINARY DRAWING: P2

DATE: 6/14/17 REVISION: 5 SHEET NUMBER: A 1 4 OF 10 SHEET


3223 32nd Ave South, Suite 201 Fargo, North Dakota 58103 Phone: (701) 297-0305 Fax: (701) 235-4847 www.imagingsolutionsinc.com

EQUIPMENT LAYOUT




USE APPROPRIATE ANCHORS AND WASHERS TO MOUNT TO THE FLOOR. USE OF ANY SMALLER SIZE MAY CAUSE THE BASE TO BREAK FREE FROM THE FLOOR UNDER EXTREME LOAD AND LEVERAGE CONDITIONS. IT IS UP TO THE INSTALLER AND THE CUSTOMER TO DETERMINE THE BEST METHOD FOR MOUNTING THE BASE TO THE FLOOR. BEFORE MOUNTING THE BASE, CONSULT WITH THE BUILDING'S MAINTENANCE SUPERVISOR ABOUT DRILLING HOLES IN THE FLOOR. MAKE SURE THAT THERE ARE NO HAZARDS UNDER THE FLOOR SUCH AS PIPES, CONDUITS, OR STRUCTURAL CABLES WHICH CAN BE DAMAGED BY DRILLING HOLES IN FLOOR.






Fax: (701) 235-4847 **CEILING STRUCTURE** www.imagingsolutionsinc.com

6 OF 10 SHEET





THREE PHASE	MAIN FACILITY DIST XFMR	INCOMING WIRE SIZE ≤ 50' ≤100' ≤200'	X-RAY ROOM BREAKER
480 VAC	105 KVA	#2 #00 250MCM	100 AMP

IMAGING SOLUTIONS	PROJECT TITLE:	PRELIMINARY DRAWING: P2	DATE: 6/14/17
3223 32nd Ave South, Suite 201 Fargo, North Dakota 58103	HOT SPRI	NGS, SD	revision: 5 sheet number:
Phone: (701) 297-0305	SHEET TITLE:		F1
Fax: (701) 235-4847 www.imagingsolutionsinc.com	ELECTRIC	AL REQUIRED	8 OF 10 SHEET

ELECTRICAL REQUIRED

ALL WIRES TO BE THHN OR TFFN STRANDED COPPER THERMOPLASTIC 600 VOLT OR EQUIVALENT, UNLESS OTHERWISE NOTED. MAXIMUM LENGTH FROM DISTRIBUTION TRANSFORMER TO ROOM MAIN BREAKER NOT TO EXCEED 200'. PROJECT TITLE: **IMAGING SOLUTIONS** PRELIMINARY DRAWING: P2 DATE: 6/14/17 **REVISION: 5** HOT SPRINGS, SD 3223 32nd Ave South, Suite 201 SHEET NUMBER: Fargo, North Dakota 58103 SHEET TITLE: Phone: (701) 297-0305 Fax: (701) 235-4847 ELECTRICAL REQUIRED 9 OF 10 SHEET www.imagingsolutionsinc.com

VOLTAGE FLUCTUATION ±10% FULL LOAD.

GENERATOR

THREE PHASE

INCOMING VOLTAGE

480 VAC

NECESSARY FROM ROOM BREAKER TO

CONTRACTOR TO SUPPLY POWER WIRES

INCOMING

WIRE SIZE

#2 #00 250MCM

≤ 50' ≤100' ≤200'

NOTE.		
NUTE	#6 GROUND WIRE REQUIRED	

X-RAY ROOM MAIN BREAKER 100 AMP	OPERATIONAL CLIMATE		
	TEMPERATURE	10 - 40 DEGREES C OR 50 - 104 DEGREES F	
	HUMIDITY	30% - 75%	
WIRE REQUIRED	PRESSURE	70 kPa - 106 kPa	
	TRESSORE		

FLEX

HOLE

. . .

ELECTRICAL CALLOUT INFO

MINIMUM RECOMMENDED

DISTRIBUTION

TRANSFORMER RATING

105 KVA

$\langle 1 \rangle$	INCOMING LINE POWER AND SHUNT TRIP BREAKER. SEE MSP-E2 SPECIFICATION BLOCK
2	12" WALL TROUGH WITH (1) 3" GROMMETED HOLE OR ACCESS SPACE IN COVER 18" FROM FLOOR
3	4" x 4" JBOX LOCATED FLUSH W/ FINISHED FLOOR WITH (1) 2" GROMMETED HOLE IN COVER
4	2" HOLE CORE DRILLED THROUGH FLOOR AS CLOSE TO WALL AS POSSIBLE
5	8"X8"X8" JUNCTION BOX 1" ABOVE FINISHED CEILING WITH CONDUIT OR FLEX TO TROUGH WITH (1) 3" GROMMETED HOLE IN COVER FACING DOWN *CONTRACTOR SUPPLIED*
6	4" X 4" J-BOX CENTERED 18" A.F.F. WITH (1) 2" GROMMETED HOLE IN COVER
7	E.P.O. SWITCH IS CONTRACTOR SUPPLIED AND INSTALLED PROVIDES SHUNT TRIP FOR INCOMING LINE POWER @ ITEM 1
8	WARNING LIGHT ABOVE DOOR. WIRES TO BE ROUTED TO WALL TROUGH 2 WITH 12 FOOT WHIP AT FLOOR TO MAKE CONNECTIONS
9	DOOR SWITCH(ES) ARE CONTRACTOR SUPPLIED AND INSTALLED WITH (2) #14 WIRES TO WALL TROUGH 2 WITH 12 ' WHIP FOR MAKING FINAL CONNECTIONS
(10)	(1) DEDICATED QUAD OUTLET 115VAC 20 AMP (1) NETWORKING DATA DROPS LOCATED 12" A.F.F
$\langle 11 \rangle$	(1) DEDICATED QUAD OUTLET 115VAC 20 AMP LOCATED 12'' A.F.F

THREE PHASE	MAIN FACILITY DIST XFMR	INCOMING WIRE SIZE ≤ 50' ≤100' ≤200'	X-RAY ROOM BREAKER
480 VAC	105 KVA	#2 #00 250MCM	100 AMP

8"x8"x8"


J-Box

4

(5)

FINISHED CEILING

NOTE: #6 GROUND WIRE REQUIRED VOLTAGE FLUCTUATION ± 10 FULL LOAD. ALL WIRES TO BE THHN OR TFFN STRANDED COPPER THERMOPLASTIC 600 VOLT OR EQUIVALENT, UNLESS OTHERWISE NOTED. MAXIMUM LENGTH FROM DISTRIBUTION TRANSFORMER TO ROOM MAIN BREAKER NOT TO EXCEED 200 FEET.



* SEE SHEET E2 FOR WIRE INFORMATION

