

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot



- KEYNOTES:**
1. INSTALL ABOVE ACCESSIBLE CEILING.
 2. PENDANT MOUNT FROM CEILING.
 3. STUB 1/2" TO ABOVE ACCESSIBLE CEILING AND ROUTE LOW VOLTAGE CONDUCTORS TO RELAY PANEL "R1". VERIFY WIRING TOPOLOGY (DAISY CHAIN OR STAR) WITH MANUFACTURER.
 4. CONNECT SINGLE BALLAST LUMINAIRES (GF3'S) TO RELAY CONTROLLING OUTBOARD LAMPS OF DUAL BALLAST LUMINAIRES (GF1'S) IN SAME AREA.
 5. PROVIDE THREE-WAY SWITCH COMPATIBLE WITH 0-10V DIMMING SWITCH. SEE ELECTRICAL SYMBOLS LIST SHEET E-001 FOR DIMMER SPECIFICATIONS.
 6. DEVICES DOWNSTREAM ARE NOT TO BE CONTROLLED BY RELAYS UNLESS NOTED OTHERWISE FURTHER DOWNSTREAM.
 7. CONNECT SINGLE BALLAST LUMINAIRES (GF3'S) AND THREE-WAY SWITCH TO SAME CIRCUIT AS OUTBOARD LAMPS OF DUAL BALLAST LUMINAIRE (GF1'S).
 8. PROVIDE MATCHING DIGITAL REMOTE DIMMER (3-WAY DIMMER). LEVITON NO. V200R-7L (OR EQUAL).
 9. COORDINATE MOUNTING IN 6" SQUARE BOLLARD PROVIDED BY HANDICAPPED PUSHPLATE MANUFACTURER.

GENERAL SHEET NOTES:

1. SEE SHEET E-001 FOR ELECTRICAL SYMBOLS LIST.

FIRST FLOOR LIGHTING PLAN
SCALE: 1/8"=1'-0"



RECORD DRAWINGS -- JULY 28, 2009
FULLY SPRINKLERED

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY OTHERS. ZGA ARCHITECTS AND PLANNERS, CHARTERED, AND THEIR CONSULTANTS, HAVE NOT VERIFIED THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY OTHERS.

CONSULTANTS: EIDAM AND ASSOCIATES CONSULTING ENGINEERS 720 E. PARK BOULEVARD, SUITE 250 BOISE, IDAHO 83712 PHONE (208)345-7157; FAX (208)345-7173 email: cades@eidam-asso.com EIDAM & ASSOCIATES PROJECT NUMBER 08-034RD		RECORD DOCUMENTS THESE DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY THE CONTRACTOR. EIDAM & ASSOCIATES HAVE NOT VERIFIED THE ACCURACY OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH MAY BE INCORPORATED HEREIN AS A RESULT. Date: JULY 2009 By: GLJ Eidam and Associates 720 E. Park Boulevard, Suite 250 Boise, Idaho 83712 208-345-7173 Copyright 2009 - Eidam and Associates		ARCHITECT: ZGA ARCHITECTS AND PLANNERS, CHARTERED 565 W. MYRTLE STREET, SUITE 225 BOISE, IDAHO 83702-7606 (208) 345-8872 CONTACT: LOWELL ALSETH, AIA		Drawing Title FIRST FLOOR LIGHTING PLAN Approved Project Director		Project Title Veterans Benefits Administration Boise Regional Office Building Location Boise, Idaho Date January 22, 2009 Checked GLJ/JMH Drawn KGL		Project Number 347 - VB3018 Building Number RO Drawing Number E-110L Dwg. 8 of --		Office of Facilities Management 	
Revisions Date													