

SECTION 07 46 46
FIBER CEMENT BOARD INSTALLATION

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Fiber cement lap siding, panels, shingle, trim, fascia, moulding and accessories; James Hardie HZ10 Engineered for Climate Siding.
- B. Factory-finished fiber cement lap siding, panels, shingle, trim, fascia, moulding and accessories; James Hardie HZ10 Engineered for Climate Siding.

1.2 RELATED SECTIONS

- A. Section 09 06 00 - Schedule of Finishes.

1.3 REFERENCES

- A. AS D3359 - Standard Test Method for Measuring Adhesion by Tape Test, Tool and Tape.
- B. AS E136 - Standard Test Method for Behavior of Materials in a Vertical Tube Furnace at 750 degrees C.

1.4 SUBMITTALS

- A. Submit under provisions of Section 01 33 23 - Shop Drawings, Product Data, Samples.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation methods.
- C. Shop Drawings: Provide detailed drawings of atypical non-standard applications of cementitious siding materials which are outside the scope of the standard details and specifications provided by the manufacturer.
- D. Verification Samples: For each finish product specified, one sample, minimum size 4 by 6 inches (100 by 150 mm), representing actual product, color, and patterns.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Minimum of 2 years' experience with installation of similar products.
- B. Materials must be certified asbestos-free.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened packaging until ready for installation.

- B. Store siding on edge or lay flat on a smooth level surface. Protect edges and corners from chipping. Store sheets under cover and keep dry prior to installing.
- C. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.7 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.8 WARRANTY

- A. Product Warranty: Limited, non-pro-rated product warranty.
 - 1. HardiePlank HZ10 lap siding for 30 years.
 - 2. HardiPanel HZ10 vertical siding for 30 years.
 - 3. HardieSoffit HZ10 panels for 30 years.
 - 4. HardieShingle HZ10 siding for 30 years.
 - 5. HardieTrim HZ10 boards for 15 years.
 - 6. Artisan HZ10 lap siding for 30 years.
- B. Finish Warranty: Limited product warranty against manufacturing finish defects.
 - 1. When used for its intended purpose, properly installed and maintained according to Hardie's published installation instructions, James Hardie's ColorPlus finish with ColorPlus Technology, for a period of 15 years from the date of purchase: will not peel; will not crack; and will not chip. Finish warranty includes the coverage for labor and material.
- C. Workmanship Warranty: Application limited warranty for 2 years.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: James Hardie Building Products, Inc.
- B. Requests for approval of equal substitutions will be considered in accordance with provisions of this Section; substitutions must carry the same or better warranty.

2.2 SIDING AND TRIM

- A. HardiePlank HZ10 lap siding requirement for materials:
 - 1. Fiber-cement siding - complies with ASTM C 1186 Type A Grade II.
 - 2. Fiber-cement siding - complies with ASTM E 136 as a noncombustible material.
 - 3. Fiber-cement siding - complies with ASTM E 84 Flame Spread Index = 0, Smoke Developed Index = 5.
 - 4. ICC-ES evaluation reports ESR-2290, ESR-1844, and ESR-

- B. Artisan HZ10 lap siding requirement for Materials:
 - 1. Fiber-cement siding - complies with ASTM C 1186 Type A Grade II.
 - 2. Fiber-cement siding - complies with ASTM E 136 as a noncombustible material.
 - 3. Fiber-cement Siding - complies with ASTM E 84 Flame Spread Index = 0, Smoke Developed Index = 5.
 - 4. ICC-ES evaluation report ESR-2290
 - 5. Intertek Product Listing.

- C. Lap Siding: Artisan HZ10 Lap Siding as manufactured by James Hardie Building Products, Inc.
 - 1. Type: Smooth 8-1/4 inches (210 mm) with 7 inches (178 mm) exposure.

- D. Lap Siding: HardiePlank HZ10 Lap as manufactured by James Hardie Building Products, Inc.
 - 1. Type: Smooth 8-1/4 inches (210 mm) with 7 inches (178 mm) exposure.

- E. Soffit Panels: HardieSoffit HZ10 soffit panel, factory sealed on 5 sides as manufactured by James Hardie Building Products, Inc.
 - 1. Type: Smooth non-vented, 12 inches (305 mm) by 12 feet (3658 mm).
 - 2. Type: Smooth vented, provides 5 square inches (32.3 sq.cm) of net free ventilation per linear foot, 12 inches (305 mm) by 12 feet (3658 mm).

- F. Trim:
 - 1. HardieTrim HZ10 boards as manufactured by James Hardie Building Products, Inc.
 - a. Product: 4/4 Boards, 3-1/2 inch (89 mm) width.
 - b. Texture: Smooth.
 - c. Length: 12 feet (3658 mm).
 - d. Thickness: 3/4 inch (19 mm).
 - 2. HardieTrim HZ10 Fascia boards as manufactured by James Hardie Building Products, Inc.
 - 3. Artisan HZ10 Accent trim as manufactured by James Hardie Building Products, Inc.
 - 4. Fiber-cement trim - complies with ASTM C 1186 Type A Grade II.
 - 5. Fiber-cement trim - complies with ASTM E 136 as a noncombustible material.
 - 6. Fiber-cement trim - complies with ASTM E 84 Flame Spread Index = 0, Smoke Developed Index = 5.
 - 7. Intertek Product Listing.

2.3 FASTENERS

- A. Wood Framing Fasteners:
 - 1. Wood Framing: 4d common corrosion resistant nails.
 - 2. Wood Framing: 6d common corrosion resistant nails.
 - 3. Wood Framing: 8d box ring common corrosion resistant nails.
 - 4. Wood Framing: 0.089 inch (2.2 mm) shank by 0.221 inch

- (5.6 mm) head by 2 inches (51 mm) corrosion resistant siding nails.
- 5. Wood Framing: 0.093 inch (2.4 mm) shank by 0.222 inch (5.6 mm) head by 2 inches (51 mm) corrosion resistant siding nails.
- 6. Wood Framing: 0.093 inch (2.4 mm) shank by 0.222 inch (5.6 mm) head by 2-1/2 inches (64 mm) corrosion resistant siding nails.
- 7. Wood Framing: 0.091 inch (2.3 mm) shank by 0.221 inch (5.6 mm) head by 1-1/2 inches (38 mm) corrosion resistant siding nails.
- 8. Wood Framing: 0.091 inch (2.3 mm) shank by 0.225 inch (5.7 mm) head by 1-1/2 inches (38 mm) corrosion resistant siding nails.
- 9. Wood Framing: 0.121 inch (3 mm) shank by 0.371 inch (9.4 mm) head by 1-1/4 inches (32 mm) corrosion resistant roofing nails.
- 10. Wood Framing: No. 11 gauge 1-1/4 inches (32 mm) corrosion resistant roofing nails.
- 11. Wood Framing: No. 11 gauge 1-1/2 inches (38 mm) corrosion resistant roofing nails.
- 12. Wood Framing: No. 11 gauge 1-3/4 inches (44 mm) corrosion resistant roofing nails.

2.4 FINISHES

- A. Factory Primer: Provide factory applied universal primer.
 - 1. Primer: Factory primed by James Hardie.
 - 2. Topcoat: Refer to Section 09 90 00 - Painting and Coating and Exterior Finish Schedule.
- B. Factory Finish: Refer to Exterior Finish Schedule.
 - 1. Product: ColorPlus Technology by James Hardie.
 - 2. Definition: Factory applied finish; defined as a finish applied in the same facility and company that manufactures the siding substrate.
 - 3. Process:
 - a. Factory applied finish by fiber cement manufacturer in a controlled environment within the fiber cement manufacturer's own facility utilizing a multi-coat, heat cured finish within one manufacturing process.
 - b. Each finish color must have documented color match to delta E of 0.5 or better between product lines, manufacturing lots or production runs as measured by photospectrometer and verified by third party.
 - 4. Protection: Factory applied finish protection such as plastic laminate that is removed once siding is installed
 - 5. Accessories: Complete finishing system includes pre-packaged touch-up kit provided by fiber cement manufacturer. Provide quantities as recommended by manufacturer.
- C. Factory Finish Color for Trim, Soffit and Siding Colors:
 - 1. Navajo Beige JH30-10.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If framing preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- C. Nominal 2 inch by 4 inch (51 mm by 102 mm) wood framing selected for minimal shrinkage and complying with local building codes, including the use of water-resistive barriers or vapor barriers where required. Minimum 1-1/2 inches (38 mm) face and straight, true, of uniform dimensions and properly aligned.
 - 1. Install water-resistive barriers and claddings to dry surfaces.
 - 2. Repair any punctures or tears in the water-resistive barrier prior to the installation of the siding.
 - 3. Protect siding from other trades.
- D. Minimum 20 gauge (33 mm) 3-5/8 inch (92 mm) C-Stud 16 inches maximum on center or 16 gauge (54 mm) 3-5/8 inches (92 mm) C-Stud 24 inches (610 mm) maximum on center metal framing complying with local building codes, including the use of water-resistive barriers and/or vapor barriers where required. Minimum 1-1/2 inches (38 mm) face and straight, true, of uniform dimensions and properly aligned.
 - 1. Install water-resistive barriers and claddings to dry surfaces.
 - 2. Repair any punctures or tears in the water-resistive barrier prior to the installation of the siding.
 - 3. Protect siding from other trades.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Install a water-resistive barrier is required in accordance with local building code requirements.
- D. The water-resistive barrier must be appropriately installed with penetration and junction flashing in accordance with local building code requirements.
- E. Install Engineered for Climate HardieWrap weather barrier in accordance with local building code requirements.
- F. Use HardieWrap Seam Tape and joint and laps.
- G. Install and HardieWrap flashing, HardieWrap Flex Flashing.

3.3 INSTALLATION - HARDIEPLANK HZ10 LAP SIDING, ARTISAN HZ10 LAP SIDING, AND ARTISAN HZ10 LAP SIDING WITH LOCK JOINT SYSTEM

- A. Install materials in strict accordance with manufacturer's installation instructions.
- B. Starting: Install a minimum 1/4 inch (6 mm) thick lath starter strip at the bottom course of the wall. Apply planks horizontally with minimum 1-1/4 inches (32 mm) wide laps at the top. The bottom edge of the first plank overlaps the starter strip.
- C. Allow minimum vertical clearance between the edge of siding and any other material in strict accordance with the manufacturer's installation instructions.
- D. Align vertical joints of the planks over framing members.
- E. Butt joints must not fall within 4 inches (102 mm) of a stud. Do not nail within 2 inches (51 mm) of the end of planks.
- F. Maintain clearance between siding and adjacent finished grade.
- G. Locate splices at least one stud cavity away from window and door openings.
- H. For proper fastener selection and fastening schedules for various wind load requirements and framing options, refer to the Technical Data Sheet at www.aspyredesign.com.
- I. Face nail to sheathing.
- J. Locate splices at least 12 inches (305 mm) away from window and door openings.

3.4 INSTALLATION - HARDIEPANEL HZ10 VERTICAL SIDING

- A. Install materials in strict accordance with manufacturer's installation instructions.
- B. Block framing between studs where HardiePanel siding horizontal joints occur.
- C. Install metal Z flashing and provide a 1/4 inch (6 mm) gap at horizontal panel joints.
- D. Place fasteners no closer than 3/8 inch (9.5 mm) from panel edges and 2 inches (51 mm) from panel corners.
- E. Allow minimum vertical clearance between the edge of siding and any other material in strict accordance with the manufacturer's installation instructions.
- F. Maintain clearance between siding and adjacent finished grade.
- G. Specific framing and fastener requirements refer to Tables 2 and 3 in National Evaluation Service Report No. NER-405.
- H. Factory Finish Touch Up: Apply touch up paint to cut edges in accordance with manufacturer's printed instructions.
 - 1. Touch-up nicks, scrapes, and nail heads in pre-finished siding using the manufacturer's touch-up kit pen.

2. Touch-up of nails shall be performed after application, but before plastic protection wrap is removed to prevent spotting of touch-up finish.
3. Use touch-up paint sparingly. If large areas require touch-up, replace the damaged area with new pre-finished siding. Match touch up color to siding color through use of manufacturer's branded touch-up kits.

3.5 INSTALLATION - HARDIE HZ10 SHINGLESIDE CLADDING

- A. Install materials in strict accordance with manufacturer's installation instructions.
- B. Substrate: Install a minimum 7/16 inch (11 mm) thick OSB wall sheathing or equivalent braced walls complying with applicable building codes.
- C. Starting: Install a minimum 1/4 inch (6 mm) thick lath starter strip at the bottom course of the wall.
- D. Maintain clearance between siding and adjacent finished grade.
- E. Apply starter course of 10 inches (254 mm) shingles or 9-1/2 inches (241 mm) lap siding overlapping the starter strip.
- F. Apply subsequent courses horizontally with a minimum 10 inch overlap at the top and a minimum 2 inch (51 mm) side lap. The bottom edge of the first two courses overlaps the starter strip.
- G. Fasten between 1/2 inch (13 mm) and 1 inch (25 mm) in from the side edge and between 8-1/2 inches (216 mm) and 9 inches (229 mm) up from the shingle bottom edge.
- H. Allow minimum vertical clearance between the edge of siding and any other material in strict accordance with the manufacturer's installation instructions.
- I. Ensure vertical joints of overlapping shingle course do not align.
- J. Wind Resistance: Where a specified level of wind resistance is required, Hardie Shingle siding is installed to substrate and secured with a minimum two fasteners described in Table No. 6, 7 and 8 in National Evaluation Service Report No. NER-405.

3.6 INSTALLATION - HARDIETRIM HZ10 BOARDS

- A. Install materials in strict accordance with manufacturer's installation instructions. Install flashing around all wall openings.
- B. Fasten through trim into structural framing or code complying sheathing. Fasteners must penetrate minimum 3/4 inch (19 mm) or full thickness of sheathing. Additional fasteners may be required to ensure adequate security.
- C. Place fasteners no closer than 3/4 inch (19 mm) and no further

than 2 inches (51 mm) from side edge of trim board and no closer than 1 inch (25 mm) from end. Fasten maximum 16 inches (406 mm) on center.

- D. Maintain clearance between trim and adjacent finished grade.
- E. Trim inside corner with a single board trim both side of corner.
- F. Outside Corner Board Attach Trim on both sides of corner with 16 gage corrosion resistant finish nail 1/2 inch (13 mm) from edge spaced 16 inches (406 mm) apart, weather cut each end spaced minimum 12 inches (305 mm) apart.
- G. Allow 1/8 inch gap between trim and siding.
- H. Seal gap with high quality, paint-able caulk.
- I. Shim frieze board as required to align with corner trim..
- J. Fasten through overlapping boards. Do not nail between lap joints.
- K. Overlay siding with single board of outside corner board then align second corner board to outside edge of first corner board. Do not fasten HardieTrim boards to HardieTrim boards.
- L. Shim frieze board as required to align with corner trim.
- M. Install HardieTrim Fascia boards to rafter tails or to sub fascia.

3.7 FINISHING

- A. Finish unprimed siding with a minimum one coat high quality, alkali resistant primer and one coat of either, 100 percent acrylic or latex or oil based, exterior grade topcoats or two coats high quality alkali resistant 100 percent acrylic or latex, exterior grade topcoat within 90 days of installation. Follow paint manufacturer's written product recommendation and written application instructions.
- B. Finish factory primed siding with a minimum of one coat of high quality 100 percent acrylic or latex or oil based exterior grade paint within 180 days of installation. Follow paint manufacturer's written product recommendation and written application instructions.

3.8 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

----- END -----