SECTION 02 41 00
DEMOLITION

PART 1 - GENERAL

1.1 DESCRIPTION:

This section specifies demolition and removal of buildings, portions of buildings, utilities, other structures and debris.

1.2 RELATED WORK:

A. Demolition and removal of roads, walks, curbs, and on-grade slabs outside buildings to be demolished: Section 31 20 11, EARTH MOVING (SHORT FORM).

B. Safety Requirements: GENERAL CONDITIONS Article, ACCIDENT PREVENTION.

C. Disconnecting utility services prior to demolition: Section 01 00 00, GENERAL REQUIREMENTS.

D. Reserved items that are to remain the property of the Government: Section 01 00 00, GENERAL REQUIREMENTS.

E. Asbestos Removal: Section 02 82 11, TRADITIONAL ASBESTOS ABATEMENT.

F. Lead Paint: Section 02 83 33.13, LEAD-BASED PAINT REMOVAL AND DISPOSAL.

G. Environmental Protection: Section 01 57 19, TEMPORARY ENVIRONMENTAL CONTROLS.

H. Infectious Control: Section 01 00 00, GENERAL REQUIREMENTS, Article 1.7, INFECTION PREVENTION MEASURES.

1.3 PROTECTION:

A. Perform demolition in such manner as to eliminate hazards to persons and property; to minimize interference with use of adjacent areas, utilities and structures or interruption of use of such utilities; and to provide free passage to and from such adjacent areas of structures. Comply with requirements of GENERAL CONDITIONS Article, ACCIDENT PREVENTION.

B. Provide safeguards, including warning signs, barricades, temporary fences, warning lights, and other similar items that are required for protection of all personnel during demolition and removal operations. Comply with requirements of Section 01 00 00, GENERAL REQUIREMENTS, Article 1.9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES AND IMPROVEMENTS.

C. Maintain fences, barricades, lights, and other similar items around exposed excavations until such excavations have been completely filled.

D. Provide enclosed dust chutes with control gates from each floor to carry debris to truck beds and govern flow of material into truck. Provide overhead bridges of tight board or prefabricated metal construction at dust chutes to protect persons and property from falling debris.

E. Prevent spread of flying particles and dust. Sprinkle rubbish and debris with water to keep dust to a minimum. Do not use water if it results in hazardous or objectionable condition such as, but not limited to; ice, flooding, or pollution. Vacuum and dust the work area daily.

F. In addition to previously listed fire and safety rules to be observed in performance of work, include following:
   1. No wall or part of wall shall be permitted to fall outwardly from structures.
   2. Wherever a cutting torch or other equipment that might cause a fire is used, provide and maintain fire extinguishers nearby ready for immediate use. Instruct all possible users in use of fire extinguishers.
   3. Keep hydrants clear and accessible at all times. Prohibit debris from accumulating within a radius of 15 feet of fire hydrants.

G. Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The contractor shall take necessary precautions to avoid damages to existing items to remain in place, to be reused, or to remain the property of the Medical Center; any damaged items shall be repaired or replaced as approved by the Resident Engineer. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition or removal works. Repairs, reinforcement, or structural replacement must have Resident Engineer’s approval.

H. The work shall comply with the requirements of Section 01 57 19, TEMPORARY ENVIRONMENTAL CONTROLS.

I. The work shall comply with the requirements of Section 01 00 00, GENERAL REQUIREMENTS, Article 1.7 INFECTION PREVENTION MEASURES.

1.4 UTILITY SERVICES:

A. Demolish and remove outside utility service lines shown to be removed.

B. Remove abandoned outside utility lines that would interfere with installation of new utility lines and new construction.

PART 2 - PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 DEMOLITION:

A. Completely demolish and remove equipment, buildings and structures, including all appurtenances related or connected thereto, as noted below:
   1. As required for installation of new utility service lines.
   2. To full depth within an area defined by hypothetical lines located 5 feet outside building lines of new structures.

B. Debris, including brick, concrete, stone, metals and similar materials shall become property of Contractor and shall be disposed of by him daily, off the Medical Center property. Materials that cannot be removed daily shall be stored in areas specified by the Resident Engineer. Contractor shall dispose debris in compliance with applicable federal, state or local permits, rules and/or regulations.

C. Remove and legally dispose of all materials other than earth to remain as part of project work. Materials removed shall become property of contractor and shall be disposed of in compliance with applicable federal, state or local permits, rules and/or regulations. All materials in trash dump areas, including above surrounding grade and extending to a depth of 5 feet below surrounding grade, shall be included as part of the lump sum compensation for the work of this section. The removal of hazardous material shall be referred to Hazardous Materials specifications.

E. Remove existing utilities as indicated or uncovered by work and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Resident Engineer. When Utility lines are encountered that are not indicated on the drawings, the Resident Engineer shall be notified prior to further work in that area.

3.2 CLEAN-UP:

On completion of work of this section and after removal of all debris, leave site in clean condition satisfactory to Resident Engineer. Clean-up shall include off the Medical Center property disposal of all items and materials not required to remain property of the Government as well as all debris and rubbish resulting from demolition operations.

- - - E N D - - -

SECTION 02 85 00

INFECTION CONTROL

PART 1 GENERAL

1.1 DEFINITIONS

Construction Type A - Inspection and Non-Invasive Activities. Includes, but is not limited to: removal of ceiling tiles for visual inspection limited to 1 tile per 50 square feet; painting (but not sanding); wall covering; electrical trim work; minor plumbing; and activities which do not generate dust or require cutting of walls or access to ceilings other than for visual inspection.

Construction Type B - Small scale, short duration activities that create minimal dust. Includes, but is not limited to: installation of telephone or computer cabling; access to pipe chase spaces; cutting of walls or ceilings where dust migration can be controlled.

Construction Type C - Any work, which generates a moderate to high level of dust or requires demolition or removal of any fixed building components or assemblies. Includes, but is not limited to: sanding of walls for painting or wall covering; removal of floor coverings, ceiling tiles and casework; new wall construction; minor ductwork or electrical work above ceilings; major cabling activities; and any activity which cannot be completed within a single work shift.

Construction Type D - Major demolition and construction projects. Includes, but is not limited to: activities that require consecutive work shifts; require heavy demolition or removal of a complete ceiling system; and new construction.

Group 1 Lowest Risk Patient Risk Group - Office areas

Group 2 Medium Risk Patient Risk Group - Cardiology, Echocardiography, Laboratories, Nuclear Medicine, Physical Therapy, Radiology/MRI, Respiratory Therapy

Group 3 Medium-High Risk Patient Risk Group - Emergency Room, Day Surgery, Pharmacy, Endoscopy

Group 4 Highest Risk Patient Risk Group - 4B (Hem/Onc Unit), Operating Rooms/Sterile Processing, Cardiac Catheterization & Angiography Areas, Dialysis, ICU/CCU/CVT/CVT-I, Med/Surg Nursing Units, Post-Anesthesia Care Units.

HEPA - High Efficiency Particulate Air

Level of Infection Control - Class I, II, III or IV, as determined from the IC Matrix

1.2 DESCRIPTION

The purpose of the infection control procedures are to minimize the risk of infection during construction by maintaining the integrity of the environment, and controlling the spread of dust.

The following Infection Control Matrix defines the matrix of precautions to be implemented for construction, demolition and renovation. Matching the planned construction type with the patient risk group on the matrix defines the minimum level of infection control required (Class I, II, III or IV).

Risk Level	Construction Activity			
	Type A	Type B	Type C	Type D
Group 1 Lowest Risk	Class I	Class II	Class II	Class III/IV
Group 2 Medium Risk	Class I	Class II	Class III	Class IV
Group 3 High Risk	Class II	Class II	Class III/IV	Class IV
Group 4 Highest Risk	Class II	Class III/IV	Class III/IV	Class IV

Class I:

1. Execute work by methods to minimize raising dust and fumes from interior and exterior construction operations.
2. Water mist work surfaces to control dust
3. Immediately replace a ceiling tile displaced for visual inspection
4. Use travel routes that minimize exposure of patients to construction workers, materials, tools, and equipment.
5. Schedule utility interruptions during periods of low hospital activity.

Class II: In addition to precautions for Class I:

1. Provide active means to prevent airborne dust from dispersing into the atmosphere.
2. HEPA vacuum upper surfaces of ceiling tiles prior to removal
3. Seal unused doors with duct tape
4. Block off and seal air vents
5. Place adhesive walk-off mats at entrances and exits of work areas.
6. Seal or isolate HVAC system in areas where work is being performed.
7. HEPA vacuum work surfaces and containers before removing from the work area.
8. HEPA vacuum worker clothing, tools, materials and equipment before leaving the work area.

Class III: In addition to the precautions for Class I and II:

1. Install critical barriers at all openings to the work area

2. Isolate HVAC system in area where work is being done to prevent contamination of the duct system.
3. Maintain negative air pressure within the work site utilizing HEPA-equipped air filtration units.
4. Seal holes, pipes, conduits and punctures within the work area using fire-safe, impermeable materials.
5. Construct anteroom contiguous to the work area and require all personnel to pass through this room so they can be vacuumed using a HEPA vacuum cleaner before leaving the work site.
6. Contain construction waste before transport in tightly covered containers
7. Cover transport receptacles or carts. Tape covering to container to seal all joints.
8. Do not remove barriers from the work area until the completed project is thoroughly cleaned by the VA's Environmental Services Department and inspected by the VA.

Class IV: In addition to precautions for Class I, II and III:

1. No work is permitted in areas occupied by patients.
2. All personnel entering the work site are required to wear head covers, shoe covers, and overalls. Head covers, shoe covers, and overalls must be changed within the anteroom each time the worker exists the work area..

Conduct work by implementing the appropriate level of infection control as required or as noted herein.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only.

SD-06 Test Reports

Air sampling results;

Pressure differential recordings for local exhausts;

SD-07 Certificates

Employee training;

VAMC Infection Control Construction Permits; G

SD-11 Closeout Submittals

Completed daily VAMC Infection Control Compliance Checklists

Construction Inspection Forms

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

All personnel are required to wear N95 respirators, disposable booties and coveralls when working inside the containment. These are to be removed when exiting the work area.

All personnel are to be trained on infection control procedures and these work procedures.

1.5 EQUIPMENT

Fire retardant polyethylene

HEPA filtered vacuum

HEPA filtered negative air machine

Duct tape

Framing and other materials necessary to isolate the work area

Power equipment that generates dust will have dust collection equipment attached.

1.6 PROJECT/SITE CONDITIONS

1.6.1 Existing Conditions

Perform work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better as determined by the Contracting Officer.

1.7 SEQUENCING AND SCHEDULING

All work will be coordinated with the hospital infection control office, facility director, safety department, security office and work will not commence until the Infection Control Construction Permit has been approved by VAMC for that specific work area, including designation of the pre-determined debris removal routes.

Any issue that could have impact on VAMC operations must be reported to the VAMC project representative before commencement. This would include containment breeching, loss of negative pressure, releases of dust/debris into uncontrolled interior building areas or other issues that could affect infection control procedures.

Work phasing and breakout of specific work areas shall be in coordination with the Contracting Officers needs and the General Contractor's schedule and not adversely affect the operations of the VAMC in any way.

PART 2 PRODUCTS

NotUsed.

PART 3 EXECUTION

3.1 PREPARATION

Obtain an Infection Control Construction Permit prior to performing any work of construction types A through D as defined above. Removal of a single ceiling tile in a suspended acoustic ceiling for observation purposes only does not require an infection control construction permit.

Existing air handling ductwork, supply and return grills, and/or HVAC fresh air intakes shall be isolated using air tight seals.

Elevator use must be coordinated with facilities and must not impact VAMC operations. Time and dates of waste load must be identified each day.

3.2 ERECTION

Install impervious barriers from floor to ceiling and wall to wall to seal work areas from non-work areas. When work is in an area designated for Class IV protection, double impervious barriers shall be used.

Impervious barriers shall be constructed of non-combustible or fire retardant materials. Barriers shall be minimum one-hour rated construction. Fire retardant polyethylene may be used for impervious (dust) barriers that remain in place for not more than 72 hours. Construct all other barriers of gypsum board (flame spread rating of 25 or less in accordance with ASTM E84) on both sides of metal steel studs. Extend the partitions through suspended ceilings to floor slab deck or roof. Wood framing is not allowed. At door openings, use Class C ¾ hour fire/smoke rated doors and frames with closers.

Critical barriers are to be installed on all doors and windows and other entrances to the work area.

Seal all holes, chases, pipe cavities and other perforations before commencing work. Sealants shall be non-flammable material.

Create a negative pressure work area by installing HEPA filtered negative air machines within the work area to remove dust particles from the air and exhaust to the outside.

Maintain negative pressure of at least -0.02 inches water in all work areas and document compliance.

Construct an entry/exit chamber for decontaminating people and equipment leaving the work area. A HEPA vacuum is required to remove dust from equipment and people leaving the site. Disposable PPE shall be removed prior to exiting the entry/exit chamber.

Adhesive Step-off pads at least 24"x36" are to be located at the exit of the work area before entering the occupied areas of the VAMC.

Vacuum the top surfaces of ceiling tiles using a HEPA vacuum prior to removal of ceiling tiles.

Traffic shall be minimized to/from the work area.

Elevators or stairwells within the work area must be isolated with impervious barriers.

Activities such as cutting, demolishing, and other large dust generating activities shall have work surfaces water-misted prior to impact.

Where powered equipment that generates dust will be utilized, such equipment shall have dust collection equipment attached.

Provide active means to prevent airborne dust from dispersing into the atmosphere.

3.3 FIELD QUALITY CONTROL

3.3.1 Inspection

Conduct daily inspections using the VAMC Infection Control Compliance Checklist and Infection Control Construction Inspection Form.

Continuously monitor and document negative pressure levels. Maintain a written log of negative pressure levels measured to include date and time of the measurement.

All barriers and HEPA filtered negative pressure are to remain in place until clearance has been obtained from VAMC representatives. This could include the IC Department, Safety Department, and Environmental Services Department.

3.3.2 Tests

VAMC representatives may conduct post abatement and during abatement sampling for dust, mold spores and surface contamination. Sampling may be conducted for dusts outside the work area to assess impact.

3.4 CLEANING AND DISPOSAL

The construction area and adjacent areas are to be kept in a clean and sanitary manner, using damp methods and HEPA filtered vacuuming.

Dry sweeping shall not be allowed.

Any dust tracked outside of the barriers must be removed immediately and as it accumulates.

Surfaces are to be cleaned daily or more frequently if needed with VAMC approved cleaning products.

There shall be no standing water in the work area. All accidental spills must be cleaned up immediately and wet porous material removed within one hour.

Any water damaged areas scheduled for impact/demolition shall be removed first, under HEPA filtered exhaust and containment, with the waste promptly bagged, to reduce aerosol of microbial agent/fungi/spore from potentially escaping out of the work space.

All barriers are to be removed carefully to minimize the spread of contaminants.

Where feasible, the optimal method for removal of debris is via an exterior type chute to closed top containers.

Where not feasible, waste is to be removed in clean air tight covered containers and transported from the work area by a pre-determined route during off-peak hours. Such designated debris removal routes shall be cleaned by damp-mop and/or HEPA filtered vacuuming prior to being returned to patient/staff use.

For work performed exterior to the building envelope, no debris/waste movement shall be allowed through the building interior spaces.

-- End of Section --