

Philadelphia VA Medical Center
Replacement of AC-19 and Laboratory
Renovation
Philadelphia, PA 19104

March 16, 2012
Issued for 70% Review
VA Project No. VA244-P-1786
Array Project No. 3515

SECTION 09 06 00

SCHEDULE FOR FINISHES

VAMC:
Location:
Project no. and Name:
Submission
Date:

SECTION 09 06 00 - SCHEDULE FOR FINISHES

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

- A. Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

- A. Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES-provide quadruplicate samples for color approval of materials and finishes specified in this section.

Philadelphia VA Medical Center
Replacement of AC-19 and Laboratory
Renovation
Philadelphia, PA 19104

March 16, 2012
Issued for 70% Review
VA Project No. VA244-P-1786
Array Project No. 3515

1.4 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)
1. 2001 Architectural Painting Specification Manual

PART 2 - PRODUCTS

2.1 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

A. SECTION 06 20 00, FINISH CARPENTRY APPLIED MATERIALS

Finish code	MATERIAL	FINISH	Manufacturer	Mfg. Color Name/No.
PL-1	PLASTIC LAMINATE	MATTE	FORMICA	7919-78 AMBER CHERRY
SSP-1	SOLID SURFACE POLYMER	MATTE ½"	CORIAN	DOESKIN (F)
TS-1	LINOLEUM RESILIENT TACKABLE SURFACE	¼" GAUGE	FORBO	2182
GROMMETS	PLASTIC		DOUG MOCKETT & CO	BLACK
COUNTER BRACKET		WHITE	RAKKS	EH-1209 FOR USE ON COUNTERTOP 13"D

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

COUNTER BRACKET		WHITE	RAKKS	EH-1212 FOR USE ON COUNTERTOP 13"D
COUNTER BRACKET		WHITE	RAKKS	EH-1818 FOR USE ON COUNTERTOP 25"D
COUNTER BRACKET		WHITE	RAKKS	EH-1827 FOR USE ON COUNTERTOP 30"D

2.2 DIVISION 08 - OPENINGS

A. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	TRANSPARENT FINISH TO MATCH EXISTING
Frames	PT-2 AT NEW PAINT AREAS MATCH EXISTING AT AREAS REQUIRED TO BE TOUCHED UP

B. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
FRAME	PT-1 OR TO MATCH EXISTING SURROUNDING WALL PAINT

C. SECTION 08 33 00, SIDE FOLDING DOORS AND GRILLS

Component	Finish/Color
Doors	TRANSPARENT FINISH TO MATCH EXISTING
POCKET DOOR & FRAME	CUSTOM COLOR TO MATCH PT-2

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

D. SECTION 08 56 19, PASS WINDOWS

Room No. and Name	Finish	Glazing	Manufacturer	Manufacturer./Color Name/No.
		WIRED	FYRE TEC	CUSTOM COLOR TO MATCH PT-2
		LAMINATED		CUSTOM COLOR TO MATCH PT-2

E. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges		
Door Closers		
Floor Closers		
Closer/ Holder		
Floor Stops		

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

Door Holders		
Lock/ Latches		
Key Cabinet	Steel	
Armor Plates	Metal Plastic	
Kick Mop Plates	Metal Plastic	
Exit Device		
Door Pulls		
Push Plates		
Combination Push Pull Plate		

2.3 DIVISION 09 - FINISHES

A. SECTION 09 30 13, CERAMIC TILING

2. SECTION 09 30 13, PORCELAIN TILING		
Finish code	Manufacturer	Mfg. Color Name/No

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

PT-1	DALTILE	CITY VIEW, CY02 SKYLINE GRAY
------	---------	---------------------------------

8. SECTION 09 30 13, PORCELAIN TILE GROUT		
Finish Code	Manufacturer	Mfg. Color Name/No.
	LATICRETE	24 NATURAL GRAY

11. SECTION 09 30 13, METAL DIVIDER STRIPS		
Size	Material	Manufacturer
SCHIENE	ANODIZED ALUMINUM	SCHLUTER
JOLLY	ANODIZED ALUMINUM	SCHLUTER

2. SECTION 09 66 13, DIVIDER STRIPS			
Size	Material	Manufacturer	Manufacturer Number
	RUBBER	JOHNSONITE	SLT-XX

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

B. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
B. GR-1	EXPOSED SUSPENSION SYSTEM	WHITE	ARMSTRONG WORLD INDUSTRIES	PRELUDE 15/16"
B. C-1	TYPE IV	WHITE	ARMSTRONG WORLD INDUSTRIES	2X4 ULTIMA 1915
B. C-2	TYPE XX	WHITE	ARMSTRONG WORLD INDUSTRIES	2x4 CERAMAGUARD 608

B.

B.

C. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
C. SVCT-1	12"X12"	ESSENTIALS	MANNINGTON	143 FLAX
C. SVT-1	18"X18"	ASSURANCE SQUARED	MANNINGTON	16405 PUTTY
C. SVT-2	6"X36"	WOODLAND PATH	SHANNON SALES	57915 BLACK CHERRY AMBER

C.

D. SECTION 09 65 16, RUBBER SHEET FLOORING, HEAT WELDED SEAMS (SR)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
D. SR-1	ENVIRONCARE 2MM	NORA RUBBER	2946 MORNING

D.

SCHEDULE FOR FINISHES

090600 - 7

C.

D.

C.

D.

C.

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

			DEW
SR-2	ENVIRONCARE 2MM	NORA RUBBER	2933 WHISPERING FOG
SR-3	ENVIRONCARE 2MM	NORA RUBBER	2931 SMOKEY FENNEL

1. SECTION 09 65 16, WELDING RODS (SR)			
Finish code	Manufacturer		Mfg. Color Name/No.
	NORA RUBBER		TO MATCH FLOOR

2. SECTION 09 65 16, CAP STRIPS (SR)			
Finish Code	Manufacturer		Mfg. Color Name/No.
	NORA RUBBER		TO MATCH FLOOR

E. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB-1	Rubber Base (RB)	4"	JOHNSONITE	121 CEMENT CB

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

F. SECTION 09 68 00, CARPET MODULES (CPT)

Finish Code	Size	Pattern direction	Manufacturer	Mfg. Color Name/No.
CPT-1	50cm x 50cm	ASHLAR	MILLIKEN	SOUND & FURY, INTENSITY, IN305 MULTI TRACK

G. SECTION 09 67 23, EPOXY RESINOUS FLOORING (PE)

G. Finish code	G. Manufacturer	G. Mfg. Color Name/No.
G. PE-1	G. STONHARD	G. STONRES RTZ, SANTA FE

G.

G.

H. SECTION 09 91 00, PAINT AND COATINGS

G.

1. MPI Gloss and Sheen Standards

G.

G.	G.	Gloss @60	Gloss @85
Gloss Level 1	a traditional matte finish-flat	max 5 units and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units and	min. 35 units

G.

SCHEDULE FOR FINISHES

G.

G.

G.

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P-1	LEVEL 3	SHERWIN WILLIAMS	CREME SW7556
P-2	LEVEL 5	SHERWIN WILLIAMS	TAUPE TONE SW7633
P-3	LEVEL 3	SHERWIN WILLIAMS	SOFTENED GREEN SW6177
P-4	LEVEL 3	SHERWIN WILLIAMS	FRIENDLY YELLOW SW6680
EPT-1		SHERWIN WILLIAMS	TO MATCH PT-1

2.4 Division 10 - SPECIALTIES

A. SECTION 10 21 23, HOSPITAL CUBILCE CURTAINS AND INTRAVENOUS SUPPORT TRACKS

Finish Code	Manufacturer	Mfg. Color Name/No.
CC-1	MAHARAM	JAUNT 511440-001 SOLACE

Philadelphia VA Medical Center
Replacement of AC-19 and Laboratory
Renovation
Philadelphia, PA 19104

March 16, 2012
Issued for 70% Review
VA Project No. VA244-P-1786
Array Project No. 3515

CURTAIN TACK	IN PRO CORP	WHITE BAKED ACRYLIC ENAMEL
--------------	-------------	-------------------------------

B. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

B. Item	Material	Manufacturer	Mfg. Color Name/No.
B. Corner Guards			
B. CG-1	EXISTING	EXISTING TO BE RELOCATED	
B. CG-2	TO MATCH EXISTING	TO MATCH EXISTING	PARTIAL HEIGHT TO MATCH EXISTING ADJACENT
B.			

B. SECTION 10 44 13, MISCELLANEOUS SPECIALITIES

B. Room No. and B. CName	Item	Finish	Manufacturer	Mfg. Color Name/No.
B. C.	FIRE EXTINGUISHER B. CABINET			TO MATCH PT-1
B. C.				

Philadelphia VA Medical Center
Replacement of AC-19 and Laboratory
Renovation
Philadelphia, PA 19104

March 16, 2012
Issued for 70% Review
VA Project No. VA244-P-1786
Array Project No. 3515

2.5 DIVISION 12- FURNISHINGS

A. SECTION 12 31 00, METAL CASEWORK

Item/ Type	Finish	Manufacturer	Mfg. Color Name/No.
SHELVES	METAL	KEWAUNEE	DRIFTWOOD
CABINETS	METAL	KEWAUNEE	DRIFTWOOD
COUNTERS	RESIN	KEWAUNEE	SLATE KEMRESIN

Philadelphia VA Medical Center
Replacement of AC-19 and Laboratory
Renovation
Philadelphia, PA 19104

March 16, 2012
Issued for 70% Review
VA Project No. VA244-P-1786
Array Project No. 3515

PART 3 - EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Acoustical Ceiling	C
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet	CP
Carpet Athletic Flooring	CAF
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Ceramic Tile	CT
Concrete	C
Concrete Masonry Unit	CMU
Divider Strips Marble	DS MB
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E
Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

Fabric Wallcovering	WF
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Granite	GT
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Linear Wood Ceiling	LWC
Marble	MB
Material	MAT
Mortar	M
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL
Polypropylene Fabric Wallcovering	PFW
Porcelain Paver Tile	PPT
Quarry Tile	QT
Radiant Ceiling Panel	RCP

Philadelphia VA Medical Center
 Replacement of AC-19 and Laboratory
 Renovation
 Philadelphia, PA 19104

March 16, 2012
 Issued for 70% Review
 VA Project No. VA244-P-1786
 Array Project No. 3515

System	
Resilient Stair Tread	RST
Rubber Base	RB
Rubber Tile Flooring	RT
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC
Suspension Decorative Grids Grids	SDG
Terrazzo Portland Cement	PCT
Terrazzo Tile	TT
Terrazzo, Thin Set	
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC
Thin set Terrazzo	TST
Veneer Plaster	VP
Vinyl Base	VB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD

--- E N D---