


D1 FLOOR PLAN - AREA A PHASE 4
1/8" = 1'-0"



E1 BREAK ROOM 3B136A - ELEVATION
1/4" = 1'-0"

- ### INTERIOR ELEVATION KEYNOTES
- 1 PLASTIC LAMINATE FILLER PANEL.
 - 2 FINISH EXPOSED SIDE OF BASE CABINET WITH PLASTIC LAMINATE.
 - 3 PLASTIC LAMINATE END PANEL.
 - 4 PLASTIC LAMINATE FASCIA PANEL ABOVE WALL CABINET, TYPICAL.
 - 5 SOLID SURFACE WORK SURFACE.
 - 6 SOLID SURFACE TRANSACTION TOP.
 - 7 TACK PANEL.
 - 8 SCHEDULED BASE.
 - 9 GYPSUM WALL BOARD SOFFIT.

- ### ARCHITECTURAL KEYNOTES
- A1 REMOVE TEMPORARY ICRA WALL AT END OF PHASE. PATCH FLOOR, WALLS AND CEILING WITH NEW FINISHES TO MATCH ADJACENT SURFACES.
 - A2 PROVIDED 1HR STEEL DOOR WITH CLOSERS AND GASKETING TO PREVENT THE MOVEMENT OF DUST. PROVIDE DOOR HARDWARE TO HAVE PUSH BUTTON COMBINATION LOCK AND CORE FOR VAMC KEYING.
 - A3 FOLDING SECURITY GATE WITH POCKET AND POCKET DOOR.
 - A4 CONTRACTOR TO PROVIDE 4'-0" HIGH 3/4" FIRE TREATED PLYWOOD ON THE INSIDE OF EACH COMMUNICATION CLOSET. PLYWOOD TO START AT 3'-0" A.F.F.
 - A5 INFILL RECESSED FLOOR WITH HYDROLIC CEMENT UNDERSLABMENT TO MATCH EXISTING CONCRETE FLOOR. PATCH CEILING, WALLS AND FLOOR TO MATCH EXISTING ADJACENT SURFACES.
 - A6 TEMPORARY OPENING.
 - A7 RELOCATE EXISTING PNEUMATIC TUBE STATION TO TEMPORARY LOCATION.
 - A8 INSTALL NEW FLOOR FINISH. SEE FINISH PLANS.
 - A9 TEMPORARY SINK.
 - A10 INSTALL GWS ON EXISTING METAL STUD AS REQUIRED. TAPE, SPACKLE AND PAINT WALL TO MATCH EXISTING ADJACENT SURFACES.
 - A11 COORDINATE WORK IN THIS AREA TO ALLOW PUBLIC EGRESS DURING NORMAL BUSINESS HOURS.
 - A12 RENOVATE ICRA WALL AT THE END OF PHASE 4. ICRA WALL TO BECOME A PERMANENT HALF HEIGHT WALL. SEE PARTITION TYPES.
 - A13 RELOCATED FIRE EXTINGUISHER CABINET AND LIGHT.
 - A14 ONE LAYER TYPE "X" GWS.
 - A15 TEMPORARY LOCATION OF PNEUMATIC TUBE STATION. PROVIDE TEMPORARY ROUTING OF PIPING FROM EXISTING LOCATION. PROVIDE POWER TO THE STATION. SEE ELECTRICAL DRAWINGS.
 - A16 REPAIR EXISTING GWS SURROUNDING COLUMN AFTER DEMOLITION OF ADJACENT WALLS. COLUMN ENCLOSURE SHALL HAVE FLUSH SIDES ON ALL FOUR SIDES.
 - A17 RELOCATE PNEUMATIC TUBE STATION BACK TO ORIGINAL LOCATION PRIOR TO PHASE 2. COORDINATE WITH OWNER.
 - A18 PROVIDE PLYWOOD BACKER BOARD. COORDINATE SIZE AND LOCATION WITH EQUIPMENT MANUFACTURER.
 - A19 PROVIDE 1 1/2" CORE THROUGH FLOOR WITH METAL SLEEVE. SEE DETAIL E1A131A. COORDINATE LOCATION WITH EQUIPMENT MANUFACTURER.
 - A20 PROVIDE 3/4" CORE THROUGH FLOOR WITH METAL SLEEVE. SEE DETAIL E1A131A. COORDINATE LOCATION WITH EQUIPMENT MANUFACTURER.

- ### ARCHITECTURAL FLOOR PLAN GENERAL NOTES
1. DO NOT SCALE DRAWINGS. DIMENSIONS IN LARGE SCALE PLANS, ELEVATIONS, AND DETAILS SHALL GOVERN OVER SMALL SCALE DETAILS. IF DIMENSIONS ARE IN QUESTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE ARCHITECT BEFORE CONTINUING WITH CONSTRUCTION.
 2. DIMENSIONS SHOWN ON THE FLOOR PLANS FOR NEW CONSTRUCTION ARE TO CENTERLINE OF COLUMNS TO FINISH FACE OF INTERIOR PARTITION, CONCRETE OR MASONRY INTERIOR WALLS AND TO EXTERIOR FACE EXTERIOR WALLS.
 3. DIMENSIONS SHALL BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION OF CASEWORK. REFER TO CASEWORK NOTES FOR ADDITIONAL INFORMATION.
 4. CONTRACTOR SHALL BE RESPONSIBLE FOR LATEXING AND TAPERING EXISTING CONCRETE FLOOR SLAB WHERE MATERIAL CHANGES OCCUR AND SHALL COORDINATE SAME WITH INSTALLER.
 5. PROVIDE METAL STUD FRAMING AROUND ALL PENETRATIONS THRU METAL STUD PARTITIONS.
 6. ALL FURNITURE & FURNITURE PANELS ARE N.I.C., UNLESS OTHERWISE NOTED.

- ### CASEWORK GENERAL NOTES
1. SEE SHEET AE-230 FOR ADDITIONAL CASEWORK DETAILS.
 2. PROVIDE 1/4" REVEAL WHERE RECEPTION DESK MEETS THE WALL.
 3. COORDINATE ALL CLEARANCES WITH EQUIPMENT.
 4. REFER TO FINISH LEGEND, SHEET AF-130 FOR ADDITIONAL FINISH INFORMATION.
 5. ALL CASEWORK TO BE PL-1 U.N.O. ALL COUNTERTOPS TO BE SSP-1 U.N.O.

- ### PARTITION PLAN INDICATIONS
- | | |
|-------|--|
| --- | EXISTING PARTITION TO BE REMOVED |
| ===== | EXISTING PARTITION TO REMAIN |
| ----- | EXISTING ONE HOUR FIRE RATED PARTITION |
| ----- | EXISTING ONE HOUR SMOKE BARRIER |
| ----- | EXISTING TWO HOUR FIRE RATED PARTITION |
| ----- | EXISTING TWO HOUR SMOKE BARRIER |
| ----- | TEMPORARY PARTITION |
| ----- | TYPICAL FURRING |
| ----- | TYPICAL NON RATED PARTITION |
| ----- | TYPICAL NON RATED SMOKE PARTITION |

FULLY SPRINKLERED
ISSUED FOR BID

CONSULTANTS: Lab Consultant: HERA MEP Engineer: H.F. Lenz 230 S. Broad Street, Suite 201 Philadelphia, PA 19102 Tel: (215) 670-5333 Fax: (215) 670-5334 1407 Scalp Avenue Johnstown, PA 15004 Tel: (814) 269-9966 Fax: (814) 269-9901		KEY PLAN: AREA A BUILDING 2	ARCHITECT:  ARRAY healthcare facilities solutions 2520 Renaissance Boulevard, Suite 110 King of Prussia, PA 19406 t: 610.270.0599 f: 610.270.0995 www.arrayhfs.com	Project Number 3515	Scale As indicated	Drawing Title THIRD FLOOR PLAN - PHASE 4	Project Title REPLACEMENT OF AC-19 AND LABORATORY RENOVATION	VA Project Number VA244-P-1786 Building Number 2	Office of Facilities Management 
Revisions Date						Approved: Project Director	Location 3900 WOODLAND AVENUE PHILADELPHIA, PA 19104	Drawing Number AE-134A	
							Date 04-12-2012	Checked WJ	Drawn EN
								Dwg. of	