

[illegible]

FACE OF VENEER AT EXTERIOR WALL, TYP.  
 PREFINISHED GASKETED FASTENER AT 12" O.C., TYP.  
 PREFINISHED METAL FLASHING, PROVIDE  
 CONTINUOUS SEALANT AT TOP EDGE, TYP.  
 2"x2"x3/16" PREFINISHED ALUMINUM TUBE W/ END CAPS,  
 ANCHOR TO BRACKET WITH (2) COUNTERSUNK #12  
 STAINLESS STEEL SCREWS AT EACH BRACKET, TYP.  
 Z CLOSURE, ANCHOR TO 2"x2" TUBE TYP.  
 EPOXY ANCHOR THRU ANCHOR PLATE HOLE AT EACH SIDE  
 INTO CENTER (+/- 1/2") OF HORIZONTAL BRICK VENEER  
 COURSE AND MINIMUM 2" MINIMUM FROM HEAD JOINT WITH  
 1/2" DIAMETER X 3' LONG STAINLESS STEEL THREADED ROD,  
 SECURE BRACKET TO THREADED ROD WITH PREFINISHED  
 STAINLESS STEEL WASHER AND CAP NUT, TYP.  
 PREFINISHED STANDING SEAM METAL ROOF  
 PANEL (PREFINISHED TOP AND BOTTOM SIDE OF  
 PANEL), PROVIDE CONCEALED ROOF CLIPS AT  
 EACH 2"x2" TUBE  
 PREFINISHED METAL FLASHING AND  
 CONTINUOUS CLEAT  
 2"x2"x3/16" PREFINISHED ALUMINUM TUBE BRACKET W/ END CAPS  
 AND 2"x3"x3/8" ANCHOR PLATES (1-PIECE WELDED ASSEMBLY)

6 AS202  
 7 AS202  
 12  
 1'-3"  
 1'-6"  
 3/8" TYP  
 2"  
 8"  
 1'-6"  
 6 3/4"  
 7'-10"  
 2'-11 3/4"  
 6'-4"  
 3'-0"  
 1'-7"  
 6  
 1'-7"  
 3/8" RD

4 SHADING CANOPY SECTION - TYPE B  
AS202 1 1/2" = 1'-0"

	<p><b>ARCHITECT/ENGINEERS:</b></p> <div data-bbox="1383 1875 1564 1898">  </div> <div data-bbox="1578 1881 1676 1892"> <p>BES DESIGN/BUILD 766 Middle St. Phone: 251.990.1111</p> </div>
---	---

PROJECT NO.: 51.990.3716 PROJECT NAME: AL 36532 PROJECT LOCATION: 51.990.3716	Drawing Title <b>EXTERIOR ELEVATIONS, NORTH AND EAST</b>
	Approved: Project Director

Project Title <b>PANAMA CITY JOINT OUTPATIENT CLINIC VA GULF COAST HEALTH CARE</b>			Project Number <b>520-326</b>	
Location <b>PANAMA CITY, FLORIDA</b>			Building Number <b>-</b>	
			Drawing Number <b>AS202</b>	
Date <b>MARCH 2012</b>	Checked <b>BM</b>	Drawn <b>TWIMF</b>	Dwg. 16 of 42	

Office of  
Construction  
and Facilities  
Management



Department of  
Veterans Affairs

\_RAC2012\Projects\132711-01\_BES\_JOPC\_walls.rvt  
 3/26/2012 10:02:07 AM  
 one eighth inch = one foot      one quarter inch = one foot      three eighths inch = one foot      one half inch = one foot      one inch = one foot  
 1/8"      1/4"      3/8"      1/2"      1"

\\rac2012\Projects\132711-01\_BES\_JOPC\_vallis.mt

VA FORM 08-6231