# EQUIPMENT NOTES

1. EQUIPMENT SHOWN IS GENERAL PATIENT TREATMENT RELATED FOR BUILDING DESIGN COORDINATION. STANDARD OFFICE EQUIPMENT IS NOT SHOWN (I.E. PC'S, FAX, PRINTERS, ETC.)

2. FURNITURE IS SHOWN FOR COORDINATION WITH EQUIPMENT AND GENERAL ROOM LAYOUTS ONLY.

3. SEE SHEET AS402 FOR EQUIPMENT SCHEDULE.

4. ALL PC'S (VV) SHOWN ON EQUIPMENT PLANS ARE FOR GENERAL LAYOUT PURPOSES AND PLANNING ONLY. IT DOES NOT INCLUDE EXACT SIZE, SHAPE, AND/OR NUMBER OF SCREENS TO BE USED.

5. NURSE CALL STATIONS SHOWN FOR GENERAL LAYOUT PURPOSES AND NOT ALL MAY BE SHOWN THAT IS REQUIRED. REFER TO TN DRAWINGS FOR NURSE CALL STATION LOCATIONS REQUIRED.

6.PROVIDE BLOCKING IN WALLS FOR CORNER GUARDS, TV BRACKETS, TOILET ACCESSORIES, AND OTHER WALL MOUNTED ITEMS.

EQUIPMENT SCHEDULE

| EQUIPMENT # | ACQ/INSTALL | JSN NUMBER | DESCRIPTION |
|---|---|---|---|
| 1 | CC | - | COMPRESSED AIR VALVE, SEE PLUMBING |
| 2 | VV | - | MODULAR WORKSTATION |
| 3 | VV | - | CENTRIFUGE |
| 4 | VV | - | UNDER COUNTER FREEZER |
| 5 | VV | - | WALL MOUNTED X-RAY (SURFACE MOUNTED) |
| 6 | VV | - | DENTAL EXAM CHAIR (BASIS OF DESIGN A-DEC 511 DENTAL CHAIR) |
| 7 | VV | - | MODULAR DENTAL TREATMENT CONSOLE (BASIS OF DESIGN A-DEC 5580.42 TREATMENT CONSOLE) |
| 8 | VV | - | MODULAR CABINETS WITH SINK |
| 9 | CC | - | WALL MOUNTED RACK, APRON/GLOVES (BASIS OF DESIGN KAPPA MEDICAL, MODEL #821 OR EQUAL) |
| 10 | VV | - | CHEMICAL ANALYZER AND PC CONTROL TERMINAL (BASIS OF DESIGN; DxC 600 & PC TERMINAL) |
| 11 | CC | - | EMERGENCY POWER OFF, SEE ELECTRICAL |
| 12 | VV | - | MODULAR DENTAL UPPER WALL CABINET (BASIS OF DESIGN A-DEC 5731.34 WALL MOUNT/WALL-INSERT) |
| 13 | CC | - | FLUSH VERTICAL WALL DUCT WITH COVER, SEE ELECTRICAL |
| 14 | CC | - | WALL HUNG SHELVES |
| 15 | VV | - | WALL SCRUBBER |
| 16 | CC | F3050 | DRY ERASE WHITEBOARD |
| 17 | VV | - | REMOTE X-RAY SWITCH |
| 18 | VV | - | EXISTING ASSISTANT STOOL (RELOCATED FROM EXISTING VA FACILITY) |
| 19 | VV | - | EXISTING DENTIST INSTRUMENT STATION (RELOCATED FROM EXISTING VA FACILITY) |
| 20 | CC | A5135 | MOP RACK WITH SHELF |
| 21 | CC | | DOUBLE COAT HOOK (CLOTHES HOOK) |
| 22 | CC | A5165 | METAL SHELF (6" X 18") |
| 23 | CC | CD040 | WALL CABINET |
| 24 | CC | CT030 | COUNTERTOP WORK SURFACE |
| 25 | VC | - | TRACK MOUNT LIGHT (EXISTING RELOCATED) |
| 26 | VV | - | MODULAR DENTAL UPPER WALL CABINET DISPENSING UNIT - GLOVES, PAPER TOWELS, & MASKS(BASIS OF DESIGN A-DEC 5730.29 DISPENSING UNIT) |
| 27 | VV | E0210 | MODULAR WORKSTATION |
| 28 | VV | E0912 | SUPPLY STORAGE LOCKER |
| 29 | VV | E0945 | CLEAN UTILITY MOBILE CART |
| 30 | VV | E0948 | GENERAL STORAGE CART |
| 31 | VV | F0205 | AUTO STORAGE CABINET |
| 32 | VV | F0500 | SUPPLY CART |
| 33 | VV | F0510 | SOILED LINEN CART |
| 34 | VV | F0515 | LINEN SUPPLY CART |
| 35 | VV | F0535 | UTILITY CART |
| 36 | CC | F3010 | BULLETIN BOARD |
| 37 | VV | M7401 | PORTABLE EXAM LIGHT |
| 38 | VV | M1801 | PC, KEYBOARD, TRAY, AND FLAT PANEL MONITOR |
| 39 | VV | - | MODULAR WORKSTATION |
| 40 | VV | M1840 | COMBO PRINTER/FAX MACHINE |
| 41 | VV | M2005 | ACID STORAGE CABINET |
| 42 | VV | M2020 | VENTED SAFETY STORAGE CABINET |
| 43 | VV | M2050 | MOBILE SHELVING |
| 44 | VV | M2070 | STORAGE SHELVING |
| 45 | VV | M2650 | FLOOR SCRUBBING MACHINE |
| 46 | VV | M3070 | MOBILE HAMPER |
| 47 | VV | M3085 | INSTRUMENT CABINET |
| 48 | VV | M4100 | SPHYGMOMANOMETER |
| 49 | VV | M4116 | VITAL SIGN MONITOR |
| 50 | VV | M4125 | RADIO COMMUNICATION SYSTEM |
| 51 | VV | M4200 | OTOSCOPE/ OPHTHALMOSCOPE |
| 52 | VV | M4255 | IV STAND |
| 53 | VV | M4655 | STRETCHER |
| 54 | VV | M7710 | ELECTROCARDIOGRAPH AND ROLLING CART |
| 55 | VV | M8320 | TREATMENT TABLE |
| 56 | VV | M9050 | EXAM ROOM TABLE |
| 57 | VV | P2450 | THERMOSTATIC MIXING VALVE |
| 58 | VV | - | RADIOLOGY BUCKY |
| 59 | VV | X2100 | ULTRASOUND SCANNER |
| 60 | VV | X3155 | MOBILE APRON AND GLOVES RACK |
| 61 | VV | X3930 | X-RAY ILLUMINATOR (SURFACE MOUNTED) |
| 62 | VV | X6185 | RADIOLOGY FLUOROSCOPIC UNIT - TABLE |
| 63 | VV | - | RADIOLOGY FLUOROSCOPIC UNIT - WORKSPOT EQUIPMENT |
| 64 | VV | - | EXISTING ASSISTANT INSTRUMENT STATION |
| 65 | VV | - | MICROSCOPE |
| 66 | VV | - | EXISTING DOCTOR'S STOOL |
| 67 | VV | M9066 | GYNOCOLOGY EXAM TABLE |
| 68 | CC | - | NURSE CALL, REFER TO TN DRAWINGS |
| 69 | CC | - | OXYGEN VALVE, SEE PLUMBING |
| 70 | CC | - | 14" X 14" PACKAGE RECEIVER |
| 71 | VV | - | PERSCRIPTION DISPENSING UNIT (BASIS OF DESIGN; SCRIPTPRO SP 200 WITH OPEN CONTROL CENTER) (RELOCATED FROM EXISTING PHARMACY) |
| 72 | VV | - | PORTABLE EXAM LIGHT |
| 73 | VV | - | HOMOSTASIS SYSTEM - (BASIS OF DESIGN; STAGO STA) |
| 74 | VV | - | GLYCOHEMOGLOBIN ANALYZER (BASIS OF DESIGN; TOSOH AIC AND PC CONTROL TERMINAL) |
| 75 | VV | - | URINALYSIS |
| 76 | CC | - | VACUUM VALVE, SEE PLUMBING |
| 77 | VV | | WEAPONS, EVIDENCE, GUN BOX STORAGE LOCKER |
| 79 | VV | | MOBILE CART, SHELVING AND STOARGE |

EQUIPMENT SCHEDULE

| EQUIPMENT # | ACQ/INSTALL | JSN NUMBER | DESCRIPTION |
|---|---|---|---|
| 80 | VV | | SINK PROVIDED IN MODULAR CASEWORK |
| 82 | VV | - | WEAPONS CLEARING BARREL |
| 83 | VV | - | MODULAR CABINET WITH SINK (BASIS OF DESIGN ADEC #5531-30) |
| 84 | CC | - | X-RAY ON/OFF WARNING LIGHT |
| 85 | VV | M4655 | STRETCHER |
| 86 | CC | - | EMERGENCY SHOWER AND EYEWASH |
| 87 | VV | - | FLAMMABLE STORAGE CABINET |
| 88 | VV | - | BIO, RADIO/PHARMACY REFRIGERATOR (58" W x 36" D) |
| 89 | VV | - | EXISTING DENTAL EXAM CHAIR |
| 90 | VV | - | HEMOTOLOGY ANALYZER AND PC CONTROL TERMINAL (BASIS OF DESIGN; BECKMAN COULTER LH 500) |
| 91 | VV | - | BLOOD DRAW CHAIR |
| 92 | CC | | MODULAR CASEWORK/WORKSTATION - 30" DEEP BASE WITH COUNTERTOP |
| 93 | CC | - | CEILING MOUNTED CURTAIN TRACK ASSEMBLY - PRIVACY CURTAIN IS BY VA (VV) |
| 94 | VV | - | 3D PANORAMIC X-RAY (BASIS OF DESIGN; PLANMECA PROMAX 3D 8X8 PAN WITH SP (W/O PAN SENSOR) |
| 95 | VV | | UNDERCOUNTER REFRIGERATOR |
| 96 | VV | - | UNDER COUNTER FREEZER |
| 97 | VV | - | RETINAL CAMERA |
| 98 | VV | | REFRIGERATOR |
| 99 | VV | - | MEDICATION CONTROL SYSTEM AND RACK - OMNI CELL |
| 100 | VV | - | FLAMMABLE STORAGE, 23"W X 18" D X 35" H (PHARMACY) |
| 101 | VV | - | CORROSION STORAGE, 23"W X 18" D X 35" H (PHARMACY) |
| 102 | VV | - | TELEHEALTH EQUIPMENT CART |
| 103 | VV | - | MEDICATION LOCKER |
| 104 | VV | - | CLEAR EYE CHART |
| 105 | VV | - | UNDER COUNTER REFRIGERATOR |
| 106 | VV | - | UNDER COUNTER FREEZER |
| 107 | VV | - | DESKTOP PERSONAL COMPUTER WITH KEYBOARD AND TRAY |
| 108 | VV | - | ADJUSTABLE INSTRUMENT TABLE |
| 109 | VV | - | REFRIGERATOR - 52" X 30" |
| 110 | VV | - | UNDER COUNTER REFRIGERATOR |
| 111 | VV | - | DI WATER UNIT |
| 113 | VV | - | REFRIGERATOR |
| 116 | VV | - | RADIOLOGY FLUOROSCOPIC UNIT - CONTROL CABINET |
| 117 | VV | - | ASSISTANT STOOL (BASIS OF DESIGN CASCADE 1622 ASSISTANT'S STOOL) |
| 118 | VV | - | DOCTOR'S STOOL (BASIS OF DESIGN CASCADE 1601 DOCTOR'S STOOL) |
| 119 | VC | - | TRACK MOUNT LIGHT (CEILING MOUNTED) (BASIS OF DESIGN GENDEX 6300 TRACK MOUNT DENTAL LIGHT) |
| 120 | VV | - | DENTIST INSTRUMENT STATION (BASIS OF DESIGN A-DEC 532 TRADITIONAL DELIVERY SYSTEM) |
| 121 | VV | - | DENTAL MONITOR MOUNT (BASIS OF DESIGN A-DEC 561 MONITOR MOUNT) |
| 122 | VV | - | ASSISTANT INSTRUMENT STATION (BASIS OF DESIGN A-DEC 545 12 O'CLOCK ASSISTAN'S INSTRUMENTATION) |
| 123 | VV | - | DESKTOP PERSONAL COMPUTER WITH KEYBOARD AND TRAY |
| 124 | VV | - | PC, KEYBOARD, TRAY, AND FLAT PANEL MONITOR |
| 125 | VV | - | PC, KEYBOARD, TRAY, AND FLAT PANEL MONITOR |
| 126 | VV | - | PC, KEYBOARD, TRAY, AND FLAT PANEL MONITOR |
| 127 | VV | - | MODULAR STERILIZATION CENTER CABINET WITH SINK (BASIS OF DESIGN; A-DEC 5590) |
| 128 | CC | - | MODULAR CASEWORK/WORKTABLE |
| 129 | CC | - | MODULAR CASEWORK/WORKSTATION |
| 130 | | - | MODULAR CASEWORK - 12" DEEP UPPER |
| 131 | CC | - | MODULAR CASEWORK - OPEN SHELVING |
| 132 | CC | - | MODULAR CASEWORK - 24" DEEP BASE WITH COUNTERTOP |
| 133 | CC | - | MODULAR CASEWORK - 18" DEEP BASE WITH COUNTERTOP |
| 134 | CC | | MODULAR CASEWORK - OPEN SHELVING |
| 135 | CC | - | MODULAR CASEWORK- 24" DEEP BASE W/ COUNTERTOP |
| 136 | CC | - | MODULAR CASEWORK |
| 137 | CC | - | FULL HEIGHT STORAGE |
| 138 | CC | | MODULAR CASEWORK - OPEN SHELVING |
| 139 | CC | | MODULAR CASEWORK - OPEN SHELVING |
| 140 | VV | - | COFFEE MAKER |
| 141 | CC | | MODULAR CASEWORK - OPEN SHELVING |
| 142 | CC | | MDULAR CASEWORK - WORKSTATION |
| 143 | VV | - | X-RAY READING STATION |
| 144 | VV | - | HOT DOG WARMER |
| 146 | CC | | TOILET TISSUE DISPENSER (DOUBLE ROLL) |
| 147 | CC | | TOILET TISSUE DISPENSER (DOUBLE ROLL) |
| 149 | | A5075 | SOAP DISPENSER (WALL MOUNTED) |
| 150 | CC | | GRAB BAR (42" LONG) |
| 151 | CC | | GRAB BAR (36" LONG) |
| 152 | VV | | TRASH CAN |
| 153 | CC | | SANITARY NAPKIN DISPOSAL |
| 154 | CC | | SHOWER GRAB BAR (L SHAPED) |
| 155 | CC | | SHOWER FOLDING SEAT |
| 156 | CC | | FOLDING SEAT |
| 157 | | A5080 | PAPER TOWEL DISPENSER |
| 159 | CC | - | METAL SHELF (18" X 6") |
| 160 | CC | - | DOUBLE COAT HOOK |
| 161 | CC | A1066 | MIRROR (24" X 36") |
| 162 | CC | | SHOWER CURTAIN AND ROD |
| 163 | CC | | SOLID SURFACE CORNER SOAP DISH AND CORNER SHAMPOO SHELF |
| 164 | VV | - | REFRIGERATOR |
| 165 | VV | | MICROWAVE |
| 166 | CC | | DIAPER CHANGING STATION (BASIS OF DESIGN KB200 KOALA HORIZONTAL) |

FINAL SUBMISSION

| Revisions: | Date |
|---|---|
| | |

## CONSULTANTS:

CIVIL:
KENNETH HORNE & ASSOCIATES
7201 NORTH 9TH AVENUE, STE. 6
PENSACOLA, FLORIDA 32504
PH: (850) 471-9005
FX: (850) 471-0093

COMM/DS:
SCHMIDT CONSULTING GROUP, INC.
139 EAST GOVERNMENT STREET
PENSACOLA, FLORIDA 32502
PH: (850) 438-0050
FX: (850) 432-8631

SURVEYORS:
KCI TECHNOLOGIES, INC.
10401 HIGHLAND MANOR DRIVE, SUITE 120
TAMPA, FLORIDA 33610
PH: (813) 740-2300

LANDSCAPE ARCHITECT:
CSA GROUP, INC.
6300 PICCADILLY SQUARE DRIVE
MOBILE, ALABAMA 36609
PH: (251) 344-4023
FX: (251) 344-4052

ARCHITECTURE:
BULLOCK TICE ASSOCIATES, INC.
909 EAST CERVANTES STREET
PENSACOLA, FL 32501
PH: (850) 434-5444
FX: (850) 432-5208

STATE OF FLORIDA
ROBERT G. MAGGIORE
0013571
29 march 2012
REGISTERED ARCHITECT

## ARCHITECT/ENGINEERS:

BES DESIGN/BUILD

BES DESIGN/BUILD, LLC
766 Middle St, Fairhope, AL 36532
Phone: 251.990.5778 Fax: 251.990.3716

Drawing Title: EQUIPMENT SCHEDULE

Approved: Project Director

Project Title: PANAMA CITY
JOINT OUTPATIENT CLINIC
VA GULF COAST HEALTH CARE

Location: PANAMA CITY, FLORIDA

Date: MARCH 2012 | Checked: BM | Drawn: TW/MF

Project Number: 520-326

Building Number: -

Drawing Number: AS402

Dwg. 25 of 42

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08 - 6231

D:_RAC2012_rojects\132711-01_BES_JOPC_walls.rvt
3/26/2012 10:02:39 AM
three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot