



FUTURE SCHEDULE						
ITEM	DESCRIPTION	CW	HW	WASTE	VENT	REMARKS (SEE NOTE)
P-103	WATER CLOSET	1"	–	3"	2"	ADA COMPLIANT. WHITE. WALL MOUNT. ELONGATED. 1.28 GPF. TOP SPUD. AMERICAN STANDARD. WITH SLOAN EXPOSED INFERRED FLUSH VALVE AND ELONGATED OPEN FRONT SEAT.
P-201	URINAL	3/4"	–	2"	1 1/2"	ADA COMPLIANT. WHITE. 0.125 GPF. AMERICAN STANDARD. WITH SLOAN EXPOSED INFERRED FLUSH VALVE.
P-405	LAMINATORY, COUNTERTOP	3/8"	3/8"	1 1/2"	1 1/2"	OVAL BASIN W/ OVERFLOW, UNDERCOUNTER, VITREOUS CHINA, ADA COMPLIANT, AMERICAN STANDARD, WITH BATTERY POWERED ELECTRONIC FAUCET. AMERICAN STANDARD 6055.165.
P-414	LAMINATORY, STRAIGHT BACK	3/8"	3/8"	1 1/2"	1 1/2"	LAMINATORY, STRAIGHT BACK, VITREOUS CHINA, AMERICAN STANDARD. WITH BATTERY POWERED ELECTRONIC FAUCET. AMERICAN STANDARD 6055.165.
P-418						**DELETED**
P-502	SERVICE SINK	1"	1"	3"	1 1/2"	TERRAZZO TOP SERVICE SINK (CORNER). 28"x28"x6" VACUUM BREAKER WITH T&S BRASS SERVICE SINK FAUCET.
P-505	CLINIC SERVICE SINK	1"	–	3"	2"	WALL MOUNTED VITREOUS CHINA, TOP SPUD, AMERICAN STANDARD. WITH 1.28 GPF SLOAN EXPOSED MANUAL FLUSH VALVE AND T&S BRASS SERVICE SINK FAUCET.
P-528	SINK, CRS	3/8"	3/8"	1 1/2"	1 1/2"	SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH BATTERY POWERED ELECTRONIC FAUCET. AMERICAN STANDARD 6055.165.
P-529	LAB SINK, CRS	3/8"	3/8"	1 1/2"	1 1/2"	SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH BATTERY POWERED ELECTRONIC FAUCET. AMERICAN STANDARD 6055.165 & FOOT CONTROLS.
P-529A	LAB SINK, CRS W/ EYE WASH	3/8"	3/8"	1 1/2"	1 1/2"	SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH BATTERY POWERED ELECTRONIC FAUCET. AMERICAN STANDARD 6055.165, FOOT CONTROLS & DECK MOUNTED EYE WASH STATION, GIBRAN 6920 OR EQ.
P-604	ELECTRIC WATER COOLER	3/8"	–	1 1/2"	1 1/2"	BI-LEVEL HEAVY DUTY 14 GALLON DRINKING FOUNTAIN, WALL MOUNT, FULLY EXPOSED, BARRIER-FREE ACCESS MODEL (OR APPROVED EQUAL).
P-703	SHOWER	1/2"	1/2"	2"	2"	LOW-FLOW SHOWER HEAD, WALL MOUNTED, 1.5 GPM, CHROME FINISH WITH TYPE T/TP THERMOSTATIC AND PRESSURE BALANCING VALVES AND TRIM, TERRAZZO SHOWER PANS, ADA ACCESSIBLE.
P-705	THERMOSTATIC MIXING VALVE	3/4"	3/4"	–	–	WALL MOUNTED, THERMOMETER AND HOSE ASSEMBLY.
P-708	EMERGENCY EYE & FACE WASH	1/2"	1/2"	1 1/4"	–	WALL MOUNTED, FOOT PEDAL CONTROL, RECEPTOR W/ DRAIN PLUG MIXING VALVE & PREF. STRAINER.
P-801	WALL HYDRANT	3/4"	–	–	–	STANDARD BRASS, 3/4" MHT, FROST-PROOF WITH VACUUM BREAKER BACKFLOW PREVENTOR.
P-900	ICE MAKER	1/4"	–	–	–	SLOUX CHIEF 666–1000WF OX BOX ICE MAKER OUTLET BOX.
P-901	COFFEE MAKER	1/4"	–	–	–	BLINN (MODEL NOT INDICATED).
P-902	DEIONIZED WATER SYSTEM	1/2"	–	–	–	OWNER FURNISHED, CONTRACTOR INSTALLED.
FD	FLOOR DRAIN	–	–	3"	–	SLOUX CHIEF 832–36PRN "FINISH LINE" ADJUSTABLE FLOOR DRAIN W/ TRAP PRIMER CONNECTION W/ 45 GPM 4" DEEP SEAL TRAP AND AUTOMATIC TRAP PRIMING VALVE.
HD	HUB DRAIN	–	–	3"	–	SLOUX CHIEF 832–36RF/832–44HD "FINISH LINE" ADJUSTABLE HUB DRAIN.

DENTAL OPERATORIES FIXTURE SCHEDULE						
ITEM	DESCRIPTION	CW	HW	WASTE	VENT	REMARKS (SEE NOTE)
P-A01L	MODULAR DENTAL CABINET WITH SINK	1/2"	1/2"	1/2"	1/2"	LEFT-SIDE CONSOLE 72", A-DEC MODEL 5531.72, WALL MOUNTED UTILITY CONNECTIONS
P-A01R	MODULAR DENTAL CABINET WITH SINK	1/2"	1/2"	1/2"	1/2"	RIGHT-SIDE CONSOLE 72", A-DEC MODEL 5531.72, WALL MOUNTED UTILITY CONNECTIONS
P-A02	MODULAR DENTAL TREATMENT CONSOLE	1/2"	-	-	-	12 O'CLOCK CONSOLE 42", A-DEC MODEL 5580.42, WALL MOUNTED UTILITY CONNECTIONS
P-A03	DENTAL EXAM CHAIR	1/2"	-	-	-	A-DEC MODEL 511, FLOOR BOX UTILITY CONNECTIONS
P-A04	MODULAR CABINET WITH SINK	1/2"	1/2"	1/2"	1/2"	ACCESSORY CONSOLE 30", A-DEC MODEL 5531-30, WALL MOUNTED UTILITY CONNECTIONS
P-A05	MODULAR CABINET STERILIZATION CABINET	1/2"	1/2"	1/2"	1/2"	STERILIZATION CABINET, A-DEC MODEL 5590, WALL MOUNTED UTILITY CONNECTIONS

SOLAR WATER HEATER SCHEDULE						
MARK	STORAGE GALLONS	BACK-UP ELECTRICAL ELEMENTS			BASIS OF DESIGN	NOTES
		NO.	KW EA.	V		
EW-1	119	1	4.5	240	SUPERSTOR MODEL SSU-119SE	2 REQUIRED

SOLAR PANELS					
DESCRIPTION	QTY.	TRANSPARENT AREA EA.	WORKING PRESSURE	FLOW RATE	BASIS OF DESIGN
SOLAR PANEL COLLECTOR	5	39.7 SF	165 PSI	0.5-1.8 GPM (RECOMMENDED)	SOLAR SPECTRUM MODEL PP-40SC

DRAIN-BACK TANK SCHEDULE					
MARK	DESCRIPTION	QTY.	CAPACITY	BASIS OF DESIGN	NOTES
DB-1	DRAIN-BACK TANK	1	15 GALLON	HIP MODEL NO. SSU-150B	

RECIRCULATION PUMP SCHEDULE						
MARK	SERVICE	GPM	ELECTRICAL	HP	BASIS OF DESIGN	REMARKS
RP-1	HOT WATER RECIRCULATION	7	115V, 60Hz, 1 PH	1/40	TACO MODEL 003-ST4	THE CONTROLLER TO BE TIED INTO DDC

[illegible]