

Remove Underground Fuel Storage Tanks
Solicitation No. 36C24418B0578
Amendment 0002

Clarification Specification Section 312000 Earthwork

Throughout 3 locations, trees are to be removed. These trees are within a 10 foot radius of the respective tanks and will have their foundation weakened when the tanks are removed. These trees will be completely removed from the premises, stumps will be ground down to at least 6" below the surface, chippings are to be removed, a minimum of 6" of topsoil, seed, and straw netting is to be installed. Two flowering trees (common and indigenous and approved by the COR) to every tree removed shall be replanted with a two year warranty of survival. All disturbed turf will be properly leveled, top-soiled, seeded, and straw netted. Trees are to be removed in pieces as opposed to "felling" the tree. All OSHA safety standards shall be adhered to including a thorough crane lift plan to be submitted through the COR prior to any start of tree removal. After hours work may be necessary.

At building 100, there are two (plus) trees to be removed. One of the two trees is a double tree and shall be considered two trees for bidding purposes. Therefore, there are three (3) trees to be removed at building 100 with respect to the instructions stated above.

At building 81, there are two trees to be removed with respect to the instructions listed above.

At building 79, one tree is to be removed with respect to the instructions listed above.