

Questions and Answers

Renovate Building 6 Gymnasium

VA246-12-B-2837

1. Spec section 114860 Gym Protection Accessories part 2.2 B. says, “see drawing A-101” however I do not find this sheet in the posted plans. Can you issue this sheet?

ANSWER: Drawing will be re-issued.

2. Spec section 114840 Gym Dividers, the length of this divider curtain is not clearly indicated. What is the length of the gym divider curtain?

ANSWER: The length of the gym divider is to cover the full width of the gym.

3. Please confirm how many new basketball backstops are required.

ANSWER: Refer to Drawing A-101 Key Notes Item 12 in relationship to the drawing you shall find that the requirement is for 6 basketball goals. Also noted is GSA-GS-07F-9030G or equivalent which is taken from GSA Advantage Website. See below:

CONVERSION BASKETBALL BACKBOARD 42X72

Mfr Part No.: BA42XLC

Contractor Part No.: BA42XLC

Manufacturer: BISON

Contract No.: GS-07F-0215J (ends: Apr 30, 2014)

MAS Schedule/SIN: 078/192 02

Warranty: STANDARD WARRANTY

Made In: UNITED STATES OF AMERICA

Weight: 217.000 LB

4. Please confirm how many new floor sleeves are required.

ANSWER: Eight Floors Sleeves in relationship to drawing A-103 & A-104.

5. How many volleyball/tennis systems are required?

ANSWER: There shall be 2 volleyball courts and 1 tennis court. Refer to drawings A-103 & A-104 for other items as required.

6. Is the Action Cush I System acceptable for flooring? Note the Action Cush I system submitted uses the same 3/8" 60 durometer resilient pads, two layers of 15/32" plywood and 25/32" x 2 1/4" 2ND btr grade MFMA maple strip flooring as called for in the contract documents.

ANSWER: Action Floor system (Action Cush I) is found to be equivalent as per specification 09 64 20 para 1.1 and part 2 products. Installation shall be as per recommendation of manufacturer and/or specifications.

1.1. QUALITY ASSURANCE

A. Manufacturer

1. Manufacturer of resilient flooring shall be a firm specializing in manufacturing products specified in this section.
2. Basis of design shall be Floating Floor System (AcerCush II or Equivalent)

PART 2 PRODUCTS

2.1. MATERIALS

A. Flooring –

1. 25/32" x 2-1/4" 2nd and Better grade northern Hard Maple flooring, TGEM, MFMA grade marked and stamped as manufactured by the vender.