

SECTION 07510
BITUMINOUS BUILT-UP ROOFING

PART 1 GENERAL

1.1 DESCRIPTION

This section includes bituminous built-up roofing, aggregate surfacing, with base flashing for new construction.

1.2 RELATED WORK

- A. Wood cants, blocking, and wood edge strips: Section 06100, ROUGH CARPENTRY.
- B. Wood sheathing: Section 06100, ROUGH CARPENTRY.
- C. Insulation: Section 07220, ROOF AND DECK INSULATION.
- D. Vapor barrier: Section 07220, ROOF AND DECK INSULATION.
- E. Base sheet for insulated roof assemblies: Section 07220, ROOF AND DECK INSULATION.
- F. Metal base flashing, pipe flashing, counter flashing, gravel stop, fascia, coping, gutter and downspout, splash pan, reglet, insulated expansion joint cover, scupper: Section 07600, FLASHING AND SHEET METAL.

1.3 APPLICABLE PUBLICATIONS

- A. Applicable publications listed below form a part of this Specification as referenced. Publications are referenced in the text by the number designation only.
- B. American Society for Testing and Materials (ASTM):
 - D41-94(R2000).....Asphalt Primer Used in Roofing,
Dampproofing and Waterproofing
 - D43-00.....Coal Tar Primer Used in Roofing,
Dampproofing and Waterproofing
 - D227-03.....Coal-Tar Saturated Organic Felt Used in
Roofing and Waterproofing
 - D312-00.....Asphalt Used in Roofing
 - D450-96(R2000).....Coal-Tar Pitch Used in Roofing,
Dampproofing and Waterproofing
 - D1863-03.....Mineral Aggregate Used on Built-Up Roofs
 - D2178-04.....Asphalt Glass Felt Used in Roofing and
Waterproofing
 - D3909-97b(R2004).....Asphalt Roll Roofing (Glass Felt) Surfaced
with Mineral Granules
 - D4586-00.....Asphalt Roof Cement, Asbestos Free
 - D4601-98.....Asphalt Coated Fiberglass Base Sheet Used
In Roofing

- D4897-01.....Asphalt Coated Glass Fiber Venting Base
Sheet Used in Roofing
- D6163-00.....Specification for Styrene Butadiene
Styrene (SBS) Modified Bituminous Sheet
Materials Using Glass Fiber Reinforcements
- E108-04.....Fire Tests of Roof Coverings
- E119-00.....Test Method for Fire Tests of Building
Construction and Materials
- F1667-03.....Driven Fasteners: Nails, Spikes, Staples
- C. FM Global (FMG):
 - P7825C-03.....Approval Guide Building Materials
 - 4450:.....Approved Standard for Class 1 Insulated
Steel Deck Roofs
 - 4470:.....Approved Standard for Class 1 Roof
Coverings
- D. National Roofing Contractors Association (NRCA):
 - "Quality Control Guidelines for the Application of Built-up
Roofing."
 - "The NRCA Roofing and Waterproofing Manual"

1.4 WARRANTY

Roofing system is subject to terms of "Warranty of Construction" Article in Section 01001, GENERAL CONDITIONS, except that warranty period is extended to Twenty (20) years.

1.5 QUALITY CONTROL

- A. Applicator Qualifications: Installer experienced in installation of systems similar in complexity to that required for this Project, including specific requirements indicated:
 - 1. Work shall be performed by installer approved in writing by roofing material manufacturer.
 - 2. Work shall comply with printed instructions of the roofing materials manufacturer.
- B. Product/Material Qualifications:
 - 1. Provide manufacturer's label on each container or certification with each load of bulk bitumen, indicating Flash Point (FP), Finished Blowing Temperature (FBT), Softening Point (SP), Equiviscous Temperature (EVT).
 - 2. Provide manufacturer's certification that field applied bituminous coatings and mastics, and field applied roof coatings comply with limits for Volatile Organic Compounds (VOC) per the National Volatile Organic Compound Emission

Standards for Architectural Coatings pursuant to Section 183(e) of the Clean Air Act with limits as follows:

- a. Bituminous Coatings and Mastics: 500 g/l (4.2#/gal.).
 - b. Roof Coatings: 250 g/l (2.1#/gal.).
3. Obtain products from single manufacturer or from sources recommended by manufacturer for use with roofing system.
- C. Comply with the recommendations of the NRCA "Roofing and Waterproofing Manual" applicable to built-up roofing for storage, handling and installation.
 - D. FMG Listing: Provide roofing membrane, base flashing, and component materials that comply with requirements in FMG 4450 and FMG 4470 as part of a roofing system and that are listed in FMG "Approval Guide" for Class 1 or noncombustible construction, as applicable. Identify materials with FMG markings.
 1. Fire/Windstorm Classification: Class 1A- 75 90.
 2. Hail Resistance: MH.

1.6 SUBMITTALS

- A. Submit in accordance with Section 01340, SAMPLES AND SHOP DRAWINGS.
- B. Product Data:
 1. Asphalt materials, each type.
 2. Roofing cement, each type.
 3. Roof Walkway
 4. Fastening requirements.
- C. Certificates:
 1. Indicate materials and method of application of roofing system meet requirements of FMG.
 2. Statements of qualification for manufacturers and installers.
 3. Inspection Report: Copy of roofing system manufacturer's inspection report certifying completed roofing complies with manufacturer's warranty requirements.
- D. Warranty: As specified in Part 1 of this Section:
 1. Warranty sample form with specific language to address Contract provisions.
- E. Contract Close-out Submittals:
 1. Maintenance Manuals.
 2. Warranty signed by installer and manufacturer.

1.7 DELIVERY, STORAGE AND MARKING

- A. Deliver roofing materials to the site in original sealed packages or containers marked with the name and brand or trademark of the manufacturer or seller.

- B. Keep roofing materials dry and store in a dry, weather-tight facility or under canvas covers. Do not use polyethylene or plastic covers to protect materials. Store above ground or deck level on wood pallets. Cover ground under pallet stored materials with plastic.
 - 1. Store rolled materials (felts, base sheets, and paper) on end. Do not store hems on top of rolled materials.
 - 2. Aggregates shall be maintained surface dry as defined by ASTM D1863.
- C. Protect from damage due to handling, weather and construction operations before, during and after installation.

1.8 ENVIRONMENTAL REQUIREMENTS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.
- B. Environmental Controls: Refer to Section 01568, Environmental Protection.
- C. Protection of interior spaces: Refer to Section 01010, General Requirements.

PART 2 - PRODUCTS

2.1 ROOFING SYSTEM

- A. Install built-up roofing membrane system according to roofing system manufacturer's written instructions and applicable recommendations of NRCA "Quality Control Guidelines for the Application of Built-up Roofing."
- B. Glass sheet, asphalt bitumen, mineral surfaced.
 - 1. Substrate: Roof Insulation
 - 2. Components: Quantity
 - a. Ply Sheet: 3 Plies
 - b. NON-Mineral Surfaced Cap Sheet: 1 Ply
 - c. Asphalt Between Substrate and First Ply: 10-17.5 kg/10 sq. meters 20-35 lbs/100 sq. ft.
 - d. Asphalt Between Each Ply 10-17.5 kg/10 sq. meters 20-35 lbs/100 sq. ft.
 - 3. Provide asphalt quantities within the indicated ranges, unless recommended otherwise in the roofing materials manufacturer's printed data.

2.2 MATERIALS

- A. Primer: ASTM D41.

- B. Base Sheet: ASTM D4601, Type II, nonperforated, asphalt-impregnated and coated, glass-fiber sheet, dusted with fine mineral surfacing on both sides.
- C. Asphalt: ASTM D312, Type III or IV for roof membrane. Use Type I for pour coat unless specified otherwise.
- D. Ply Sheet/Backer Sheet: ASTM D2178, Type VI, heavy-duty ply sheet.
- E. Cap Sheet: ASTM D3909, asphalt-impregnated and -coated, glass-fiber cap sheet, appropriate for cold process fibrated roof coating.
- F. Roof Cement: ASTM D4586, Type I.
- G. Flashing Sheet: ASTM D6163, Type I or II, glass-fiber-reinforced, SBS-modified asphalt sheet; granular surfaced; suitable for application method specified.

2.3 MISCELLANEOUS MATERIALS

- A. Coating:
 - 1. Cold process fibrated emulsion.
- B. Roof Walkway:
 - 1. Prefabricated asphalt plank consisting of a homogeneous core of asphalt, plasticizer and inert fillers, bonded by heat and pressure between two saturated and coated sheets of felt:
 - a. Topside of plank surfaced with ceramic granules.
 - b. Size: Minimum 13 mm (1/2-inch) thick, manufactures standard size, but not less than 300 mm (12 inches) in least dimension and 600 mm (24 inches) in length.

2.4 FASTENERS

- A. Nails and Staples: ASTM F1667.
- B. Nails for Securing built-up Flashing and Base Sheets to Wood Nailers and Deck:
 - 1. Zinc coated steel roofing nails with minimum head diameter of 10 mm (3/8-inch) through metal discs at least 25 mm (one inch) across.
 - 2. One-piece nails with an integral flat cap at least 24 mm (15/16-inch) across.
- C. Fasteners for Securing Dry Felt Edge Strips to Wood Nailer and Decks:
 - 1. Zinc coated steel roofing nails, 16-mm (5/8-inch) minimum head diameter.
 - 2. Staples, Flat top Crown, zinc coated may be used.
- D. Nails for attaching built-up Flashing to Masonry:
 - 1. Hardened steel nails through metal discs at least 25 mm (one inch in diameter).

2. One-piece nails with an integral flat cap at least 24 mm (15/16-inch) across.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of Conditions: Examine substrates, areas and conditions under which Work is to be performed and identify conditions detrimental to proper or timely completion:
 1. Do not proceed until unsatisfactory conditions, including moisture, have been corrected.
 2. Do not install roofing materials over wet insulation.
 3. Do not install roofing materials unless roof openings, wood nailers, edge venting, insulation board, flashing, curbs, and roof joints are constructed.
 4. Do not install roof materials unless deck and/or insulation provides designed drainage to working drains.
- B. Do not apply roof system if roofed deck will be used as a work platform.
- C. Existing Intake Louvers:
 1. Use large fans during placement to direct airflow away from existing intake louvers.
 2. If required to install roof near intake louvers after work hours, it shall be done so without additional cost to the Government.

3.2 PREPARATION

- A. Sweep substrate to broom clean condition. Remove all dust, dirt and debris.
- B. Remove surface irregularities that may damage materials or cause installation defects.
- C. Coordinate operations with roof insulation and sheet metal work to permit continuous roofing operations.

3.3 INSTALLATION

- A. Comply with roofing system manufacturer's written instructions and applicable recommendations of NRCA "Quality Control Guidelines for the Application of Built-up Roofing."
- B. Cooperate with inspection and test agencies required to perform services in connection with built-up roofing system installation.

C. General:

1. Provide uniform and positive adhesion between all installed materials, including adhesion to insulation or substrate, and between each ply of felt.
2. Substrate Penetrations: Do not allow bitumen to penetrate joints or enter building. Where mopping is applied directly to a substrate, tape joints. When applying steep asphalt, hold mopping back 50mm (2 inches) from each side of joint.

D. Asphalt Products Schedule:

1. Use asphalt only with asphalt-saturated or asphalt-impregnated felts.
2. Use Type I asphalt for pour coats up to 1:10 (one inch per foot) slope.
3. Coats on slopes over 1:10 (one inch per foot).
4. Use asphalt roof cement with asphalt products.

E. Bitumen Schedule:

1. Per square, unless otherwise specified.
2. Between substrate and plies of organic felt:
 - a. Asphalt 7 to 11 Kg (15 to 25 pounds).
3. Between substrate and plies of glass fiber felts asphalt, 9 to 14 kg (20 to 30 pounds).
4. Glaze Coats:
 - a. Asphalt 7 to 11 Kg (15 to 25 pounds).
5. Pour coats:
 - a. Asphalt 25 to 30 Kg (55 to 65 pounds).

F. Heating Bitumen:

1. Heat the asphalt to the equiviscous temperature (EVT) plus or minus 4 C (25 degrees F) at the time of application.
 - a. Do not heat asphalt greater than 38 C (100 degrees F) above the EVT.
 - b. When the EVT is not furnished do not heat asphalt above 246 C (475 degrees F) for Type I and 275 C (525 degrees) F for Type II and IV, with an application not less than 218 C (425 degrees F) and 246 C (475 degrees F) respectively.
2. Do not heat bitumen above the flash point temperature.
3. Provide heating kettles with a thermometer kept in operating condition. Attend, during heating, to insure the bitumen is heated within the temperatures specified.
4. Do not mix different types of bitumen in kettle.

G. Terminations:

1. Where cants occur at vertical surfaces, cut off plies of membrane 50mm (2 inches) above top of cant strip, (except at prefabricated curbs, scuttles and other roof accessories having integral cants) extend membrane over cant and up vertical surface to top of curb or blocking.
2. Where wood blocking occurs at roof edge, under gravel stops or penetrations to receive base flashing, nail a continuous strip of 400 mm (16-inch) wide, loose applied organic felt envelope over the blocking before the first ply sheet is applied.
 - a. Install strip on top of venting base sheet.
 - b. After membrane is installed, turn the dry felt back over the roofing and secure in place with hot bitumen before gravel stops or metal flanges extending onto the membrane are installed.
3. Where fascia/cant occurs at roof edges, extend membrane beyond outside face and cut off after base flashing is installed.

H. Base Sheet:

1. One ply of base sheet dry to deck, except mop between laps. Lap and attach as specified to deck.

I. Roof Ply Installation:

1. Install, asphalt, glass fiber felt construction. Base sheet is not considered a ply.
2. Extend the first ply 100 mm (4-inches) beyond the insulation and the second ply 75 mm (3-inches) beyond the first. Lap ends 75 mm (3-inches) with joints broken 450 mm (18-inches) in each ply.

J. Laps for felts and base sheet:

1. Base sheet, lapped 50 mm (2-inches).
2. Three plies of felt with 300 mm (12-inches) 600 mm (24-inches) and 900 mm (36-inch) starting widths, lapped 624 mm (24-1/2 inches).
3. End joints of felt and base sheet, lapped 50 mm (2-inches). Stagger end joints in relation to joints in adjacent and proceeding plies.

K. Flashing:

1. Prime vertical surfaces of masonry and concrete with asphalt primer except where vented base sheet is required to provide edge venting.

2. Apply flashing on top of built-up roofing, up face of cant and vertical surfaces, at least 200 mm (8-inches) above the roof, full height beneath counter flashing or top of curb flashing:
 - a. At fascia-cants, extend to top of cant and cut off.
 3. Except at metal fascia cants, secure top edge of base flashing with nails on a line approximately one inch below top edge, spaced not more than 200 mm (8-inches) on center.
 - a. Cover all nail heads with roof cement.
 - b. Cover the top of the base flashing with counter flashing as specified in Section 07600, FLASHING AND SHEET METAL. At the cants secure the top edge of the flashing with fascia compression clamp as specified in Section 07600, FLASHING AND SHEET METAL.
 4. Install flashing using longest pieces practicable. Complete splices between flashing and main roof sheet before bonding to vertical surface. Seal splice not less than 76mm (3-inches) beyond fasteners that attach membrane to blocking. Apply bonding adhesive to both flashing and surface to which flashing is being adhered per manufacturer recommendations. Nail top of flashing 300mm (12-inches) on center under metal counter flashing or cap.
 - a. Parapet Walls: Extend up parapet and turn over top edge. Apply with 100 percent adhesive.
 5. Install flashing over cants to make system watertight.
 6. Install flashing before final roofing coat and aggregate are installed.
- L. Stripping:
1. Set flanges of metal flashing in roof cement before the final bituminous coat and roof aggregate are installed and nail to blocking per Section 07600, FLASHING AND SHEET METAL.
 2. Before the final bituminous coat and aggregate are installed, cover that portion of the horizontal flanges of metal base flashing, gravel stops and other flanges, extending onto the roofing with flashing sheet
- M. Surfacing:
1. Cold process fibrated emulsion top coating.
- N. Roof Walkways:
1. Install roof walkways where shown.
 2. Prefabricated asphalt plank: Set planks in hot bitumen poured over the firmly embedded roof aggregate as specified for pour

coat. Maintain minimum 75-mm (3-inches) to maximum of 150 mm
(6-inches) space between planks

- - - E N D - - -