



ProScience Analytical Services, Inc

Stacey Wallace
ENRM VA Hospital
200 Springs Road
Bedford, MA 01730

January 13, 2018

Dear Stacey Wallace,

The enclosed analytical results have been obtained by using EPA 600/R-93/116 or EPA 600/M4-82-020. Calibrated Visual Estimate (CVE) is used by ProScience for the determination of the percentage of asbestos and other components in the sample. Point Counting is recommended when the sample contains less than 10% asbestos by CVE. Friable materials found to be less than 1% by CVE are automatically point counted (400 points) at no additional charge. ProScience recommends further analysis by a gravimetric method for non-friable materials that are less than 1% by CVE.

The Quality Control data related to the samples analyzed is available upon client's written request. ProScience Analytical Services Inc., assumes no responsibility for potential sample contamination that may have occurred during the sample collection process or erroneous data provided by the client. Unless otherwise indicated, all samples were received in acceptable condition.

The enclosed results may not be used under any circumstances as product endorsement by any US government agency including NIST/NVLAP.

All Laboratory records are retained for at least three years unless otherwise directed in writing by the client. The actual samples are retained for a period of two months and written request is necessary in order to be retained for a longer period of time. All analytical results and records are considered strictly confidential and will not be released under any circumstances to anyone except the actual client. The analytical results included in this report apply only to the items tested. This report may not be reproduced except in its entirety, without the permission of ProScience Analytical Services, Inc., Laboratory Director.

If you have any questions please contact the Laboratory Manager or the Laboratory Director.

Sincerely,

Patricia Weakley, Optical Asbestos Manager

Aimee Cormier, Laboratory Director

Enclosure: Version 2
LAB BATCH ID: B 108003 CLIENT PROJECT ID: N/A
Client Ref: Crescent House Room 205 - Kitchen
CT ID# PH-0209; MA ID# AA000156; ME ID# LB-055; ME ID# LA-056; NVLAP Lab Code 200090-0;
RI ID # AAL-093; VT ID# AL016876

ProScience Analytical Services, Inc.

Client Name: ENRM VA Hospital
 PO #: 518-7R1055
 Client Project #: N/A
 Client Reference: Crescent House Room 205 - Kitchen
 Method: EPA/600/R-93/116

Batch: B108003
 Date Sampled: 1/12/2018
 Date Received: 1/12/2018
 Date Analyzed: 1/12/2018
 Date of Report: 1/13/2018

Sample ID	Color	Asbestos %						Non-Asbestos %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
01A	Tan	0	0	0	0	0	0	0	0	0	0	0	0	100
Description: 12x12 Floor Tile Location: Crescent House Room 205 Kitchen Comments:														
Is asbestos present? No. Analyzed: Yes														

Sample ID	Color	Asbestos %						Non-Asbestos %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
01B	Tan	0	0	0	0	0	0	0	0	0	0	0	0	100
Description: 12x12 Floor Tile Location: Crescent House Room 205 Kitchen Comments:														
Is asbestos present? No. Analyzed: Yes														

Sample ID	Color	Asbestos %						Non-Asbestos %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
02A	Yellow	0	0	0	0	0	0	0	0	0	0	0	0	100
Description: Yellow Mastic assoc. w/Tile Location: Crescent House Room 205 Kitchen Comments:														
Is asbestos present? No. Analyzed: Yes														


Sample ID	Color	Asbestos %						Non-Asbestos %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
02B	Yellow	0	0	0	0	0	0	0	0	0	0	0	0	100
Description: Yellow Mastic assoc. w/Tile Location: Crescent House Room 205 Kitchen Comments:														
Is asbestos present? No. Analyzed: Yes														

Asbestos Codes: CHR = Chrysotile AMO = Amosite CRO = Crocidolite ACT = Actinolite TRE = Tremolite ANT = Anthophyllite
 Non-Asbestos Codes: FBG = Fiberglass MNW = Mineral Wool CEL = Cellulose HAR = Hair SYN = Synthetic OTH = Other NON = Non-Fibrous Minerals

Note: To create a unique lab sample ID, use the Batch # and the Sample ID (example: [Batch #] - [Sample ID]).

* All results are in percentage.

Analyst: Patricia Weakley



ProScience Analytical Services, Inc.

PLM Asbestos Chain of Custody Record

LABORATORY/HEADQUARTERS

22 Cummings Park, Woburn, MA 01801 683 North Mountain Rd., Newington, CT 06111
T: 781-936-3212 F: 781-932-4857 T: 860-953-1022 F: 860-953-1030

LABORATORY SERVICES



Turn Around Time Requested

☐ Same day ☒ 24 Hour ☐ 48 Hour ☐ 72 Hour ☐ 5 Days

Client: Bedford VA Hospital

Address: 200 Springs Rd Bedford MA 01730

Project Site & Bldg: Crescent House Room 205

Project #:

Phone / FAX Number:

781-687-3312

Contact: Jason Pronovost (Email: jason.pronovost@va.gov)

For Lab Use ->

Batch #

B108003

Analyzed by/date:

Turnaround 1/12/18

QC by/date:

1/12/18

QC by/date:

1/12/18

Relinquished by/date: 1/12/18
Received by/date: 1/12/18
Samples received: 950
Faxed, E-mailed, Verbal by/date: 1/12/18
Stop on first positive: Yes
Analyzed: 950

Lab ID	Field ID	Sample Date	Description / Location	% Asbestos	Color	Homogeneity	Texture	Friable	Morphology	Extinction	Sign of Elongation	Birefringence	Pleochroism	=	+	Chrysotile	Amosite	Crocidolite	Tremolite	Anthophyllite	Actinolite	Fiberglass	Mineral Wool	Cellulose	Hair	Synthetic	Other	Non Fibrous
	O2A	1/12/18	Crescent House Room 205 Kitchen 1st floor tile	Ø	TNHN																						100	
	O2B	1/12/18	Crescent House Room 205 Kitchen yellow mastic assoc. tile	Ø	TNHN																						100	
	O2A	1/12/18	Crescent House Room 205 Kitchen yellow mastic assoc. tile	Ø	TNHN																						100	
	O2B	1/12/18	Crescent House Room 205 Kitchen yellow mastic tile	Ø	TNHN																						100	