

SALIENT CHARACTERISTICS

1. Hospital grade 304L Stainless steel cleanable construction.
2. Integral Mechanical cooler to maintain 66-75F payload temperature setpoint.
3. Integral steam humidifier in the payload storage area to be supplied with Demineralized sterile water bottles to be replaced by nursing staff.
4. Condensate collection system using collection bottles to be hand emptied by nursing staff.
5. Built in recirculation fans and HEPA filtration system to ISO 7 levels.
6. Unit mounted casters for mobility.
7. UPS batter backup for temporary power backup protection.
8. See through glass doors.
9. (5) stainless steel pullout shelves sized to accommodate (25) VA spec storage containers.
10. Onboard DDC control system utilizing a digital display for monitoring temperature, humidity and status.
11. 120V Hospital grade 10" long plug in cord.
12. Pressure monitor with alarm Unit must be installed in a heated normal indoor work environment, cannot be installed in an unconditional space.
13. Warranty: 1 year parts and labor.