ROOM FINISH SCHEDULE - HOUSING A1-A2

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1A502	DIETICIAN	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1AC05C	CORR	WSF-13,14,15	RB-3	ST-3 / P-12 / P-20 / PTM	P-12	ST-3 / P-12 / PTM	P-12	AT-1 / P-14, 15	1, 2, 12, 19
1AC05K	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H001	SOCIAL WRK	WSF-13A	RB-3	P-3	P-19	P-3	P-3	AT-1	---
1H002	MECH	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1H003	HEAD NURSE	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	5
1H004	OFFICE, ANP	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	5
1H005	COMM	CONCS-1	RB-3	P-1	P-1	P-1	P-1	---	---
1H006	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1H007	ELEC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1H008	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1H009	OFFICE, PCM	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	---
1H010	STF. LOUNGE	WSF-14	RB-3A	P-3	P-25	P-3	P-3	P-1	---
1H012	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1H012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7, 8A	PPT-6, 7, 8A	EC-2	3
1H013	SOILED	WSF-13A	IV-13A	EC-1 / WG-2	EC-1	EC-1	EC-1 / WG-2	AT-2 / EC-2	2,17
1H014	BEDROOM	WSF-13,14	RB-3	P-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H015	MED.	WSF-13A	RB-3A	P-3	P-3 / WG-2	P-3 / WG-2	P-3	AT-1 / P-1	2,17
1H016	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1H016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H017	LIVING	CPT-13	RB-3	---	P-3	---	P-3	P-1	1, 2
1H018	BEDROOM	WSF-13,14	RB-3	P-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H019	CONCIERGE	CPT-13	RB-3	---	P-3	P-3	P-3	AT-1 / P-3	1, 2, 10, 12
1H020	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1H020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H021	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1H022	BEDROOM	WSF-13,14	RB-3	P-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H022C	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H023	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	---	P-3 / WG-2	P-1	1, 2, 13
1H024	BEDROOM	WSF-13,14	RB-3	P-43	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H025	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	---	P-1	1, 2, 13
1H026	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-43	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H026A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H028	BEDROOM	WSF-13,14	RB-3	P-40	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H028A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H030	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-40	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H030A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H030B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1H031	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1H032	BEDROOM	WSF-13,14	RB-3	P-41	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H033	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1H033A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H034	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-41	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1H034A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H035	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1H035A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H040	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1, 3	1, 2, 9, 10, 11, 15
1H040A	PANTRY	WSF-13	RB-3	P-3 / PPT-6A	P-3	P-3	P-3	AT-1	11
1H041	LIVING	CPT-13	RB-3	P-3,20 / STN-1	P-3	P-3	P-3	P-1	1, 2, 10
1H041A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1H042	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1H042A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1H043	NOURISH.	WSF-13	RB-3A	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3	AT-1 / P-1	2,17
1H044	QUIET ROOM	WSF-14	RB-3	P-3	P-3	P-3	P-25	AT-1 / P-1	6, 9, 10
1H045	SOIL. HLD.	WSF-13A	IV-13	EC-1 / WG-2	EC-1	EC-1 / WG-2	EC-1 / WG-2	AT-2	2,17
1H047	PAT. SHOWER	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3

ROOM FINISH SCHEDULE - HOUSING A1-A2

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1H049	WARD CLK.	WSF-13	RB-3	---	---	P-20	P-3	P-1	1, 2, 9
1HC01	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1
1HC02	CORR	WSF-14	RB-3	P-3	P-3	P-3	---	AT-1 / P-1	1
1HC03	CORR	WSF-13,14	RB-3	P-3	P-3	---	P-3, 20	AT-1 / P-1	1, 2
1HC04	CORR	WSF-13,14	RB-3	P-3	---	P-3	P-3	AT-1 / P-1	1
1HC04A	CORR	WSF-13,14	RB-3	P-3, 12	P-3	P-3, 14, 15, 23	P-3	AT-1 / P-1	1, 2, 12
1HC05	CORR	WSF-13,14	RB-3	P-3	P-3, 23	P-3	P-3, 14, 15, 17	AT-1 / P-1	1, 2
1HC06	CORR	WSF-14	RB-3	P-3	---	P-3	---	AT-1 / P-1	1, 2
1HC08	CORR	WSF-13,14	RB-3	P-3, 14	P-3	P-3, 20	P-3	AT-1 / P-1	1, 2
1J001	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1J002	EQUIP.	WSF-13A	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1	17
1J004	BEDROOM	WSF-13,14	RB-3	P-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J004A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J005	OFFICE, PCM	WSF-13A	RB-3	P-3	P-19	P-3	P-3	AT-1	---
1J006	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1J006A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J007	CLEAN	WSF-13A	RB-3	EC-1	EC-1	EC-1 / WG-2	EC-1	AT-2	2,17
1J008	BEDROOM	WSF-13,14	RB-3	P-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J008A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J009	LIVING	CPT-13	RB-3	---	P-3	---	P-3	P-1	1, 2
1J010	ISO. BEDROOM	WSF-13,14	RB-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-1	1, 2, 6, 9, 10
1J011	CONCIERGE	CPT-13	RB-3	---	P-3	P-3	P-3	AT-1 / P-3	1, 2, 10, 12
1J012	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1J012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J013	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	---	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1J014	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1J014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J015	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1J016	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1J016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J017	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	---	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1J018	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1J018A	PANTRY	WSF-13	RB-3	P-3	P-3 / PPT-6A	P-3	P-3	AT-1	11
1J019	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1J020	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1J020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J021	BEDROOM	WSF-13,14	RB-3	P-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J021A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J022	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-41	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J022B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1J023	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1J023A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J024	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1J024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J026	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-40	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J026A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J027	LIVING	CPT-13	RB-3	P-3,20 / STN-1	P-3	P-3	P-3	P-1	1, 2, 10
1J027A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1J028	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-43	AT-1 / P-3	1, 2, 6, 10, 18
1J028A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J030	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-43	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1J030A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1J031	SUPPLY	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	
1J032	QUIET ROOM	WSF-14	RB-3	P-3	P-25	P-3	P-3	AT-1 / P-1	6, 9, 10
1J033	EQUIP.	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	2,17
1J035	EXAM	WSF-13	RB-3A	P-3	P-3	P-3	P-19	AT-1 / P-3	---
1J037	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1JC03	CORR	WSF-13,14	RB-3	P-3	P-3, 20	---	P-3	AT-1 / P-1	1, 2
1JC04	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	---	AT-1 / P-1	1
1JC04A	CORR	WSF-13,14	RB-3	P-3, 12	P-3	P-3, 15, 23	P-3	AT-1 / P-1	1, 2, 12
1JC05	CORR	WSF-13,14	RB-3	P-3 / WG-2	P-3, 14, 23	P-3 / WG-2	P-3 / WG-2	AT-1 / P-1	1, 2, 13
1JC06	CORR	WSF-14	RB-3	P-3	P-3	P-3	---	AT-1 / P-1	1
1JC06A	CORR	WSF-15	RB-3	P-3	---	P-3	P-3	AT-1 / P-1	1
1JC08	CORR	WSF-13,14	RB-3	P-3, 14, 15, 17	P-3	P-3, 20, 23	P-3	AT-1 / P-1	1, 2

FINISH UPGRADES, BID ALTERNATE NO. 3 SCHEDULE - HOUSING A1-A2

ROOM NUMBER	ROOM NAME	NORTH	EAST	SOUTH	WEST	ID FINISH REMARKS
1H019	CONCIERGE	BASE BID	BASE BID	BASE BID	P-3 / WC-3	1, 2, 12
1HC04A	CORR	P-3 / WP-21	BASE BID	BASE BID	BASE BID	1, 2, 12
1J011	CONCIERGE	BASE BID	P-3 / WC-3	BASE BID	BASE BID	1, 2, 12
1JC04A	CORR	P-3 / WP-21	BASE BID	BASE BID	BASE BID	1, 2, 12
1AC05C	CORR	ST-3 / WP-22	BASE BID	ST-3 / WP-22	BASE BID	1, 2, 12

NOTES:

SHEET NOTES:

A REFER TO SHEETS N-AI1.1A1-A THROUGH N-AI1.1C4 FOR CEILING DESIGN AND HEIGHT VARIATIONS.
B REFER TO CASEWORK AND MILLWORK SCHEDULE ON SHEETS N-AI6.101-A THROUGH N-AI6.103 FOR FINISH LOCATIONS.
C USE CG-1, CR-13, AND HR-1 WALL PROTECTION IN ALL LOCATIONS UNLESS NOTED OTHERWISE. SEE SHEET N-QH5.101 AND N-QH6.101 FOR MOUNTING HEIGHTS AND DETAILS.
D ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS TO MATCH FLOOR MATERIAL.
E ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.
F ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21, UNLESS NOTED OTHERWISE
G REFER TO SHEET N-IN6.106 AND N-IN6.107 FOR KEY TO FINISHES.
H ALL WINDOW STOOLS TO BE SSM-5.
I LIGHT COVES: PAINT THE INTERIOR SURFACE A GLOSS PAINT FINISH.

ID FINISH REMARKS

1 SEE SHEETS N-IN7.1A1-A THROUGH N-IN7.1C4 FOR FLOOR PATTERN PLANS
2 SEE SHEETS N-IN1.1A1-A THROUGH N-IN1.1C4 FOR WALL FINISH LOCATIONS PLANS
3 SEE SHEET N-AI2.206 FOR WALL ELEVATIONS WITH TILE MATERIAL LOCATIONS
4 LOCATE MOTORIZED WINDOW TREATMENT WT-3 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
5 LOCATE MANUAL WINDOW TREATMENT WT-1 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
6 LOCATE MOTORIZED WINDOW SHADES WT-3 AND WT-7 IN RESIDENT ROOMS. (DRAPERY NOT IN CONTRACT)
7 NOT USED
8 PAINT WAINSCOT ACCENT P-19 TO TOP OF DOOR FRAME WITH 2 INCH BULLNOSE TRANSITION PAINTED P-21, PAINT ABOVE TRIM P-3. ALIGN TOP OF BULLNOSE WITH THE TOP OF THE DOOR FRAME
9 PAINT FRONT OF SOFFIT TO MATCH ADJACENT WALL, PAINT HORIZONTAL SURFACE P-1
10 SEE INTERIOR ELEVATIONS ON SHEETS N-AI2.201 THROUGH N-AI2.207-A FOR ADDITIONAL INFORMATION
11 PAINT FINISH TO BE SATIN
12 SEE SHEET N-AI.2.207-A FOR BID ALTERNATE NO.3, FINISH UPGRADES
13 WG-2 WAINSCOT FROM FLOOR TO 30 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
14 NOT USED
15 WALL SIDE SPLASH TO BE PPT-6A, SEE ELEVATION SHEET N-AI2.206 FOR LOCATIONS
16 PPT-6A WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH EC-1 ABOVE
17 WG-2 WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
18 PAINT FRONT AND HORIZONTAL SURFACES OF SOFFIT P-3
19 INTERIOR STUCCO TO BE SMOOTH AND NON ABBRASSIVE

FINISH ABBREVIATIONS

AT	ACOUSTICAL CEILING TILE
CC	CUBICAL CURTAIN
CG	CORNER GAURD
CONCS	CONCRETE SEALED
CPT	CARPET TILE
CR	CRASH RAIL
EC	EPOXY COATING PAINT
FM	FLOOR MAT
GLT	GLASS TILE
GRT	GROUT
HPDL	HIGH PRESSURE DECORATIVE LAMINATE
HR	HAND RAIL
IV	INTEGRAL BASE
P	PAINT
PPT	PORCELAIN PAVER TILE
PTM	PAINT TO MATCH
QSM	QUARTZ SURFACE MATERIAL
QT	QUARRY TILE
QTB	QUARRY TILE BASE
RB	RUBBER BASE
SC	STUCCO, EXTERIOR (SEE N-IN6.107)
SSM	SOLID SURFACE MATERIAL
STN	STONE VENEER
WC	WALLCOVERING
WD	WOOD
WDV	WOOD VENEER
WG	WALL GUARD
WP	WALL PANEL
WSF	WELDED SHEET FLOOR
WT	WINDOW TREATMENT

BUILDING IS FULLY SPRINKLERED

⚠No.	Description	Date
	RECORD DRAWINGS	12-01-2015

VA FORM 08-6231, OCT 1978

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue, Winter Park, Florida 32789, 407 647 1039
1001 G Street,NW, Suite 1000, Washington, D.C. 20001, 202 654 9300

Drawing Title: COMMUNITY LIVING CENTER FINISH SCHEDULE - AREA A1-A2 BID ALTERNATE NO. 1

Approved: Project Director: Milan Brašić

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.101-A

Dwg. 259 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

ROOM FINISH SCHEDULE - HOUSING A3-A4

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1F001	MECH	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1F002	SOCIAL WRK	WSF-13A	RB-3	P-3	P-19	P-3	P-3	AT-1	---
1F004	HEAD NURSE	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	5
1F005	OFFICE, ANP	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	5
1F006	COMM	CONCS-1	RB-3	P-1	P-1	P-1	P-1	---	---
1F007	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1F008	ELEC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1F009	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1F010	EQUIP.	WSF-13A	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1	17
1F012	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-42	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F013	OFFICE, PCM	WSF-13A	RB-3	P-3	P-19	P-3	P-3	AT-1	---
1F014	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1F014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F015	CLEAN	WSF-13A	RB-3	EC-1 / WG-2	EC-1	EC-1	EC-1	AT-2	2,17
1F016	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-40	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F017	LIVING	CPT-13	RB-3	---	P-3	---	P-3	P-1	1, 2
1F018	ISO. BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	P-3	AT-1 / P-1	1, 2, 6, 9, 10
1F018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F019	CONCIERGE	CPT-13	RB-3	P-3	P-3	---	P-3	AT-1 / P-3	1, 2, 10, 12
1F020	BEDROOM	WSF-13,14	RB-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1F020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F021	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	---	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1F022	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1F022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F023	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1F024	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1F024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F025	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	---	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1F026	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1F026A	PANTRY	WSF-13	RB-3	P-3	P-3 / PPT-6A	P-3	P-3	AT-1	11
1F027	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1F027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F029	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-42	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F029A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F030	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1F030A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F031	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1F032	BEDROOM	WSF-13,14	RB-3	P-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F032B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1F034	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1F034A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F036	BEDROOM	WSF-13,14	RB-3	P-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F036A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F037	LIVING	CPT-13	RB-3	P-3	---	P-3, 20 / STN-1	---	P-1	1, 2, 10
1F037A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1F038	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-43	AT-1 / P-3	1, 2, 6, 10, 18
1F038A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F040	BEDROOM	WSF-13,14	RB-3	P-3	P-43	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1F040A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1F041	SUPPLY	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	
1F042	QUIET ROOM	WSF-14	RB-3	P-3	P-25	P-3	P-3	AT-1 / P-1	6, 9, 10
1F043	EQUIP.	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	2,17
1F045	EXAM	WSF-13	RB-3A	P-19	P-3	P-3	P-3	AT-1 / P-3	---
1F047	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1FC01	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1FC02	CORR	WSF-14	RB-3	P-3	P-3	P-3	---	AT-1 / P-1	1, 2
1FC03	CORR	WSF-13,14	RB-3	---	P-3, 20	P-3	P-3	AT-1 / P-1	1, 2
1FC04	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	---	AT-1 / P-1	1, 2
1FC04A	CORR	WSF-13,14	RB-3	P-3, 15, 23	P-3	P-3,12	P-3	AT-1 / P-1	1, 2, 12

ROOM FINISH SCHEDULE - HOUSING A3-A4

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1FC05	CORR	WSF-13,14	RB-3	P-3 / WG-2	P-3, 14, 23	P-3 / WG-2	P-3 / WG-2	AT-1 / P-1	1, 2, 13
1FC06	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1FC06A	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1FC08	CORR	WSF-13,14	RB-3	P-3, 20, 23	P-3	P-3, 14, 15, 17	P-3, 20	AT-1 / P-1	1, 2
1G002	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1G003	OFFICE, PCM	WSF-13A	RB-3	P-3	P-3	P-3	P-19	AT-1	---
1G004	STF. LOUNGE	WSF-14	RB-3A	P-3	P-25	P-3	P-3	P-1	---
1G006	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1G006A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G007	SOILED	WSF-13A	IV-13A	EC-1	EC-1	EC-1 / WG-2	EC-1 / WG-2	AT-2 / EC-2	2,17
1G008	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-40	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G008A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G009	MED.	WSF-13A	RB-3A	P-3 / WG-2	P-3 / WG-2	P-3	P-3	AT-1 / P-1	2,17
1G010	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1G010A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G011	LIVING	CPT-13	RB-3	---	P-3	---	P-3	P-1	1, 2
1G012	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-42	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G013	CONCIERGE	CPT-13	RB-3	P-3	P-3	---	P-3	AT-1 / P-3	1, 2, 10, 12
1G014	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1G014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G015	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1G016	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-41	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G017	EQUIP. ALCOVE	WSF-14	RB-3	---	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1G018	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-43	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G019	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	---	P-1	1, 2, 13
1G020	BEDROOM	WSF-13,14	RB-3	P-43	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G022	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-40	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G024	BEDROOM	WSF-13,14	RB-3	P-40	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G024B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1G025	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1G026	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-41	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G026A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G027	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1G027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G028	BEDROOM	WSF-13,14	RB-3	P-41	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1G028A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G029	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1G029A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G030	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1G030A	PANTRY	WSF-13	RB-3	P-3	P-3	P-3 / PPT-6A	P-3	AT-1	11
1G031	LIVING	CPT-13	RB-3	P-3	---	P-3, 20 / STN-1	---	P-1	1, 2, 10
1G031A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1G032	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1G032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G033	NOURISH.	WSF-13	RB-3A	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3	AT-1 / P-1	2,17
1G034	QUIET ROOM	WSF-14	RB-3	P-3	P-3	P-3	P-25	AT-1 / P-1	6, 9, 10
1G035	SOIL. HLD.	WSF-13A	IV-13	EC-1 / WG-2	EC-1	EC-1 / WG-2	EC-1 / WG-2	AT-2	2,17
1G037	PAT. SHOWER	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1G039	WARD CLK.	WSF-13	RB-3	P-20	---	---	P-3	P-1	1, 2, 9
1GC03	CORR	WSF-13,14	RB-3	---	P-3	P-3	P-20	AT-1 / P-1	1, 2
1GC04	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1GC04A	CORR	WSF-13,14	RB-3	P-3, 14, 15, 23	P-3	P-3,12	P-3	AT-1 / P-1	1, 2, 12
1GC05	CORR	WSF-13,14	RB-3	P-3 / WG-2	P-3, 23 / WG-2	P-3 / WG-2	P-3, 14, 15, 17	AT-1 / P-1	1, 2, 13
1GC06	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1GC08	CORR	WSF-13,14	RB-3	P-3, 20	P-3, 20	P-3, 14	P-3, 20	AT-1 / P-1	1, 2
1J010A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3

FINISH UPGRADE - BID ALTERNATE NO. 3 SCHEDULE - HOUSING A3-A4

ROOM NUMBER	ROOM NAME	NORTH	EAST	SOUTH	WEST	ID FINISH REMARKS
1F019	CONCIEGRE	BASE BID	P-3 / WC-3	BASE BID	BASE BID	1, 2, 12
1FC04CA	CORR	BASE BID	BASE BID	P-3 / WP-21	BASE BID	1, 2, 12
IG013	CONCIEGRE	BASE BID	BASE BID	BASE BID	P-3 / WC-3	1, 2, 12
IGC04A	CORR	BASE BID	BASE BID	P-3 / WP-21	BASE BID	1, 2, 12
1AC05C	CORR	ST-3 / WP-22	BASE BID	ST-3 / WP-22	BASE BID	1, 2, 12

NOTES:

SHEET NOTES

A REFER TO SHEETS N-AI1.1A1-A THROUGH N-AI1.1C4 FOR CEILING DESIGN AND HEIGHT VARIATIONS.

B REFER TO CASEWORK AND MILLWORK SCHEDULE ON SHEETS N-AI6.101-A THROUGH N-AI6.103 FOR FINISH LOCATIONS.

C USE CG-1, CR-13, AND HR-1 WALL PROTECTION IN ALL LOCATIONS UNLESS NOTED OTHERWISE. SEE SHEET N-QH5.101 AND N-QH6.101 FOR MOUNTING HEIGHTS AND DETAILS.

D ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS TO MATCH FLOOR MATERIAL.

E ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.

F ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21, UNLESS NOTED OTHERWISE

G REFER TO SHEET N-IN6.106 AND N-IN6.107 FOR KEY TO FINISHES.

H ALL WINDOW STOOLS TO BE SSM-5.

I LIGHT COVES: PAINT THE INTERIOR SURFACE A GLOSS PAINT FINISH.

ID FINISH REMARKS

1 SEE SHEETS N-IN7.1A1-A THROUGH N-IN7.1C4 FOR FLOOR PATTERN PLANS
2 SEE SHEETS N-IN1.1A1-A THROUGH N-IN1.1C4 FOR WALL FINISH LOCATIONS PLANS
3 SEE SHEET N-AI2.206 FOR WALL ELEVATIONS WITH TILE MATERIAL LOCATIONS
4 LOCATE MOTORIZED WINDOW TREATMENT WT-3 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
5 LOCATE MANUAL WINDOW TREATMENT WT-1 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
6 LOCATE MOTORIZED WINDOW SHADES WT-3 AND WT-7 IN RESIDENT ROOMS. (DRAPERY NOT IN CONTRACT)
7 NOT USED
8 PAINT WAINSCOT ACCENT P-19 TO TOP OF DOOR FRAME WITH 2 INCH BULLNOSE TRANSITION PAINTED P-21. PAINT ABOVE TRIM P-3. ALIGN TOP OF BULLNOSE WITH THE TOP OF THE DOOR FRAME
9 PAINT FRONT OF SOFFIT TO MATCH ADJACENT WALL, PAINT HORIZONTAL SURFACE P-1
10 SEE INTERIOR ELEVATIONS ON SHEETS N-AI2.201 THROUGH N-AI2.207-A FOR ADDITIONAL INFORMATION
11 PAINT FINISH TO BE SATIN
12 SEE SHEET N-AI.2.207-A FOR BID ALTERNATE NO.3, FINISH UPGRADES
13 WG-2 WAINSCOT FROM FLOOR TO 30 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
14 NOT USED
15 WALL SIDE SPLASH TO BE PPT-6A, SEE ELEVATION SHEET N-AI2.206 FOR LOCATIONS
16 PPT-6A WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH EC-1 ABOVE
17 WG-2 WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
18 PAINT FRONT AND HORIZONTAL SURFACES OF SOFFIT P-3
19 INTERIOR STUCCO TO BE SMOOTH AND NON ABBRASSIVE

FINISH ABBREVIATIONS

AT	ACOUSTICAL CEILING TILE
CC	CUBICAL CURTAIN
CG	CORNER GAURD
CONCS	CONCRETE SEALED
CPT	CARPET TILE
CR	CRASH RAIL
EC	EPOXY COATING PAINT
FM	FLOOR MAT
GLT	GLASS TILE
GRT	GROUT
HPDL	HIGH PRESSURE DECORATIVE LAMINATE
HR	HAND RAIL
IV	INTEGRAL BASE
P	PAINT
PPT	PORCELAIN PAVER TILE
PTM	PAINT TO MATCH
QSM	QUARTZ SURFACE MATERIAL
QT	QUARRY TILE
QTB	QUARRY TILE BASE
RB	RUBBER BASE
SC	STUCCO, EXTERIOR (SEE N-IN6.107)
SSM	SOLID SURFACE MATERIAL
STN	STONE VENEER
WC	WALLCOVERING
WD	WOOD
WDV	WOOD VENEER
WG	WALL GUARD
WP	WALL PANEL
WSF	WELDED SHEET FLOOR
WT	WINDOW TREATMENT

BUILDING IS FULLY SPRINKLERED

⚠No.	Description	Date
	RECORD DRAWINGS	12-01-2015

VA FORM 08-6231, OCT 1978

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue, Winter Park, Florida 32789, 407 647 1039
1001 G Street,NW, Suite 1000, Washington, D.C. 20001, 202 654 9300

Drawing Title: COMMUNITY LIVING CENTER FINISH SCHEDULE - AREA A3-A4 BID ALTERNATE NO. 1

Approved: Project Director: Milan Brakic

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.102-A

Dwg. 260 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

ROOM FINISH SCHEDULE - ADMIN B1-B2										
				WALLS						
ROOM NUMBER	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CEILING	ID FINISH REMARKS
1A102	CONF	CPT-1	RB-2	P-12	P-12	P-12	P-12	AT-1 / P-1	5
1A103	PHARMACIST	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A104	CONF	CPT-1	RB-2	P-12	P-12	P-12	P-12	AT-1 / P-1	5
1A105	CLIN SPEC	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A106	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A108	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A110	LOBBY	WSF-13,14	RB-3	P-12	P-12, 21	P-12	P-12	P-1	1, 2, 5
1A112	SECRETARY	CPT-1	RB-2	P-20	P-12	P-20	P-12	AT-1	---
1A112A	ADMIN	CPT-1	RB-2	P-3	P-3	P-3	P-3	AT-1	5
1A112B	ADMIN	CPT-1	RB-2	P-3	P-3	P-3	P-3	AT-1	5
1A112C	DIRECTOR	CPT-1	RB-2	P-3	P-3	P-3	P-3	AT-2	5
1A113	GRIEVING	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A115	MDS	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A116	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1A202	STF. LOUNGE	WSF-14	RB-3A	P-3	P-3	P-3	P-25	AT-1	---
1A203	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A204	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1A205	SPEECH PATH	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A207	DENTAL EXAM	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A302A	CHARGING	WSF-13A	RB-3A	P-3 / WG-2	P-3	P-3 / WG-2	P-3 / WG-2	AT-1	2,17
1A302B	STORAGE	CONCS-1	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1	17
1A304	PET STORAGE	PPT-8	PPT-7A	EC-1	EC-1	EC-1	EC-1	AT-2	---
1A305	SOILED HOLDING	WSF-13A	IV-13A	EC-1 / WG-2	EC-1 / WG-2	EC-1 / WG-2	EC-1 / WG-2	AT-1	17
1A401	PHYSICIAN	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A402	ADMISSIONS	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A405	COMM	CONCS-1	RB-3	P-1	P-1	P-1	P-1	---	---
1A406	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A410	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1A504	CHAPLAIN	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A505	MEDITATION	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A506	FOOD SERVICES	QT-1	QTB-1	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-2	17
1A506A	FOOD SERVICES	QT-1	QTB-1	EC-1	EC-1	EC-1	EC-1	EC-2	---
1A506B	FOOD SERVICES	QT-1	QTB-1	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-2	---
1A506C	FOOD SERVICES	QT-1	QTB-1	EC-1 / CT-2	EC-1 / CT-2	EC-1 / CT-2	EC-1 / CT-2	EC-2	---
1A506D	FOOD SERVICES	QT-1	QTB-1	EC-1	EC-1	EC-1	EC-1	EC-2	---
1A506E	FOOD SERVICES	QT-1	QTB-1	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-1 / WP-16	EC-2	---
1A508	MULTIPURPOSE	WSF-13,14,15	RB-3	P-3, 19, 21	P-3, 19, 21	P-3, 19, 21	P-3, 19, 21	AT-1 / P-1	1, 2, 4, 8
1A508A	RECREATIONAL THERAPY	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A508B	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A508C	STORAGE	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	---
1A510	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1A512	VENDING	WSF-14	RB-3	P-12	P-12	---	P-12	P-1	1
1A601	EMERGENCY ELECTRIC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A602	BARBER	WSF-13	RB-3A	P-3	P-3	P-3	P-25	AT-1 / P-3	5
1A603	TRANSFER SWITCHES	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A605	NORMAL ELECTRIC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A607	WATER HEATERS	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A607A	MECHANICAL	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A607B	MECHANICAL	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1A611	PT	WSF-17	RB-3	P-3	P-25	P-3	P-3	AT-1 / P-1	4
1A611A	STORAGE								(none)
1A611B	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	EC-2	3
1A611C	TREATMENT	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	---
1A611D	REHAB STAFF	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1A611E	PT SUPER	WSF-13	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1AC01	CORR	WSF-13,14,15	PPT-18, RB-3	P-12	P-12	P-12, 21	P-12	AT-1 / P-1	1, 2
1AC02	CORR	WSF-13,14,15	PPT-18, RB-3	P-12	P-12, 21	P-12	P-12	AT-1 / P-1	1, 2
1AC03	CORR	WSF-14 / FM-2	RB-3	P-12	---	P-12	P-12	AT-1 / P-1	1, 2
1AC04	CORR	WSF-14 / FM-2	RB-3	---	---	---	---	P-1	1
1AC04A	CORR	WSF-15	RB-3	---	P-12	P-12	P-12	P-1	1, 2, 9
1AC04B	CORR	WSF-13, 15	RB-3	P-12	P-13	P-13	P-13	AT-1 / P-1	1, 2, 9
1AC04C	CORR	WSF-14	RB-3	---	P-12	P-12	P-12	P-1	---
1AC05	CORR	WSF-13,14,15	RB-3	ST-1 / PTM	P-12	P-12	P-12	AT-1 / P-1	1, 2, 19
1AC05B	CORR	WSF-13,14,15	RB-3	P-12, 20	P-12	P-12, 20	P-12	AT-1 / P-12	1, 2
1AC06	CORR	WSF-13,14,15	RB-3	P-12	P-12, 21	P-12	P-12, 21	AT-1 / P-1	1, 2, 9
1AC06A	CORR	WSF-13,14,15	RB-3	P-12	P-12	P-12	P-12, 21	AT-1 / P-1	1, 2, 9

NOTES:

SHEET NOTES

- A REFER TO SHEETS N-AI1.1A1-A THROUGH N-AI1.1C4 FOR CEILING DESIGN AND HEIGHT VARIATIONS.
- B REFER TO CASEWORK AND MILLWORK SCHEDULE ON SHEETS N-AI6.101-A THROUGH N-AI6.103 FOR FINISH LOCATIONS.
- C USE CG-1, CR-13, AND HR-1 WALL PROTECTION IN ALL LOCATIONS UNLESS NOTED OTHERWISE. SEE SHEET N-QH5.101 AND N-QH6.101 FOR MOUNTING HEIGHTS AND DETAILS.
- D ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS TO MATCH FLOOR MATERIAL.
- E ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.
- F ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21, UNLESS NOTED OTHERWISE
- G REFER TO SHEET N-IN6.106 AND N-IN6.107 FOR KEY TO FINISHES.
- H ALL WINDOW STOOLS TO BE SSM-5.
- I LIGHT COVES: PAINT THE INTERIOR SURFACE A GLOSS PAINT FINISH.

ID FINISH REMARKS

1. SEE SHEETS N-IN7.1A1-A THROUGH N-IN7.1C4 FOR FLOOR PATTERN PLANS
2. SEE SHEETS N-IN1.1A1-A THROUGH N-IN1.1C4 FOR WALL FINISH LOCATIONS PLANS
3. SEE SHEET N-AI2.206 FOR WALL ELEVATIONS WITH TILE MATERIAL LOCATIONS
4. LOCATE MOTORIZED WINDOW TREATMENT WT-3 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
5. LOCATE MANUAL WINDOW TREATMENT WT-1 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
6. LOCATE MOTORIZED WINDOW SHADES WT-3 AND WT-7 IN RESIDENT ROOMS. (DRAPERY NOT IN CONTRACT)
7. NOT USED
8. PAINT WAINSCOT ACCENT P-19 TO TOP OF DOOR FRAME WITH 2 INCH BULLNOSE TRANSITION PAINTED P-21, PAINT ABOVE TRIM P-3. ALIGN TOP OF BULLNOSE WITH THE TOP OF THE DOOR FRAME
9. PAINT FRONT OF SOFFIT TO MATCH ADJACENT WALL, PAINT HORIZONTAL SURFACE P-1
10. SEE INTERIOR ELEVATIONS ON SHEETS N-AI2.201 THROUGH N-AI2.207-A FOR ADDITIONAL INFORMATION
11. PAINT FINISH TO BE SATIN
12. SEE SHEET N-AI.2.207-A FOR BID ALTERNATE NO.3, FINISH UPGRADES
13. WG-2 WAINSCOT FROM FLOOR TO 30 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
14. NOT USED
15. WALL SIDE SPLASH TO BE PPT-6A, SEE ELEVATION SHEET N-AI2.206 FOR LOCATIONS
16. PPT-6A WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH EC-1 ABOVE
17. WG-2 WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
18. PAINT FRONT AND HORIZONTAL SURFACES OF SOFFIT P-3
19. INTERIOR STUCCO TO BE SMOOTH AND NON ABBRASSIVE

FINISH ABBREVIATIONS

AT	ACOUSTICAL CEILING TILE
CC	CUBICAL CURTAIN
CG	CORNER GAURD
CONCS	CONCRETE SEALED
CPT	CARPET TILE
CR	CRASH RAIL
EC	EPOXY COATING PAINT
FM	FLOOR MAT
GLT	GLASS TILE
GRT	GROUT
HPDL	HIGH PRESSURE DECORATIVE LAMINATE
HR	HAND RAIL
IV	INTEGRAL BASE
P	PAINT
PPT	PORCELAIN PAVER TILE
PTM	PAINT TO MATCH
QSM	QUARTZ SURFACE MATERIAL
QT	QUARRY TILE
QTB	QUARRY TILE BASE
RB	RUBBER BASE
SC	STUCCO, EXTERIOR (SEE N-IN6.107)
SSM	SOLID SURFACE MATERIAL
STN	STONE VENEER
WC	WALLCOVERING
WD	WOOD
WDV	WOOD VENEER
WG	WALL GUARD
WP	WALL PANEL
WSF	WELDED SHEET FLOOR
WT	WINDOW TREATMENT

BUILDING IS FULLY SPRINKLERED

No.	Description	Date
	RECORD DRAWINGS	12-01-2015

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue
Winter Park, Florida 32789
407 647 1039
1001 G Street,NW, Suite 1000
Washington, D.C. 20001
202 654 9300

Drawing Title
COMMUNITY LIVING CENTER
FINISH SCHEDULE - ADMINISTRATION
- AREA B, ZONE 1-2

Approved: Project Director

Project Title
A NEW HOSPITAL FOR
VAMC ORLANDO, FLORIDA

Location
Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.103

Dwg. 261 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

VA FORM 08-6231, OCT 1978

ROOM FINISH SCHEDULE - HOUSING C1-C2

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1D001	SOCIAL WRK	WSF-13A	RB-3	P-19	P-3	P-3	P-3	AT-1	---
1D002	MECH	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1D003	HEAD NURSE	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	5
1D004	OFFICE, ANP	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	5
1D005	COMM	CONCS-1	RB-3	P-1	P-1	P-1	P-1	---	---
1D006	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1D007	ELEC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1D008	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1D009	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1D010	STF. LOUNGE	WSF-14	RB-3A	P-25	P-3	P-3	P-3	P-1	---
1D012	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1D012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D013	OFFICE, PCM	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	---
1D014	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1D014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D015	CLEAN	WSF-13A	RB-3	EC-1	EC-1 / WG-2	EC-1	EC-1	AT-2	2,17
1D016	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1D016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D017	LIVING	CPT-13	RB-3	P-3	P-3	P-3	---	P-1	1, 2
1D018	ISO. BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	AT-1 / P-1	1, 2, 6, 9, 10
1D018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D019	CONCIERGE	CPT-13	RB-3	P-3	P-3	P-3	---	AT-1 / P-3	1, 2, 10, 12
1D020	BEDROOM	WSF-13,14	RB-3	P-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D021	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	---	P-3 / WG-2	P-1	1, 2, 13
1D022	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1D022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D023	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1D024	BEDROOM	WSF-13,14	RB-3	P-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D025	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	P-3 / WG-2	---	P-3 / WG-2	P-1	1, 2, 13
1D026	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1D026A	PANTRY	WSF-13	RB-3	P-3	P-3	P-3 / PPT-6A	P-3	AT-1	11
1D027	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1D027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D029	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1D029A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D030	BEDROOM	WSF-13,14	RB-3	P-41	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D030A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D031	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1D032	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-41	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D032B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1D034	BEDROOM	WSF-13,14	RB-3	P-40	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D034A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D036	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-40	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D036A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D037	LIVING	CPT-13	RB-3	---	P-3	---	P-3, 20 / STN-1	P-1	1, 2, 10
1D037A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1D038	BEDROOM	WSF-13,14	RB-3	P-43	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D038A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D040	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-43	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1D040A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1D041	SUPPLY	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	---
1D042	QUIET ROOM	WSF-14	RB-3	P-3	P-3	P-25	P-3	AT-1 / P-1	6, 9, 10
1D043	EQUIP.	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	2,17
1D045	EXAM	WSF-13	RB-3A	P-3	P-3	P-3	P-19	AT-1 / P-3	---
1D047	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1DC01	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1DC02	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1DC03	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1DC03A	CORR	WSF-13,14	RB-3	P-3	P-3, 15, 23	P-3	P-3,12	AT-1 / P-1	1, 2, 12

ROOM FINISH SCHEDULE - HOUSING C1-C2

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING	ID FINISH REMARKS
1DC04	CORR	WSF-13,14	RB-3	P-3	P-3	P-3, 20	P-3	AT-1 / P-1	1, 2
1DC05	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1DC05A	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1DC06	CORR	WSF-13,14	RB-3	P-3	P-3	P-3, 14, 23	P-3	AT-1 / P-1	1, 2
1DC07	CORR	WSF-13,14	RB-3	P-3	P-3, 20, 23	P-3	P-3, 14, 15, 17	AT-1 / P-1	1, 2
1E001	OFFICE, PCM	WSF-13A	RB-3	P-19	P-3	P-3	P-3	AT-1	---
1E002	EQUIP.	WSF-13A	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1	17
1E004	BEDROOM	WSF-13,14	RB-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E004A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E005	SOILED	WSF-13A	IV-13A	EC-1 / WG-2	EC-1	EC-1	EC-1 / WG-2	AT-2 / EC-2	2,17
1E006	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E006A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E007	MED.	WSF-13A	RB-3A	P-3	P-3 / WG-2	P-3 / WG-2	P-3	AT-1 / P-1	2,17
1E008	BEDROOM	WSF-13,14	RB-3	P-43	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E008A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E009	LIVING	CPT-13	RB-3	P-3	P-3	P-3	P-3	P-1	1, 2
1E010	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-43	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E010A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E011	CONCIERGE	CPT-13	RB-3	P-3	P-3	P-3	---	AT-1 / P-3	1, 2, 10, 12
1E012	BEDROOM	WSF-13,14	RB-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E013	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1E014	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1E014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E015	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	---	P-3 / WG-2	P-12 / WG-2	P-1	1, 2, 13
1E016	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1E016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E017	EQUIP. ALCOVE	WSF-13	RB-3	---	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1E018	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-42	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1E018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E020	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1E020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E022	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-40	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1E022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E022B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1E023	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1E024	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1E024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E025	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-43	AT-1 / P-3	1, 2, 6, 10, 18
1E025A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E026	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-41	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1E026A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E027	BEDROOM	WSF-13,14	RB-3	P-3	P-43	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1E027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E030	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1E030A	PANTRY	WSF-13	RB-3	P-3	P-3	P-3	P-3 / PPT-6A	AT-1	11
1E031	LIVING	CPT-13	RB-3	P-3	P-3	P-3	P-3, 20 / STN-1	P-1	1, 2, 10
1E031B	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1E032	BEDROOM	WSF-13,14	RB-3	P-41	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1E032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E033	NOURISH.	WSF-13	RB-3A	P-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1 / P-1	2,17
1E034	QUIET ROOM	WSF-14	RB-3	P-25	P-3	P-3	P-3	AT-1 / P-1	6, 9, 10
1E035	SOIL. HLD.	WSF-13A	IV-13	EC-1 / WG-2	EC-1 / WG-2	EC-1	EC-1 / WG-2	AT-2	2,17
1E037	PAT. SHOWER	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1E039	WARD CLK.	WSF-13	RB-3	P-3	P-20	---	---	P-1	1, 2, 9
1EC03	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1EC03A	CORR	WSF-13,14	RB-3	P-3	P-3, 14, 15, 23	P-3	P-3,12	AT-1 / P-1	1, 2, 12
1EC04	CORR	WSF-13,14	RB-3	P-3, 20	P-3	P-3	P-3	AT-1 / P-1	1, 2
1EC05	CORR	WSF-13	RB-3	---	P-3	P-3	P-3	AT-1 / P-1	1, 2
1EC06	CORR	WSF-13,14	RB-3	P-3, 14, 15, 17	P-3 / WG-2	P-3, 23 / WG-2	P-3 / WG-2	AT-1 / P-1	1, 2, 13
1EC07	CORR	WSF-13,14	RB-3	P-3	P-3, 20	P-3	P-3, 14	AT-1 / P-1	1, 2

FINISH UPGRADE - BID ALTERNATE NO. 3 SCHEDULE - HOUSING C1-C2

NUMBER	NAME	NORTH	EAST	SOUTH	WEST	ID FINISH REMARKS
1D019	CONCIERGE	BASE BID	BASE BID	P-3 / WC-3	BASE BID	1, 2, 12
1DC03A	CORR	BASE BID	BASE BID	BASE BID	P-3 / WP-21	1, 2, 12
IE011	CONCIERGE	P-3 / WC-3	BASE BID	BASE BID	BASE BID	1, 2, 12
1EC03A	CORR	BASE BID	BASE BID	BASE BID	P-3 / WP-21	1, 2, 12
1AC04D	CORR	BASE BID	ST-3 / WP-22	BASE BID	ST-3 / WP-22	1, 2, 12

NOTES:

SHEET NOTES:

A REFER TO SHEETS N-AI1.1A1-A THROUGH N-AI1.1C4 FOR CEILING DESIGN AND HEIGHT VARIATIONS.
B REFER TO CASEWORK AND MILLWORK SCHEDULE ON SHEETS N-AI6.101-A THROUGH N-AI6.103 FOR FINISH LOCATIONS.
C USE CG-1, CR-13, AND HR-1 WALL PROTECTION IN ALL LOCATIONS UNLESS NOTED OTHERWISE. SEE SHEET N-QH5.101 AND N-QH6.101 FOR MOUNTING HEIGHTS AND DETAILS.
D ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS TO MATCH FLOOR MATERIAL.
E ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.
F ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21, UNLESS NOTED OTHERWISE
G REFER TO SHEET N-IN6.106 AND N-IN6.107 FOR KEY TO FINISHES.
H ALL WINDOW STOOLS TO BE SSM-5.
I LIGHT COVES: PAINT THE INTERIOR SURFACE A GLOSS PAINT FINISH.

ID FINISH REMARKS

1 SEE SHEETS N-IN7.1A1-A THROUGH N-IN7.1C4 FOR FLOOR PATTERN PLANS
2 SEE SHEETS N-IN1.1A1-A THROUGH N-IN1.1C4 FOR WALL FINISH LOCATIONS PLANS
3 SEE SHEET N-AI2.206 FOR WALL ELEVATIONS WITH TILE MATERIAL LOCATIONS
4 LOCATE MOTORIZED WINDOW TREATMENT WT-3 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
5 LOCATE MANUAL WINDOW TREATMENT WT-1 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
6 LOCATE MOTORIZED WINDOW SHADES WT-3 AND WT-7 IN RESIDENT ROOMS. (DRAPERY NOT IN CONTRACT)
7 NOT USED
8 PAINT WAINSCOT ACCENT P-19 TO TOP OF DOOR FRAME WITH 2 INCH BULLNOSE TRANSITION PAINTED P-21, PAINT ABOVE TRIM P-3. ALIGN TOP OF BULLNOSE WITH THE TOP OF THE DOOR FRAME
9 PAINT FRONT OF SOFFIT TO MATCH ADJACENT WALL, PAINT HORIZONTAL SURFACE P-1
10 SEE INTERIOR ELEVATIONS ON SHEETS N-AI2.201 THROUGH N-AI2.207-A FOR ADDITIONAL INFORMATION
11 PAINT FINISH TO BE SATIN
12 SEE SHEET N-AI.2.207-A FOR BID ALTERNATE NO.3, FINISH UPGRADES
13 WG-2 WAINSCOT FROM FLOOR TO 30 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
14 NOT USED
15 WALL SIDE SPLASH TO BE PPT-6A, SEE ELEVATION SHEET N-AI2.206 FOR LOCATIONS
16 PPT-6A WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH EC-1 ABOVE
17 WG-2 WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
18 PAINT FRONT AND HORIZONTAL SURFACES OF SOFFIT P-3
19 INTERIOR STUCCO TO BE SMOOTH AND NON ABBRASSIVE

FINISH ABBREVIATIONS

AT	ACOUSTICAL CEILING TILE
CC	CUBICAL CURTAIN
CG	CORNER GAURD
CONCS	CONCRETE SEALED
CPT	CARPET TILE
CR	CRASH RAIL
EC	EPOXY COATING PAINT
FM	FLOOR MAT
GLT	GLASS TILE
GRT	GROUT
HPDL	HIGH PRESSURE DECORATIVE LAMINATE
HR	HAND RAIL
IV	INTEGRAL BASE
P	PAINT
PPT	PORCELAIN PAVER TILE
PTM	PAINT TO MATCH
QSM	QUARTZ SURFACE MATERIAL
QT	QUARRY TILE
QTB	QUARRY TILE BASE
RB	RUBBER BASE
SC	STUCCO, EXTERIOR (SEE N-IN6.107)
SSM	SOLID SURFACE MATERIAL
STN	STONE VENEER
WC	WALLCOVERING
WD	WOOD
WDV	WOOD VENEER
WG	WALL GUARD
WP	WALL PANEL
WSF	WELDED SHEET FLOOR
WT	WINDOW TREATMENT

BUILDING IS FULLY SPRINKLERED

No.	Description	Date
	RECORD DRAWINGS	12-01-2015

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE

145 Lincoln Avenue
Winter Park, Florida 32789
407 647 1039

1001 G Street,NW, Suite 1000
Washington, D.C. 20001
202 654 9300

Drawing Title: COMMUNITY LIVING CENTER FINISH SCEDULE - HOUSING AREA C1-C2

Approved: Project Director

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.104

Dwg. 262 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

VA FORM 08-6231, OCT 1978

ROOM FINISH SCHEDULE - HOUSING C3-C4									
ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS: NORTH	WALLS: EAST	WALLS: SOUTH	WALLS: WEST	CEILING	ID FINISH REMARKS
1A417	DIETICIAN	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	5
1AC04D	CORR	WSF-13,14,15	RB-3	P-12	ST-3 / P-12, 20 / PTM	P-12	ST-3 / P-12 / PTM	AT-1 / P-17, 23	1, 2, 12, 19
1B001	MECH	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1B002	SOCIAL WRK	WSF-13A	RB-3	P-19	P-3	P-3	P-3	AT-1	---
1B004	HEAD NURSE	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	5
1B005	OFFICE, ANP	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	5
1B006	COMM	CONCS-1	RB-3	P-1	P-1	P-1	P-1	---	---
1B007	HAC	PPT-8	PPT-7A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-1 / PPT-6A	EC-2	16
1B008	ELEC	CONCS-1	RB-3	P-3	P-3	P-3	P-3	---	---
1B009	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1B010	EQUIP.	WSF-13A	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	AT-1	17
1B012	BEDROOM	WSF-13,14	RB-3	P-43	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B013	OFFICE, PCM	WSF-13A	RB-3	P-19	P-3	P-3	P-3	AT-1	---
1B014	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-43	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B015	CLEAN	WSF-13A	RB-3	EC-1	EC-1	EC-1	EC-1 / WG-2	AT-2	2,17
1B016	BEDROOM	WSF-13,14	RB-3	P-40	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B017	LIVING	CPT-13	RB-3	P-3	---	P-3	---	P-1	1, 2
1B018	ISO. BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-41	P-3	P-3 / HPDL-4	AT-1 / P-1	1, 2, 6, 9, 10
1B018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B019	CONCIERGE	CPT-13	RB-3	P-3	---	P-3	P-3	AT-1 / P-3	1, 2, 10, 12
1B020	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1B020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B021	EQUIP. ALCOVE	WSF-14	RB-3	---	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1B022	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-43	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B023	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1B024	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-43	AT-1 / P-3	1, 2, 6, 10, 18
1B024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B025	EQUIP. ALCOVE	WSF-13	RB-3	---	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	1, 2, 13
1B026	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1B026A	PANTRY	WSF-13	RB-3	P-3 / PPT-6A	P-3	P-3	P-3	AT-1	11
1B027	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-43	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B029	BEDROOM	WSF-13,14	RB-3	P-43	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1B029A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B030	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B030A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B031	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1B032	BEDROOM	WSF-13,14	RB-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B032B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1B034	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B034A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B036	BEDROOM	WSF-13,14	RB-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B036A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B037	LIVING	CPT-13	RB-3	---	P-3, 20 / STN-1	---	P-3	P-1	1, 2, 10
1B037A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1B038	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-42	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B038A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B040	BEDROOM	WSF-13,14	RB-3	P-42	P-3 / HPDL-4	P-3 / HPDL-4	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1B040A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1B041	SUPPLY	WSF-13A	RB-3	P-3	P-3	P-3	P-3	AT-1	---
1B042	QUIET ROOM	WSF-14	RB-3	P-25	P-3	P-3	P-3	AT-1 / P-1	6, 9, 10
1B043	EQUIP.	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	P-1	2,17
1B045	EXAM	WSF-13	RB-3A	P-3	P-3	P-3	P-19	AT-1 / P-3	---
1B047	STF. TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1BC01	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC02	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC03	CORR	WSF-13,14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2

ROOM FINISH SCHEDULE - HOUSING C3-C4									
ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS: NORTH	WALLS: EAST	WALLS: SOUTH	WALLS: WEST	CEILING	ID FINISH REMARKS
1BC03A	CORR	WSF-13,14	RB-3	P-3	P-3, 12	P-3	P-3, 15, 23	AT-1 / P-1	1, 2, 12
1BC04	CORR	WSF-13,14	RB-3	P-3, 20	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC05	CORR	WSF-14	RB-3	P-3	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC05A	CORR	WSF-13,14	RB-3	---	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC06	CORR	WSF-13,14	RB-3	P-3, 14, 23	P-3	P-3	P-3	AT-1 / P-1	1, 2
1BC07	CORR	WSF-13,14	RB-3	P-3	P-3, 14, 15, 17	P-3	P-3, 20, 23	AT-1 / P-1	1, 2
1C002	TLT	PPT-8	PPT-7A	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	PPT-6, 6B, 7, 8A / EC-1	AT-1	3
1C003	OFFICE, PCM	WSF-13A	RB-3	P-3	P-3	P-19	P-3	AT-1	---
1C004	STF. LOUNGE	WSF-14	RB-3A	P-25	P-3	P-3	P-3	P-1	---
1C006	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-40	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C006A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C007	SOILED	WSF-13A	IV-13A	EC-1	EC-1 / WG-2	EC-1 / WG-2	EC-1	AT-2 / EC-2	2,17
1C008	BEDROOM	WSF-13,14	RB-3	P-40	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C008A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C009	MED.	WSF-13A	RB-3A	P-3 / WG-2	P-3	P-3	P-3 / WG-2	AT-1 / P-1	2,17
1C010	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-42	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C010A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C011	LIVING	CPT-13	RB-3	P-3	---	P-3	---	P-1	1, 2
1C012	BEDROOM	WSF-13,14	RB-3	P-42	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C012A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C013	CONCIERGE	CPT-13	RB-3	P-3	---	P-3	P-3	AT-1 / P-3	1, 2, 10, 12
1C014	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3	P-41	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C014A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C016	BEDROOM	WSF-13,14	RB-3	P-41	P-3	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C016A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C017	OXYGEN STOR.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1C018	BEDROOM	WSF-13,14	RB-3	P-3	P-43	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C018A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C019	EQUIP. ALCOVE	WSF-14	RB-3	P-3 / WG-2	P-3 / WG-2	P-3 / WG-2	---	P-1	1, 2, 13
1C020	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-43	AT-1 / P-3	1, 2, 6, 10, 18
1C020A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C021	EQUIP. ALCOVE	WSF-13	RB-3	P-3 / WG-2	P-3 / WG-2	---	P-3 / WG-2	P-1	1, 2, 13
1C022	BEDROOM	WSF-13,14	RB-3	P-3	P-40	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C022A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C024	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-40	AT-1 / P-3	1, 2, 6, 10, 18
1C024A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C025	LAUNDRY	WSF-13	RB-3	EC-1	EC-1	EC-1	EC-1	AT-2	---
1C026	BEDROOM	WSF-13,14	RB-3	P-3	P-41	P-3 / HPDL-4	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C026A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C026B	ELEC	WSF-13A	RB-3	P-3	P-3	P-3	P-3	---	---
1C027	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-42	P-3	P-3 / HPDL-4	AT-1 / P-3	1, 2, 6, 10, 18
1C027A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C028	BEDROOM	WSF-13,14	RB-3	P-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	AT-1 / P-3	1, 2, 6, 10, 18
1C028A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C029	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-3	P-42	AT-1 / P-3	1, 2, 6, 10, 18
1C029A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C030	KITCHEN	WSF-13	RB-3	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-3 / PPT-6A / GLT-1	P-1,3	1, 2, 9, 10, 11, 15
1C030A	PANTRY	WSF-13	RB-3	P-3	P-3 / PPT-6A	P-3	P-3	AT-1	11
1C031	LIVING	CPT-13	RB-3	---	P-3, 20 / STN-1	---	P-3	P-1	1, 2, 10
1C031A	CL.	WSF-14	RB-3	P-3	P-3	P-3	P-3	P-1	---
1C032	BEDROOM	WSF-13,14	RB-3	P-3 / HPDL-4	P-3 / HPDL-4	P-41	P-3	AT-1 / P-3	1, 2, 6, 10, 18
1C032A	TLT	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C033	NOURISH.	WSF-13	RB-3A	P-3 / WG-2	P-3 / WG-2	P-3	P-3 / WG-2	AT-1 / P-1	2,17
1C034	QUIET ROOM	WSF-14	RB-3	P-3	P-3	P-25	P-3	AT-1 / P-1	6, 9, 10
1C035	SOIL. HLD.	WSF-13A	IV-13	EC-1	EC-1 / WG-2	EC-1 / WG-2	EC-1 / WG-2	AT-2	2,17
1C037	PAT. SHOWER	PPT-8A	PPT-7A	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	PPT-6, 7 / GLT-1	EC-2	3
1C039	WARD CLK.	WSF-13	RB-3	---	---	P-3	P-20	P-1	1, 2, 9
1CC03	CORR	WSF-13,14	RB-3	---	P-3	P-3	P-3	AT-1 / P-1	1, 2
1CC03A	CORR	WSF-13,14	RB-3	P-3	P-3, 12	P-3	P-3, 14, 15, 23	AT-1 / P-1	1, 2, 12
1CC04	CORR	WSF-13,14	RB-3	P-3	P-3	P-3, 20	P-3	AT-1 / P-1	1, 2
1CC05	CORR	WSF-14	RB-3	---	P-3	P-3	P-3	AT-1 / P-1	1, 2
1CC06	CORR	WSF-13,14	RB-3	P-3, 23	P-3	P-3, 14, 15, 17	P-3	AT-1 / P-1	1, 2
1CC07	CORR	WSF-13,14	RB-3	P-3	P-3,14	P-3	P-3, 20	AT-1 / P-1	1, 2

FINISH UPGRADE - BID ALTERNATE NO. 3 SCHEDULE - HOUSING C3-4						
ROOM NUMBER	ROOM NAME	NORTH	EAST	SOUTH	WEST	ID FINISH REMARKS
1B019	CONCIERGE	P-3 / WC-3	BASE BID	BASE BID	BASE BID	1, 2, 12
1BC03A	CORR	BASE BID	P-3 / WP-21	BASE BID	BASE BID	1, 2, 12
1C013	CONCIERGE	BASE BID	BASE BID	P-3 / WC-3	BASE BID	1, 2, 12
1CC03A	CORR	BASE BID	P-3 / WP-21	BASE BID	BASE BID	1, 2, 12
1AC04D	CORR	BASE BID	ST-3 / WP-22	BASE BID	ST-3 / WP-22	1, 2, 12

NOTES:

SHEET NOTES

A REFER TO SHEETS N-AI1.1A1-A THROUGH N-AI1.1C4 FOR CEILING DESIGN AND HEIGHT VARIATIONS.
B REFER TO CASEWORK AND MILLWORK SCHEDULE ON SHEETS N-AI6.101-A THROUGH N-AI6.103 FOR FINISH LOCATIONS.
C USE CG-1, CR-13, AND HR-1 WALL PROTECTION IN ALL LOCATIONS UNLESS NOTED OTHERWISE. SEE SHEET N-QH5.101 AND N-QH6.101 FOR MOUNTING HEIGHTS AND DETAILS.
D ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS TO MATCH FLOOR MATERIAL.
E ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.
F ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21, UNLESS NOTED OTHERWISE
G REFER TO SHEET N-IN6.106 AND N-IN6.107 FOR KEY TO FINISHES.
H ALL WINDOW STOOLS TO BE SSM-5.
I LIGHT COVES: PAINT THE INTERIOR SURFACE A GLOSS PAINT FINISH.

ID FINISH REMARKS

1 SEE SHEETS N-IN7.1A1-A THROUGH N-IN7.1C4 FOR FLOOR PATTERN PLANS
2 SEE SHEETS N-IN1.1A1-A THROUGH N-IN1.1C4 FOR WALL FINISH LOCATIONS PLANS
3 SEE SHEET N-AI2.206 FOR WALL ELEVATIONS WITH TILE MATERIAL LOCATIONS
4 LOCATE MOTORIZED WINDOW TREATMENT WT-3 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
5 LOCATE MANUAL WINDOW TREATMENT WT-1 IN THIS LOCATION. SEE SHEET N-IN6.107 FOR ADDITIONAL INFORMATION
6 LOCATE MOTORIZED WINDOW SHADES WT-3 AND WT-7 IN RESIDENT ROOMS. (DRAPERY NOT IN CONTRACT)
7 NOT USED
8 PAINT WAINSCOT ACCENT P-19 TO TOP OF DOOR FRAME WITH 2 INCH BULLNOSE TRANSITION PAINTED P-21, PAINT ABOVE TRIM P-3. ALIGN TOP OF BULLNOSE WITH THE TOP OF THE DOOR FRAME
9 PAINT FRONT OF SOFFIT TO MATCH ADJACENT WALL, PAINT HORIZONTAL SURFACE P-1
10 SEE INTERIOR ELEVATIONS ON SHEETS N-AI2.201 THROUGH N-AI2.207-A FOR ADDITIONAL INFORMATION
11 PAINT FINISH TO BE SATIN
12 SEE SHEET N-AI.2.207-A FOR BID ALTERNATE NO.3, FINISH UPGRADES
13 WG-2 WAINSCOT FROM FLOOR TO 30 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
14 NOT USED
15 WALL SIDE SPLASH TO BE PPT-6A, SEE ELEVATION SHEET N-AI2.206 FOR LOCATIONS
16 PPT-6A WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH EC-1 ABOVE
17 WG-2 WAINSCOT FROM FLOOR TO 48 INCHES ABOVE FLOOR FINISH WITH PAINT ABOVE. FACTORY EDGE SHALL BE ON TOP AND CUT EDGE ON BOTTOM
18 PAINT FRONT AND HORIZONTAL SURFACES OF SOFFIT P-3
19 INTERIOR STUCCO TO BE SMOOTH AND NON ABBRASSIVE

FINISH ABBREVIATIONS

AT	ACOUSTICAL CEILING TILE
CC	CUBICAL CURTAIN
CG	CORNER GAURD
CONCS	CONCRETE SEALED
CPT	CARPET TILE
CR	CRASH RAIL
EC	EPOXY COATING PAINT
FM	FLOOR MAT
GLT	GLASS TILE
GRT	GROUT
HPDL	HIGH PRESSURE DECORATIVE LAMINATE
HR	HAND RAIL
IV	INTEGRAL BASE
P	PAINT
PPT	PORCELAIN PAVER TILE
PTM	PAINT TO MATCH
QSM	QUARTZ SURFACE MATERIAL
QT	QUARRY TILE
QTB	QUARRY TILE BASE
RB	RUBBER BASE
SC	STUCCO, EXTERIOR (SEE N-IN6.107)
SSM	SOLID SURFACE MATERIAL
STN	STONE VENEER
WC	WALLCOVERING
WD	WOOD
WDV	WOOD VENEER
WG	WALL GUARD
WP	WALL PANEL
WSF	WELDED SHEET FLOOR
WT	WINDOW TREATMENT

BUILDING IS FULLY SPRINKLERED

No.	Description	Date
	RECORD DRAWINGS	12-01-2015

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue, Winter Park, Florida 32789, 407 647 1039
1001 G Street,NW, Suite 1000, Washington, D.C. 20001, 202 654 9300

Drawing Title: COMMUNITY LIVING CENTER FINISH SCHEDULE - HOUSING AREA C3-C4

Approved: Project Director

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.105

Dwg. 263 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

FLOOR FINISH LEGEND									
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN	COLOR	SIZE	SURFACE / EDGE	GROUT	ID FINISH REMARKS
-									
CONCS-1	CONCRETE SEALED WITH PENETRATING SEALER	---	---	---	---	---	---	---	---
CPT-1	CARPET TILE	INTERFACE CARPET	1672002500	EQUATOR	MIST 5475	19-1/2" X 19-1/2"	---	---	BRICK PATTERN INSTALLATION
CPT-13	CARPET TILE	INTERFACE CARPET	123490250H	BIODIVERSITY	9314 FRONTIER	19-1/2" X 19-1/2"	---	---	WITH GLASBAC BACKING. ASHLAR INSTALLATION
FM-2	FLOOR MAT	CONSTRUCTION SPECIALTIES	#G1-C-HC-LB	PEDIGRID HEAVY DUTY	9303 SANDBAR	---	---	---	CARPET INSERT
PPT-8	PORCELAIN PAVER TILE	AFI	---	TUNDRA COLLECTION	AUTUMN	12" X 12"	---	GROUT-4	---
PPT-8A	PORCELAIN PAVER TILE	AFI	1092917	TUNDRA COLLECTION	AUTUMN MOSAIC	2" X 2"	---	GROUT-4	ADD ABBRASIVE GRAIN TO TILE TO MEET .7 COF, FOR WET AREAS
QT-1	QUARRY TILE	DAL TILE	OQ41	QUARRY TILE	BLAZE	6" X 6" X 1/2"	---	GROUT-5	---
WSF-13	WELDED SHEET FLOORING	GERFLOR	ACOUSTICAL	NERA COMPACT	0585 SATURNE PEROU	6' 6" X 82"	---	---	WITH CUSTOM CUSHION BACK
WSF-13A	WELDED SHEET FLOORING	GERFLOR	ACOUSTICAL	NERA COMPACT	0585 SATURNE PEROU	6' 6" X 82"	---	---	
WSF-14	WELDED SHEET FLOORING	GERFLOR	ACOUSTICAL	NERA COMPACT	1310 SYCAMORE GOLDEN	6' 6" X 82"	---	---	WITH CUSTOM CUSHION BACK
WSF-15	WELDED SHEET FLOORING	GERFLOR	ACOUSTICAL	NERA COMPACT	0592 OTTOWA POPLAR	6' 6" X 82"	---	---	WITH CUSTOM CUSHION BACK
WSF-17	WELDED SHEET FLOORING	GERFLOR	TARAFLEX SPORT FLOORING	TARAFLEX SPORT M PLUS	6381 MAPLE	4' 11" X 86' 6"	---	---	CUSHION BACK

BASE FINISH LEGEND							
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN	COLOR	SIZE	ID FINISH REMARKS
(none)							
IV-13	INTEGRAL VINYL BASE	GERFLOR	ACOUSTICAL	NERA COMFORT WOOD	0594 DAKOTA AUTUMN	6"	INTEGRAL BASE TO MATCH FLOOR
IV-13A	INTEGRAL VINYL BASE	GERFLOR	ACOUSTICAL	NERA COMPACT WOOD	0594 DAKOTA AUTUMN	6"	INTEGRAL BASE TO MATCH FLOOR
PPT-7A	PORCELAIN TILE	AFI	1092777	TUNDRA COLLECTION	TERRAIN	6" X 12"	---
PPT-18	PORCELAIN TILE	STONEPEAK	USG1818005	SLATE COLLECTION	EARTH	18" X 18"	---
QTB-1	QUARRY TILE BASE	DAL TILE	Q-3565	QUARRY TILE COVE	BLAZE	5" X 6"	---
RB-2	RUBBER BASE	JOHNSONITE	---	COVE	130 SISAL	4"	---
RB-3	RUBBER BASE	JOHNSONITE	---	COVE	259 TERRA FIRMA	6"	---
RB-3A	RUBBER BASE	JOHNSONITE	---	COVE	259 TERRA FIRMA	4"	---

WALL FINISH LEGEND									
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN / STYLE	COLOR	SIZE	SURFACE / EDGE	GROUT	ID FINISH REMARKS
CT-2	CERAMIC TILE	DALTILE	0139	SEMII GLOSS	CRISP LINEN	6 X 6		EXPOXY TO MATCH	TILE TO 6'-0" AFF WITH BULLNOSE TOP TRIM
EC-1	EPOXY PAINT	SHERWIN WILLIAMS	SW 6378	---	CRISP LINEN	---	---	---	EPOXY PAINT
GLT-1	GLASS TILE	INTERCERAMICS	MIXED GLASS MOSAIC	SHIMMER	CORAL BLEND	1" X 1"	---	GROUT-3	ON 12X12 SHEET
HPDL-4	HIGH PRESSURE DECORATIVE LAMINATE	WILSONART	7925-78	---	MONTICELLO MAPLE	---	---	---	---
P-1	PAINT	SHERWIN WILLIAMS	SW 7007	HARMONY	CEILING WHITE	---	---	---	---
P-3	PAINT	SHERWIN WILLIAMS	SW 6378	HARMONY	CRISP LINEN	---	---	---	---
P-12	PAINT	SHERWIN WILLIAMS	SW 6113	HARMONY	INTERACTIVE CREAM	---	---	---	---
P-14	PAINT	SHERWIN WILLIAMS	SW 7729	HARMONY	EDAMAME	---	---	---	---
P-15	PAINT	SHERWIN WILLIAMS	SW 6228	HARMONY	REFUGE	---	---	---	---
P-17	PAINT	SHERWIN WILLIAMS	1204	HARMONY	ONONDAGA CLAY	---	---	---	TO MATCH BENJAMIN MOORE ONONDAGA CLAY #1204
P-19	PAINT	SHERWIN WILLIAMS	SW 7727	HARMONY	KOI POND	---	---	---	---
P-20	PAINT	SHERWIN WILLIAMS	SW 0009	HARMONY	EASTLAKE GOLD	---	---	---	---
P-21	PAINT	BENJAMIN MOORE	AF-240	AFFINITY	SATCHEL	---	---	---	TO MATCH RB-3 259 TERRA FIRMA BASE
P-23	PAINT	SHERWIN WILLIAMS	SW 6354	HARMONY	ARMAGNAC	---	---	---	---
P-25	PAINT	SHERWIN WILLIAMS	1677	HARMONY	COLONIAL BLUE	---	---	---	TO MATCH BENJAMIN MOORE COLONIAL BLUE #1677
P-40	PAINT	SHERWIN WILLIAMS	7613	HARMONY	AQUA SPHERE	---	---	---	
P-41	PAINT	SHERWIN WILLIAMS	7733	HARMONY	BAMBOO SHOOT	---	---	---	
P-42	PAINT	SHERWIN WILLIAMS	7708	HARMONY	RUSTIC ADOBE	---	---	---	
P-43	PAINT	SHERWIN WILLIAMS	7702	HARMONY	SPICED CIDER	---	---	---	
PPT-6	PORCELAIN TILE	TCL	---	GALLERY COLLECTION	GOLDEN CREME	12" X 12"		GROUT-3	---
PPT-6A	PORCELAIN TILE	TCL		GALLERY COLLECTION	GOLDEN CREME	6" X 6"		GROUT-3	
PPT-6B	PORCELAIN TILE	TCL	---	GALLERY COLLECTION	GOLDEN CREME BULLNOSE	3" X 12"	---	GROUT-3	---
PPT-7	PORCELAIN TILE	AFI	1092614	TUNDRA COLLECTION	TERRAIN	12" X 12"	---	GROUT-3	---
PPT-8A	PORCELAIN TILE	AFI	1092917	TUNDRA COLLECTION	AUTUMN MOSAIC	2" X 2"	---	GROUT-3	ACCENT BAND
STN-1	STONE VENEER	REALSTONE SYSTEM	SLATE	LEDGESTONE	TERRACOTTA VERDE LEDGESTONE	6" X 24"	---		
WC-3	WALLCOVERING	DESIGNTEX WALLCOVERING	---	DIGITALLY PRINTED WALLCOVERING	---	FIELD VERIFY	TEXTURE	--	ALTERNATE BID NO. 3 REFER TO SHEETS N-IN6.101-A THROUGH N-IN6.102-A AND N-IN6.104 THROUGH N-IN6.105 FOR LOCATIONS
WG-2	WALL GUARD	C/S ACROVYN	---	PEBBLETTE TEXTURE	#253 PARCHMENT	4' X 8"	---	---	FACTORY EDGE SHALL BE ON TOP
WP-16	WALL PANEL	MARLITE	---	STANDARD FRP	S 118G ALMOND	4' X 8'	SMOOTH	--	WITH PVC TRIM MOLDINGS, INSTALL 4'-0" AFF
WP-21	WALL PANEL	MARLITE	---	MAP SYSTEM 40	WILSONART HUNTINGTON MAPLE 7929-38	CUSTOM	---	---	ALTERNATE BID NO 3. REFER TO SHEETS N-IN6.101-A THROUGH N-IN6.102-A AND N-IN6.104 THROUGH N-IN6.105 FOR LOCATIONS
WP-22	WALL PANEL	DESIGNTEX WALLCOVERING	---	DIGITALLY PRINTED SINTRA	---	42" X 42"	TEXTURE	---	ALTERNATE BID NO. 3 PANELS TO RECEIVCE 4 1" DIAMETER X 1/2" BARREL STANDOFFS, ALTERNATIVE BID FINISH UPGRADE SEE SHEET N-IN6.101-A THROUGH N-IN6.102-A AND N-IN6.104 THROUGH N-IN6.105 FOR LOCATIONS

CEILING FINISH LEGEND									
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN	COLOR	SIZE	EDGE	GRID	ID FINISH REMARKS
---	EXPOSED	NONE							
AT-1	ACOUSTICAL CEILING TILE	ARMSTRONG	#589	CIRRUS BEVELED TEGULAR EDGE	WHITE	24" X 24' X 3/4"	BEVEL TEGULAR	EXPOSED TEE GRID SUPRAFINE 9/16", WHITE	---
AT-2	ACOUSTICAL CEILING TILE	ARMSTRONG	#1715	CLEAN ROOM MYLAR, SQUARE EDGE, NON-PERFORATED	WHITE	24" X 24' X 5/8"	SQUARE	EXPOSED TEE GRID 15/16" (AL PRELUDE PLUS XL)	USE WITH #1720 (BORDER TILE)
EC-2	EPOXY PAINT	SHERWIN WILLIAMS	SW 7007	HARMONY	CEILING WHITE	---	---	---	EPOXY PAINT
P-1	PAINT	SHERWIN WILLIAMS	SW 7007	HARMONY	CEILING WHITE	---	---	---	---
P-3	PAINT	SHERWIN WILLIAMS	SW 6378	HARMONY	CRISP LINEN	---	---	---	---
P-15	PAINT	SHERWIN WILLIAMS	SW 6228	HARMONY	REFUGE	---	---	---	---
P-16	PAINT	SHERWIN WILLIAMS	6432	HARMONY	GARDEN SPOT				
P-17	PAINT	SHERWIN WILLIAMS	1204	HARMONY	ONONDAGA CLAY				TO MATCH BENJAMIN MOORE
P-18	PAINT	SHERWIN WILLIAMS	2063-20	HARMONY	DOWN POUR BLUE				TO MATCH BENJAMIN MOORE
P-19	PAINT	SHERWIN WILLIAMS	SW 7727	HARMONY	KOI POND	---	---	---	---
P-23	PAINT	SHERWIN WILLIAMS	6354	HARMONY	ARMAGNAC				
P-25	PAINT	SHERWIN WILLIAMS	1677	HARMONY	COLONIAL BLUE	---	---	---	TO MATCH BENJAMIN MOORE COLONIAL BLUE #1677

WALL PROTECTION FINISH LEGEND							
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN	COLOR	SIZE	ID FINISH REMARKS
CG-1	CORNER GUARD	C/S ACROVYN	SM-20E	---	#253 PARCHMENT	3"	48" HIGH FROM TOP OF BASE, PVC FREE, ANGLES AS REQUIRED
CG-13	CORNER GUARD	C/S ACROVYN	SM-20E	---	#373 AMBER CHERRY	3"	FULL HEIGHT FROM BASE TO CEILING, PVC FREE, ANGLES AS REQUIRED
CR-1	CRASH RAIL	C/S ACROVYN	SCR-48S	---	#253 PARCHMENT	8"	---
CR-7	CRASH RAIL	C/S ACROVYN	SCR-40E	---	#253 PARCHMENT	4"	PVC FREE, 34" AFF
CR-13	CRASH RAIL	C/S ACROVYN	SCR-48S	---	#373 AMBER CHERRY	8"	---
HR-1	HANDRAIL	C/S ACROVYN	RENAISSANCE COLLECTION	AW-LRVB	WOOD BEECH #053 HONEY	2.5"	ALL WOOD HANDRAIL
WG-2	WALL GUARD	C/S ACROVYN		PEBBLETTE TEXTURE	#253 PARCHMENT	4' X 8' X .060"	FACTORY EDGE INSTALLED AT TOP

NOTES:

SHEET NOTES

A MANUFACTURER'S TRADE NAMES AND NUMBERS USED HEREIN ARE ONLY TO IDENTIFY COLORS, FINISHES, TEXTURES AND PATTERNS. PRODUCTS OF OTHER MANUFACTURER'S EQUIVALENT TO COLORS, FINISHES, TEXTURES AND PATTERNS OF MANUFACTURER'S LISTED THAT MEET REQUIREMENTS OF TECHNICAL SPECIFICATIONS WILL BE ACCEPTABLE UPON APPROVAL IN WRITING BY CONTRACTING OFFICER FOR FINISH REQUIREMENTS.

B SEE FINISH SCHEDULES ON SHEETS N-IN6.101-A THROUGH N-IN6.105.

C SEE INTERIOR ELEVATIONS SHEETS N-AI2.201 THROUGH N-AI2.208 AND MILLWORK DETAILS SHEET N-AI3.101 THROUGH N-AI3.106 FOR ADDITIONAL FINISH LOCATION INFORMATION.

D ALL MILLWORK TO HAVE EASED EDGES UNLESS NOTED OTHERWISE SEE PLANS AND DETAILS.

E ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21 UNLESS NOTED OTHERWISE

F PAINT TO BE SEMI-GLOSS UNLESS OTHERWISE NOTED.

G ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS.

H FOR CASEWORK AND MILLWORK INFORMATION SEE SHEETS N-AI6.101-A THROUGH N-AI6.103.

I ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.

BUILDING IS FULLY SPRINKLERED

No.	Description	Date
	RECORD DRAWINGS	12-01-2015

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue, Winter Park, Florida 32789, 407 647 1039
1001 G Street,NW, Suite 1000, Washington, D.C. 20001, 202 654 9300

Drawing Title: COMMUNITY LIVING CENTER KEY TO FINISHES

Approved: Project Director

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.106

Dwg. 264 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

INTERIOR FINISH MATERIALS CONTINUED

MISCELLANEOUS LEGEND							
FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN	COLOR	SIZE	ID FINISH REMARKS
CC-2	CUBICLE CURTIAN	STANDARD TEXTILE	CM485105	CORONET	05 BRASS	---	---
FABRIC-1	FABRIC	MAHARAM	463770	LEDGER	018 GRASS	---	---
FABRIC-2	FABRIC	ARC COM	AC-67490	FRONTIER	CARIBBEAN #11	---	---
FABRIC-3	FABRIC	MAHARAM	463770	LEDGER	006 TANGERINE	---	---
FABRIC-4	FABRIC	ARC COM	AC-67484	FRONTIER	CORAL #5	---	---
FABRIC-5	FABRIC	MAHARAM	463770	LEDGER	022 OTTER	---	BENCH SEAT
FABRIC-6	FABRIC	ARC COM	AC-68232	SAVANNAH	MINT CHOCOLATE #3	---	BENCH BACK
GRT -3	GROUT	MAPEI	#06	---	HARVEST	---	---
GRT -4	GROUT	MAPEI	#24	---	SUMMER TAN	---	---
GRT -5	GROUT	MAPEI	#47	---	CHARCOAL	---	---
SC-2	SHOWER CURTAIN	STANDARD TEXTILE	---	BEZEL	03 APRICOT	---	---
WDV-2	WOOD VENEER	GREENLINE INDUSTRIES		FINELINE RECONSTITUTED FSC CERTIFIED ITALIAN POPLAR VENEER BY IPIR.	TO MATCH HPDL-6 NEVAMAR TOPAZ KHAYAWOOD W8369T. SUPPLIED BY HEITINK PLYWOOD TECHNOLOGIES, BLOOMINGTON, IN.	---	TYPICAL INTERIOR DOOR FINISH. DOOR CORE SUPPLIED BY HEITINK PLYWOOD TECHNOLOGIES, BLOOMINGTON, IN. HEITINK TO APPLY VENEER TO CORE. VENEER SUPPLIED BY GREENLINE INDUSTRIES, BEAUFORT, SC. FINELINE RECONSTITUTED FSC CERTIFIED ITALIAN POPLAR VENEER BY IPIR, STAIN TO MATCH HPDL-6.
WT-1	WINDOW TREATMENT	MECHOSHADE	MANUAL ROLLER SHADE	ECOVEIL BASKET WEAVE, 1350 SERIES	1366 EGGSHELL	5% OPENNESS	WHITE FASCIA
WT-3	WINDOW TREATMENT	MECHOSHADE	MOTORIZED ROLLER SHADE	ECOVEIL BASKET WEAVE, 1350 SERIES	1366 EGGSHELL	5% OPENNESS	WHITE FASCIA
WT-7	WINDOW TREATMENT	MECHOSHADE	MOTORIZED ROLLER SHADE	BLACK OUT SHADE, 0700 SERIES	0705 CHAMPAGNE	SOLID, NO OPENNESS	WHITE FASCIA

MISCELLANEOUS EQUIPMENT FINISH LEGEND			
EQUIPMENT CODE	EQUIPMENT	MANUFACTURER/ BASIS OF DESIGN	COLOR/ FINISH
4098-009	OVEN, ELECTRIC, BUILT-IN	GE PT916SMSS	STAINLESS STEEL APPLIANCES
4207-003	RANGE, ELECTRIC, BUILT-IN	GE JP655MSS	BLACK CERAMIC GLASS TOP WITH STAINLESS STEEL TRIM
A1030	LOCKER, 2 PERSON	PENCO, 60" HIGH DOUBLE TIER GUARDIAN KNOCKDOWN LOCKER	012 TAWNY TAN
A1066A	MIRROR, WITH WOOD FRAME, 36X47	AESTHETIC MIRROR, U35-BR6529BZ	BRONZE
A5145	GARMENT HOOK, DUBLE, SURFACE MOUNTED	BOBRICK, B-76727	STAINLESS STEEL, SATIN
F0820D	SUSPENDED TABLE, ROUND, 60" DIAMETER	T-FABCO, AF 1000E	WILSONART 1787-60 OXIDE (HPDL-10) TOP WITH VINYL BUMPER EDGE TO MATCH
U1123	HOOD, KITCHEN	GE JV930SC	FAUX STAINLESS STEEL APPLIANCES, BRUSHED
U9104	SIMULATED FIREPLACE	OPTI-FLAME, BUILT-IN PURIFIRE FIREBOX BF33	BFGLASS33BLK FRONT GLASS, BLACK ACCENTS; BFKIT33SS 3 PIECE SURROOUND-STAINLESS STEEL; BC3336U3 UNFINISHED CABINET
U9905	FAN, CEILING, EXTERIOR	EMERSON FANS, CONTEMPORARY, CF930ORB W/ LIGHT PACKAGE	OIL RUBBED BRONZE FINISH, MOHOGANY BLADES (ALL WEATHER B750RB), AMBER GLASS

EXTERIOR FINISH MATERIALS

DUPLICATE FINISH ABBREVIATION CODES USED IN BOTH INTERIOR AND EXTERIOR FINISH MATERIAL SCHEDULES
ARE NOT THE SAME TYPE MATERIALS OR COLORS.

FOR INTERIOR FINISH MATERIALS REFER TO FINISH CODES LISTED IN THE INTERIOR FINISH MATERIAL SCHEDULES.

FINISH CODE	MATERIAL	MANUFACTURER	MANUFACTURER NO.	PATTERN / STYLE / COLOR
CT-1	CONCRETE ROOF TILE	MONIERLIFE TILE	SAXONY 900 SLATE "FLORIDA BLEND"	CONCRETE TILE
M-1	STANDING SEAM ROOF	MERCHANT & EVANS	ZIP - RIB PROFILE 306	COLOR: EVERGREEN 435B617
P-1	PAINT			PAINT COLOR TO MATCH METAL PANEL CENTRIA 181 SLATE GREY
P-2	PAINT			PAINT COLOR TO MATCH EXTERIOR GLAZING KYNAR "SANDSTONE"
P-3	PAINT			COLOR TO MATCH STANDING SEAM ROOF- EVERGREEN 435B617
PC-1	PRECAST CONCRETE			MATCH APPROVED PRECAST SAMPLE ON SITE
PCS-1	DECORATIVE MEDALLION	PINEAPPLE GROVE DESIGNS	36SM-115	COLOR: ALLUVIAL SAND
PCS-2	DECORATIVE MEDALLION	PINEAPPLE GROVE DESIGNS	12SM-113	COLOR: ALLUVIAL SAND
PCS-3	DECORATIVE MEDALLION	PINEAPPLE GROVE DESIGNS	16SM-113	COLOR: ALLUVIAL SAND
SS-1	STONE VENEER	ELDORADO CO		STONE VENEER - STACKED STONE "ALDERWOOD"
ST-1	STUCCO			FINISH STUCCO TO MATCH SHERWIN WILLIAMS 6107 "NOMADIC DESERT"
ST-2				DELETE
ST-3	STUCCO			FINISH STUCCO TO MATCH BENJAMIN MOORE 954 "SPRING IN ASPEN"
ST-4	STUCCO			FINISH STUCCO TO MATCH BENJAMIN MOORE 1546 "GARGOYLE"

NOTES:

SHEET NOTES

A MANUFACTURER'S TRADE NAMES AND NUMBERS USED HEREIN ARE ONLY TO IDENTIFY COLORS, FINISHES, TEXTURES AND PATTERNS. PRODUCTS OF OTHER MANUFACTURER'S EQUIVALENT TO COLORS, FINISHES, TEXTURES AND PATTERNS OF MANUFACTURER'S LISTED THAT MEET REQUIREMENTS OF TECHNICAL SPECIFICATIONS WILL BE ACCEPTABLE UPON APPROVAL IN WRITING BY CONTRACTING OFFICER FOR FINISH REQUIREMENTS.

B SEE FINISH SCHEDULES ON SHEETS N-IN6.101-A THROUGH N-IN6.105.

C SEE INTERIOR ELEVATIONS SHEETS N-AI2.201 THROUGH N-AI2.208 AND MILLWORK DETAILS SHEET N-AI3.101 THROUGH N-AI3.106 FOR ADDITIONAL FINISH LOCATION INFORMATION.

D ALL MILLWORK TO HAVE EASED EDGES UNLESS NOTED OTHERWISE SEE PLANS AND DETAILS.

E ALL INTERIOR METAL DOOR AND WINDOW FRAMES TO BE PAINTED P-21 UNLESS NOTED OTHERWISE.

F PAINT TO BE SEMI-GLOSS UNLESS OTHERWISE NOTED.

G ALL WELDED SHEET VINYL (WSF) TO HAVE HEAT WELDED SEAMS.

H FOR CASEWORK AND MILLWORK INFORMATION SEE SHEETS N-AI6.101-A THROUGH N-AI6.103.

I ALL WOOD DOORS TO MATCH WDV-2 UNLESS NOTED OTHERWISE.

BUILDING IS FULLY SPRINKLERED

⚠No.	Description	Date
	RECORD DRAWINGS	12-01-2015

CONSULTANTS:

Professional Seals:

THESE RECORD DRAWINGS HAVE BEEN PREPARED BY THE DESIGN PROFESSIONAL BASED ON INFORMATION FURNISHED BY OTHERS. NO FIELD VERIFICATION OF THEIR CORRECTNESS HAS OCCURRED. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OR INFORMATION INCORPORATED INTO THESE RECORD DRAWINGS. REFER TO SUPPLEMENTAL SHOP DRAWINGS INCLUDED WITH THE RECORD DOCUMENT SET FOR ADDITIONAL INFORMATION.

ARCHITECT/ENGINEERS:

RLF ELLERBE BECKET
A JOINT VENTURE
145 Lincoln Avenue, Winter Park, Florida 32789, 407 647 1039
1001 G Street,NW, Suite 1000, Washington, D.C. 20001, 202 654 9300

Drawing Title: COMMUNITY LIVING CENTER KEY TO FINISHES

Approved: Project Director: Milan Brakic

Project Title: A NEW HOSPITAL FOR VAMC ORLANDO, FLORIDA

Location: Orlando, Florida

Date: 8 JUNE, 2009 | Checked: CME | Drawn: EB / RLF

Project Number: 673-950

Building Number: 11

Drawing Number: N-IN6.107

Dwg. 265 of 660

OFFICE OF FACILITIES MANAGEMENT

Department of Veterans Affairs

VA FORM 08-6231, OCT 1978