



7/16" PREDRILLED HOLE
EACH CORNER (TYPICAL)

EASE ALL EDGES AND CORNERS 1/8" RADIUS

GENERAL NOTES:

- ALL MARBLE DIMENSIONAL TOLERANCES ARE $\pm 1/16"$ UNLESS OTHERWISE SPECIFIED.
- THE TOP AND ALL SIDES SHALL BE FREE OF SCRATCHES, SAW MARKS, CHIPS OR CRACKS. FINISHED NICHE COVERS SHALL BE CRATED FOR SHIPMENT ACCORDING TO CONTRACT SPECIFICATIONS.
- MARBLE SHALL BE SELECT, WHITE MARBLE CONFORMING TO ASTM C119 WITH A SOUNDNESS CLASSIFICATION OF GROUP A, AS DEFINED BY THE MARBLE INSTITUTE OF AMERICA WITH UNIFORM AND FAVORABLE WORKING QUALITIES CONTAINING NO GEOLOGICAL FLAWS OR VOIDS.

CONVERSION TABLE

ENGLISH/ U.S. STANDARD	METRIC	ENGLISH/ U.S. STANDARD	METRIC
42"	106.68 cm	2"	5.08 cm
24"	60.96 cm	1 5/8"	4.13 cm
14 1/2"	36.83 cm	1"	2.54 cm
13"	33.02 cm	3/4"	1.90 cm
4"	10.16 cm	5/8"	1.59 cm
3"	7.62 cm	1/2"	1.27 cm
2 1/2"	6.35 cm	1/4"	.64 cm



NATIONAL
CEMETERY
ADMINISTRATION

Drawing Title
BLANK NICHE COVER LAYOUT
ARLINGTON NC / MARBLE

Approved: Linnie L. Lenox, Director Memorial Programs Service

Signed

Project Title
GOVERNMENT HEADSTONES
AND MARKERS

Marker Type

E1

Checked

KEE/KS

Drawn

MLT
SYSTEMS

Date
JULY 23, 2014

Project No.

DRAWING NO.

A-E1-BNC

Sheet 1 of 3