

## Brand Name or Equal Worksheet (“Salient Characteristics”) v 2.0

### **Brand Name Item:** Stryker Neptune 3 Rover (120V)

#### **1) Essential/significant physical, functional, or performance characteristics.**

- System must be compatible with our current docking stations at Mather VA
- Must have an adjustable top display that can be angled and rotated for easy viewing that is at least 7”
- Must have a large 8.4” interactive touch screen for viewing and navigating with displays and controls providing access to multiple functions
- Must have on-screen information to guide the user with onsite troubleshooting and servicing
- Must have dual canisters to allow for the collection and containment of liquids in one procedure, or multiple procedures
- Must have two independently controlled canisters to provide up to 8 lines of suction when using a 4-port manifold in each canister
- Must have an integrated smoke evacuator. The auto mode must detect surgical site smoke and adjust flow accordingly
- Must have tactile feedback dials with low/medium/high suction range indicators on the screen
- Must have storage for new manifolds
- Must have multiple suction range indicators with high suction audio alerts
- Must have technology that locks away suctioned biohazards
- Must have a powered I.V. pole with auto retraction that can hold four 3000cc bags on hooks
- Must have rotating power washers to provide an improved cleaning mechanism with multi-directional spray to cover the entire canister
- Suction range must be from 50-520 mmHG. The knobs on screen must be able to adjust in increments of 5 (low and medium suction) and 20 (high suction) for enhanced control.
- The 4L canister must be able to be illuminated
- Must have manifold port range indicators that display suction range to operating field

#### **2) Complete generic identification – O.R. Waste Management System**

#### **3) Applicable model/make/catalog number – Neptune 3 Rover (120V) (Product #0702001000)**

#### **4) Manufacturer name – Stryker**

## **Brand Name or Equal Worksheet (“Salient Characteristics”) v 2.0**

Per VAAR 811.104 and 811.105, I certify the following regarding the above information:

- The salient characteristics listed above are essential to the Government’s requirements.
- To my knowledge, the restrictions listed above will not limit the acquisition to an item peculiar to one manufacture.

Name, Date: Madison Pallante, 6/26/18