

Salient Characteristics

A. General

- a. Curtains and carriers to be designed for use in a medical environment with mesh upper section and fabric panel lower section. Privacy curtains to be constructed to allow a floor clearance of 12" from the finished floor to the bottom of the curtain fabric panel unless otherwise specified.
- b. Curtain fabric panels must work on a hookless track to facilitate safety. Curtains must be able to be removed without a ladder. Snaps or fasteners must be plastic and fasten firmly. The curtains must be able to withstand at least 200 washes.
- c. Curtain fabric panels will overlap each other if needed by approximately 4". Attic stock of privacy curtains to be 10% of total order for laundering and change out.
- d. Curtain fabric must be splash, stain and flame resistant. Curtain material must have inherent antimicrobial properties which are certified by third party testing. Xstatic silver antimicrobial fiber or equal.
- e. Carriers and tracks must be compatible with existing system or equal. Existing system is On the Right Track (OTRT) provided by Standard Textile. Curtains must be able to be removed from track without a ladder.
- f. Track to be installed on ceiling grid. All conflicts to be brought to the attention of the COR during or shortly after site visit.

B. Warranty and Code Requirements

- a. Lifetime Limited Warranty (up to 25 years), including 100% replacement.
- b. Testing of fabric abrasion, stain resistance and durability must be documented and available upon request.
- c. Curtains shall pass NFPA 701 – Standard Methods of Fire Tests for Flame Propagation of Textiles and Films.

C. Specifications

<u>ITEM</u>	<u>QTY</u>	<u>Description</u>	Preferred Manufacturers

1	100	Track and Carriers <ul style="list-style-type: none"> • Hookless attachment to curtain • Smooth, quiet operation • Easily removal and replacement of curtains without a ladder • Powder coated white finish 	Standard Textile OR EQUAL
2	100	Custom Made Cubicle Curtains for Exam rooms <ul style="list-style-type: none"> • 2 panels per track • 72" W x 72" L • Vertical Plastic Snap • Standard tie backs at all wall • 12" mesh • Tie backs 	ARC COM XStatic Structure-X, AC-33297X Spring #8 OR EQUAL
3	1	Mock-Up – One complete unit for approval prior to installation of remaining cubicle curtains and tracks.	
4		Installation	

D. Existing facility standard

