

## Salient Characteristics & Specifications for Patient Room Furnishings

Department of Veterans Affairs  
Sheridan VA Healthcare System  
1898 Fort Road, Sheridan, WY 82801

### Overview

Sheridan VA Healthcare System is expanding our Domiciliary Care for Homeless Veterans Program. This project adds approximately 13,450 square feet of new Mental Health Space to the SVAHCS footprint. New furnishings and artwork are required to fill the added space.

### Dimensions and Features

- - Wardrobes
    - a. Overall dimensions: 23.75 – 45" W x 23 – 23.25" D x 71" H
    - b. Available in the following layouts:
      - i. Single, No Drawers, 1 Door
      - ii. Single, 1 Drawer, 1 Door
      - iii. Single, 2 Drawers, 1 Door
      - iv. Double, No Drawers, 2 Doors
      - v. Double, 1 Drawer, 2 Doors
      - vi. Double, 2 Drawers, 2 Doors
      - vii. Armoire, 3 Drawers, 3 Doors
    - c. Must be available with a locking option on Doors and Drawers, if requested.
  - Armoires
    - a. Overall dimensions: 34.75" W x 22.75 – 24.75" D x 63.5 – 72.25" H
    - b. Available in the following layouts:
      - i. 3 Drawers, No Doors
      - ii. 3 Drawers, 2 Doors
      - iii. TV Armoire, DVD Shelf, 3 Drawers, No Doors
      - iv. TV Armoire, DVD Shelf, 3 Drawers, 2 Doors
    - c. Must be available with a locking option on Doors and Drawers, if requested.
  - Desks
    - a. Overall dimensions: 40.5 – 69" W x 19.5" D x 30" H
    - b. Available in the following layouts:
      - i. Small, 1 Drawer on Left or Right
      - ii. Medium, 1 Drawer on Left or Right
      - iii. Large, 1 Drawer on Left or Right
      - iv. Small, 1 Drawer on Left or Right
    - c. Must be available with a locking option on Drawers, if requested.
  - Hutches
    - a. Overall dimensions: 20.5" W x 11.75" D x 20" H
  - Bedside Stands
    - a. Overall dimensions: 21.25 – 21.75" W x 19 – 19.25" D x 25 – 30" H
    - b. Available in the following layouts:
      - i. Nightstand, 1 Drawer

- ii. Bedside Cabinet, 1 Drawer, 1 Door, Left or Right Hinged, Corian Top
  - iii. Bedside Cabinet, 1 Drawer, 1 Door, Left or Right Hinged
  - iv. Bedside Cabinet, 3 Drawers, Corian Top
  - v. Bedside Cabinet, 3 Drawers
  - vi. Bedside Cabinet, 4 Drawers
- c. Must be available with a locking option on Doors and Drawers, if requested.
- Chest/Dressers
  - a. Overall dimensions: 24.25 – 47.75"W x 19.25"D x 30 – 46.75"H
  - b. Available in the following layouts:
    - i. Chest, 5 Drawers
    - ii. Chest, 3 Drawers
    - iii. Chest, Wide, 4 Drawers
    - iv. Dresser, 6 Drawers
    - v. Chest, Wide 3 Drawers
  - c. Must be available with a locking option on Drawers, if requested.
- Headboards
  - a. Overall dimensions: 36 – 42"W x .75 – 1"D x 24"H
  - b. Available in the following layouts:
    - i. Single
    - ii. Single, Inlay Detail
    - iii. Twin
    - iv. Twin, Inlay Detail
- Footboards
  - a. Overall dimensions: 36 – 42"W x .75 – 1"D x 16"H
  - b. Available in the following layouts:
    - i. Single
    - ii. Single, Inlay Detail
    - iii. Twin
    - iv. Twin, Inlay Detail
- Mirrors
  - a. Overall dimensions: 23.25"W x .75"D x 45"H
  - b. Available in the following layouts:
    - i. Mirror
    - ii. Mirror, Square Corners

### **Construction Method**

- Casegoods must be of sturdy construction.
- Durable Finish
  - a. Should be up to 1/8" thick, mostly maintenance free, and offer protection against:
    - i. Moisture
    - ii. Graffiti
    - iii. Dirt and scuffs
  - b. Door Hinges
    - i. 100-degree self-closing, kitchen grade European hinges
    - ii. Smooth motion
  - c. Drawers
    - i. Constructed with dowel and mechanical fasteners for added strength
    - ii. 100lb static and dynamic load, euro drawer slides

- iii. Easy opening and closing
- d. Clothes Rod
  - i. Durable rod may be attached at standard height, or ADA height of 48" from the floor, if desired.
- e. Hardware
  - i. Door and Drawer pulls/knobs must be available in at least 28 standard styles and 24 premium styles.

#### **Surface Materials**

- Casegoods
  - a. Must have at least sixteen color/finish options available, to include natural looking wood patterns.
  - b. Must be resistant against chipping, marring or denting.
- Hardware
  - a. Must be available in at least 13 different metallic, and painted finishes.

#### **Warranty**

- Must offer at least a 10-year warranty that covers:
  - Performance
  - Durable Finish
  - Antimicrobial Protection
  - Warranty must be a full, non pro-rated warranty

#### **Testing**

- Must meet or exceed SCS Certified Furniture: SCS Indoor Air Advantage Gold
- Must be ANSI / BIFMA x7.1 Compliant

#### **Miscellaneous**

- Packaging
  - Goods shall be available to ship blanket wrapped to reduce waste and promote environmental responsibility.
  - Goods shall be available to ship with a packaging method in which the unit is placed on a corrugated cardboard pad, wrapped with a protective cloth and a plastic bag which is carefully shrunk with heat to secure it for shipping.
  - Manufacturer shall have documentation that units were tested to survive typical shipping conditions using testing methods compliant to ASTM D-999 standards.
- Assembly
  - Product shall have the option to be shipped fully assembled for ease of installation.
  - Service parts (arms, controls, bases, cylinders and casters) shall be offered.

## Salient Characteristics & Specifications

Department of Veterans Affairs  
Sheridan VA Healthcare System  
1898 Fort Road, Sheridan, WY 82801

Project: **Sheridan VA Healthcare System – Domiciliary Expansion, Patient Room Furnishings**  
Transaction Number: **666-18-3-137-0115**

### General

Built with additional reinforcement and a completely tamper-proof design, the health and safety of your patients are the most important features of the Fairview Behavioral Health collection. The Fairview Bedside is steel-reinforced with two open fixed shelves against a solid panel back and features edge detailing on the top and front.

### Dimensions and Features

- Wardrobes
  - a. Overall dimensions: 25"W x 24.5"D x 71"H
  - b. Available in the following layouts:
    - i. Single, Open Wardrobe
      - 1. Slanted Top
      - 2. Fixed Open Shelves
      - 3. No Doors, No Drawers
      - 4. Black Octagonal Glides lock in place
      - 5. 3/8" Bullnose Edge Banding
- Desks
  - a. Overall dimensions: 35.75"W x 23.75"D x 30"H
  - b. Available in the following layouts:
    - i. Compact Desk
      - 1. Wall Mount/Floor Mount Required
      - 2. Black Octagonal Glides lock in place
      - 3. 3/8" Bullnose Edge Banding
- Bedside Stands
  - a. Overall dimensions: 21.25"W x 18.25"D x 30"H
  - b. Available in the following layouts:
    - i. Bedside Stand
      - 1. Wall Mount/Floor Mount Required
      - 2. 2 Open Fixed Shelves
      - 3. Solid Panel on Back
      - 4. Black Octagonal Glides lock in place
      - 5. 3/8" Bullnose Edge Banding
- Platform Beds
  - a. Overall dimensions: 24.25 – 47.75"W x 19.25"D x 30 – 46.75"H
  - b. Available in the following layouts:
    - i. Single Bed, Closed Sides
    - ii. Single Bed, Open Left Side
    - iii. Single Bed, Open Right Side
  - c. Must be available with a locking option on Drawers, if requested.
  - d. Floor Mount
  - e. Black Octagonal Glides lock in place
  - f. 3/8" Bullnose Edge Banding

### **Construction Method**

- Casegoods must be of sturdy, steel frame construction.
- Durable Finish
  - a. Should be up to 1/8" thick, mostly maintenance free, and offer protection against:
    - j. Moisture
    - iv. Graffiti
    - v. Dirt and scuffs
  - f. Drawers
    - i. Constructed with dowel and mechanical fasteners for added strength
    - ii. 100lb static and dynamic load, euro drawer slides
    - iii. Easy opening and closing

### **Surface Materials**

- Casegoods
  - a. Must have at least sixteen color/finish options available, to include natural looking wood patterns.
  - b. Must be resistant against chipping, marring or denting.

### **Warranty**

- Must offer at least a 10-year warranty that covers:
  - o Performance
  - o Durable Finish
  - o Antimicrobial Protection
  - o Warranty must be a full, non pro-rated warranty

### **Testing**

- Must meet or exceed SCS Certified Furniture: SCS Indoor Air Advantage Gold
- Must be ANSI / BIFMA x7.1 Compliant

### **Miscellaneous**

- Packaging
  - o Goods shall be available to ship blanket wrapped to reduce waste and promote environmental responsibility.
  - o Goods shall be available to ship with a packaging method in which the unit is placed on a corrugated cardboard pad, wrapped with a protective cloth and a plastic bag which is carefully shrunk with heat to secure it for shipping.
  - o Manufacturer shall have documentation that units were tested to survive typical shipping conditions using testing methods compliant to ASTM D-999 standards.
- Assembly
  - o Product shall have the option to be shipped fully assembled for ease of installation.
  - o Service parts (arms, controls, bases, cylinders and casters) shall be offered.

## **Salient Characteristics & Specifications**

Department of Veterans Affairs  
Sheridan VA Healthcare System  
1898 Fort Road, Sheridan, WY 82801

Project: **Sheridan VA Healthcare System – Domiciliary Expansion, Patient Room Furnishings**  
Transaction Number: **666-18-3-137-0115**

### **General**

Classic and refined, the Torretta Dining chair makes meal time a special occasion. Available without arms or if you choose, custom curved arms provide spacious comfort and ingress/egress support. The stunning show frame back upholstery style ensures your comfort. Available with Diamond Back insert. Detailing this sophisticated brings a new level of design to any location.

### **Dimensions and Features**

- Overall Dimensions
  - a. Overall Depth 26.5"
  - b. Overall Width 25"
  - c. Overall Height 38"
  - d. Seat Depth 18.5"
  - e. Seat Width 19.25"
  - f. Back Height from Seat 18.5"
  - g. Back Width 20.5"
  - h. Arm Height 26.50"
  - i. Arm Height from Seat 7"
  - j. Weight Capacity 250lbs

### **Construction Method**

- Chair frames and seats must be of steel reinforced, sturdy construction.
- Cushioning
  - a. Must be of multiple laminations of high-density polyurethane foam, or similar.
- Must be available in commercial healthcare grade upholsteries (100,000 or greater double-rubs) graded-in to include:
  - a. Crypton or similar fabric with moisture barrier
  - b. Vinyl (plain, textured and patterned)
  - c. PVC Free Vinyl
- Seams should be double stitched, with seam binding or equivalent, for extended durability.
- Finish should be up to 1/8" thick, mostly maintenance free, and offer protection against:
  - a. Moisture
  - b. Graffiti
  - c. Dirt and scuffs

### **Surface Materials**

- Chairs
  - a. Must have at least the following upholstery options available:
    - i. Seat Fabric: Momentum, Beeline Epu – Portobello Vinyl
    - ii. Inside and Outside Back Fabric:
      - 1. CF Stinson, Piccadilly – 64831 Pacific
      - 2. Arc Com, Laurel AC-69608 – Caribbean #9
    - iii. Fabric with soil-retardant treatment
    - iv. Dimensional Knit (back only)
    - v. Leather
    - vi. Vinyl
    - vii. COM (Customer's Own Material)
    - viii. COL (Customer's Own Leather)
  - b. Must have at least sixteen color/finish options available for chair frame and legs, to include natural looking wood patterns.
  - c. Frame must be resistant against chipping, marring or denting.

### **Warranty**

- Must offer at least a 10-year warranty that covers:
  - Performance
  - Durable Finish
  - Antimicrobial Protection
  - Warranty must be a full, non pro-rated warranty

### **Testing**

- Must meet or exceed SCS Certified Furniture: SCS Indoor Air Advantage Gold
- Must be ANSI / BIFMA x7.1 Compliant

### **Miscellaneous**

- Packaging
  - Goods shall be available to ship blanket wrapped to reduce waste and promote environmental responsibility.
  - Goods shall be available to ship with a packaging method in which the unit is placed on a corrugated cardboard pad, wrapped with a protective cloth and a plastic bag which is carefully shrunk with heat to secure it for shipping.
  - Manufacturer shall have documentation that units were tested to survive typical shipping conditions using testing methods compliant to ASTM D-999 standards.
- Assembly
  - Product shall have the option to be shipped fully assembled for ease of installation.
  - Service parts (arms, controls, bases, cylinders and casters) shall be offered.