



1 PARTIAL FLOOR PLAN-NEW  
SCALE: 1/8" = 1'-0"

**FLOOR PLAN NOTES:**

- 1 5" TYPE "X" LEAD LINED GYP TO A HEIGHT OF 7' 8" TYPE X ABOVE. PRIME AND PAINT.
- 2 NEW 4" 20 GA STUD WALL WITH LEAD LINED GYP AND SOUND INSULATION
- 3 INSTALL DOORS AND FRAME WITH HARDWARE THAT WAS REMOVED DURING DEMOLITION
- 4 SEE ELEVATIONS FOR CASEWORK MODIFICATIONS.
- 5 NEW CORNER GUARD TO MATCH EXISTING.
- 6 INSTALL FLOORING IN NEW AREA TO MATCH EXISTING.
- 7 PATCH AND REPAIR FLOORING AT CASEWORK TO MATCH EXISTING.
- 8 PATCH, REPAIR AND PAINT EXISTING WALL.
- 9 PROVIDE AND INSTALL NEW WALL MOUNTED MONITOR ARM PER SOW
- 10 PROVIDE AND INSTALL WALL PROTECTION TO MATCH EXISTING.

**FLOOR PLAN GENERAL NOTES:**

1. ALL DIMENSIONS ARE TO FINISH FACE OF WALL OR PARTITION.
2. GENERAL CONTRACTOR TO FIELD VERIFY DIMENSIONS.
3. GENERAL CONTRACTOR TO SURVEY EXISTING CONDITIONS & COMPARE THEM WITH THE PROPOSED SCOPE OF WORK. INFORM COR OF ANY CONFLICTS BETWEEN EXISTING CONDITIONS AND PROPOSED SCOPE BEFORE COMMENCEMENT OF WORK.
4. GENERAL CONTRACTOR SHALL STRIVE TO RE-USE ALL CORNER GUARDS, HAND RAILS, AND CRASH GUARD WHERE PERMISSIBLE, UNLESS EXPLICITLY INDICATED OTHERWISE.

**CONSULTANTS:**

1	UPDATED HAZARD RISK ASSESSMENT AND DHA	03/27/2008

**ARCHITECT/ENGINEERS:**

Drawing Title	Project Title	Project Number	Office of Construction and Facilities Management
FLOOR PLAN - NEW	3A-401 UPGRADE FOR ANESTHESIA EO	380-18-123	
Approved Project Director	Location	Drawing Number	Date
		AS-101	