



1 THIRD FLOOR FRAMING PLAN
1/8" = 1'-0"

- LEGEND:**
- ENHANCE (E) STEEL CONNECTION, SEE BRACED FRAME ELEVATIONS
 - STEEL BEAM TO COLUMN MOMENT CONNECTION
 - A, B, C, ETC. - SEE COLLECTOR SCHEDULE 5/SS531. <SLRS>
- SHEET NOTES:**
- REPLACE (E) MECHANICAL EQUIPMENT WITH NEW SIMILAR UNITS OR SIMILAR WEIGHT/DIMENSIONS, S.M.D.
 - FOR EXISTING FRAMING SIZES CONTRACTOR TO VERIFY WITH EXISTING DRAWINGS AND VERIFY IN FIELD.
 - ITEMS NOTED <SLRS> ARE PART OF THE SEISMIC LOAD RESISTING SYSTEM AS INDICATED IN THE SPECIFICATIONS.
- KEY NOTES:**
- 1 ADD BENT PLATE ANCHORED TO SLAB AND WALL, SEE DETAIL 3/SS513.
 - 2 SEE TYPICAL BEAM TO BEAM CONNECTION DETAIL, SIMILAR.
 - (E) W21x55 BM, STRENGTHEN w/ 50 KSI STEEL PLATES, SEE TYPICAL DETAIL 6/SS111, MARK 'BU2'
 - 3 (N) CONCRETE COLLECTOR BEAM AT FLOOR-LEVEL LANDING BEAM.
 - 3B (N) CONCRETE COLLECTOR BEAM AT INTER-FLOOR LANDING BEAM ABOVE.
 - 4 STRENGTHEN EXISTING COLUMNS WITH FULL HEIGHT WELDED 5/8" STEEL PLATES, 36ksi. SEE TYPICAL DETAIL 6/SS111, MARK 'BU1' STRENGTHEN (E) COLUMN SPLICES AT FLOOR LEVELS PER DETAIL 11/SS514.
 - 4A STRENGTHEN EXISTING COLUMNS WITH FULL HEIGHT WELDED 5/8" STEEL PLATES 36 ksi, SEE TYPICAL DETAIL 6/SS111, MARK 'BU1'
 - 5 TYPICAL FULL-DEPTH BM-TO-BM CONNECTION AT END OF COLLECTOR, SEE 3/SS111.
 - 6 (N) 8" THICK SUSPENDED CONC. SLAB, S.A.D. FOR MORE INFO.
 - 7 COLLECTOR TO WALL CONNECTION, SEE 3/SS514.
 - (N) CONCRETE / METAL DECK AT (N) PERIMETER FRAMING. PROVIDE VERCO FORMLOCK W2 DECK (OR EQUIVALENT) WITH 3 1/2" LWC TOPPING. MATCH DEPTH OF ADJACENT (E) MTL DECK AND (E) CONC. SLAB. VERIFY (E) DEPTHS IN FIELD. CONTACT ENGINEER IF THERE ARE DISCREPANCIES. SEE 5/SS521 FOR REQ'D METAL DECK PROPERTIES. FLUTES TO RUN PERPENDICULAR TO THE ADJACENT PERIMETER WALL. PROVIDE 3/4" DIA. SHEAR STUDS @ 12" O.C. TO ALL STEEL FRAMING BELOW PER 5/SS513. PROVIDE #4 @ 12" O.C., E.W., REINF.
 - 9 W12x19 BRACING BEAM WITH TYPICAL FULL-DEPTH CONNECTION EACH END. PROVIDE 3/4" DIA. CORED STUDS @ 12" O.C. ON BEAM, SEE DETAIL 5/SS513.
 - 10A (N) HSS10x10x5/8 STL. BRACES, SINGLE STORY X-CONFIGURATION.
 - 10B (N) 4" Ø XS PIPE STEEL BRACES, SINGLE STORY V-CONFIGURATION.
 - 11 DEMO (E) CONCRETE PARAPET TO TYPICAL TOP-OF-SLAB AT PERIMETER OF (N) FLOOR FRAMING
 - 12 (E) W21x55 BM, STRENGTHEN PER 5/SS516
 - 13 FOR EXISTING SLAB INFORMATION, SEE 13/SS121, TYPE E.
 - 14 W14x26 BEAM WITH FULL-DEPTH CONNECTION EACH END, PER 3/SS11. PROVIDE 3/4" DIA. CORED STUDS @ 12" O.C. ON BEAM, SEE DETAIL 5/SS513.
 - 15 CONTINUE BENT PL & ANCHORS BENEATH COLLECTOR AND TERMINATE AT EDGE OF CONCRETE WALL.
 - 16 STRENGTHEN (N) COLUMN WITH WELDED 3/4" STEEL PLATES, 36 ksi, 3rd STORY ONLY, SEE TYPICAL DETAIL 6/SS111, MARK 'BU1'.

CONSULTANTS: Degenkolb DEGENKOLB ENGINEERS 235 Montgomery Street, Suite 500 San Francisco, CA 94104 415.392.6952 Phone 415.981.3157 Fax www.degenkolb.com 80584020.00		ARCHITECT/ENGINEERS: HMC Architects 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION		Project Number 570-215 Building Number 24		Office of Construction and Facilities Management 	
Drawing Title THIRD FLOOR FRAMING PLAN		Approved Project Director		Location VAMC FRESNO, CA		Drawing Number SF203 Dwg. 15 of 180			
Date January 31, 2012		Checked WQ		Drawn MAM/KM					