



LIBRARY MAIN ROOM - PLAN 1/SS201

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
A1	WALL-MOUNTED BOOK SHELF	18'-0"	1'-0"	6'-10"	6/- SIM, T&B	2600
A2	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A3	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A4	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A5	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A6	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A7	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A8	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A9	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A10	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A11	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A12	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A13	FREE-STANDING BOOK SHELF	15'-0"	2'-0"	7'-6"	3/- AND 15/-	4500
A14	WALL-MOUNTED BOOK CASE	3'-0"	1'-4"	6'-0"	5/- SIM, T&B	900

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
B1	WALL-MOUNTED BOOK SHELF	6'-0"	1'-2"	7'-6"	5/- SIM, T&B	1100
B2	WALL-MOUNTED BOOK SHELF	21'-0"	1'-2"	7'-6"	5/- SIM, T&B	3600
B3	WALL-MOUNTED BOOK SHELF	15'-0"	1'-2"	7'-6"	5/- SIM, T&B	2600
B4	WALL-MOUNTED BOOK SHELF	3'-0"	1'-2"	7'-6"	5/- SIM, T&B	600

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb, U.O.N.)
C1	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C2	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C3	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C4	WALL-MOUNTED CABINETS		1'-0"	4'-5'-7'-0"	5/- SIM, T&B	200 lbs/ ft.
C5	OLYMPUS CKX41 MICROSCOPE	1'-0"	1'-4"	1'-6"	7/- OR 9/-	100
C6	SORVALL BIOFUGE STRATOS	2'-1"	1'-11"	1'-3"	9/-	500
C7	LIGHTING BOX	1'-0"	0'-3"	0'-8"	9/- SIM	100
C8	SINK W/ BASE UNIT	5'-0"	2'-0"	3'-8"	3/-	500
C9	KENDROLAB PRODUCTS ISOTEMP	2'-2"	2'-0"	3'-5"	9/-	500
C10	BATHWATER EQUIP.	1'-2"	0'-10"	0'-7"	9/-	200
C11	ORBIT SHAKER	0'-10"	1'-1"	0'-7"	9/-	200
C12	HOT PLATE	0'-8"	0'-10"	0'-4"	9/-	100
C13	AB15PLUS PH METER	0'-5"	0'-7"	0'-3"	7/-	100
C14	SAFETY SHOWER			7'-6"	13/- (BOT.)	500
C15	HOT PLATE	0'-8"	0'-10"	0'-4"	9/-	100
C16	MICROPLATE READER	1'-2"	1'-4"	0'-6"	9/-	200
C17	BIOHAZARD ROLLING GARBAGE BIN	2'-0"Ø		3'-0"	6/- SIM	500
C18	CENTRIFUGE	0'-9"Ø		0'-11"	9/-	250
C19	TROPICOLER	1'-0"	0'-9"	0'-7"	9/-	200
C20	SINK W/ BASE UNIT	4'-0"	2'-0"	3'-2"	3/-	500
C21	FUME HOOD	4'-6"	2'-8"	7'-4"	1/- AND 12/-	1100

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
D1	WALL-MOUNTED SHELVES	4'-0"	1'-1"	4'-6"-7'-0"	5/- SIM, T&B	700
D2	MICROTOME	0'-9"	1'-8"	1'-0"	9/-	280
D3	UNDERHUNG CABINETS	4'-0"	1'-10"	2'-0"	5/- SIM, T&B	400
D4	ROLLING CART	2'-3"	1'-6"	3'-5"	6/-	900
D5	YELLOW CABINET	3'-8"	1'-6"	5'-9"	1/- AND 5/-	700
D6	COUNTERTOP SHELVES	3'-0"	1'-0"	4'-0"	3/- AND 15/- SIM	300

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
E1	FILING CABINET	3'-4"	1'-2"	7'-0"	3/- AND 5/-	1000
E2	WALL CABINET	3'-0"	1'-0"	2'-6"	5/- SIM, T&B	500
E3	REFRIGERATOR	2'-4"	1'-4"	5'-0"	3/- (FRONT) AND 5/- (REAR)	500
E4	SPECTROPHOTOMETER	3'-6"	2'-0"	0'-10"	9/-	500
E5	PRINTER	1'-10"	1'-10"	2'-0"	9/-	300
E6	FUME HOOD	4'-0"	2'-0"	6'-8"	1/- AND 5/-	1100
E7	WATER BATH	0'-10"	1'-10"	2'-2"	9/-	500
E8	WATER BATH	0'-10"	1'-10"	2'-2"	9/-	500
E9	HYDRIDIZATION OVEN	1'-0"	1'-0"	1'-3"	9/-	300

1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720
T 559 322 2444 / www.hmcarchitects.com

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (LB)
G1	BIOHAZARD FRIDGE	4'-0"	4'-0"	6'-2"	8/- (FRONT) AND 5/- (REAR)	2670
G2	EYE WASH	1'-0"Ø		3'-0"	13/- SIM	500
G3	SINK	5'-0"	2'-0"	3'-2"	3/-	500
G4	FREEZER	1'-8"	2'-0"	2'-6"	9/- AND 5/-	500
G5	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G6	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G7	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G8	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300
G9	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
H1	TV	3'-0"	2'-6"	3'-0"	5/- SIM T&B OR 12/- SIM T&B	300
H2	PROJECTOR	2'-6"	2'-6"	1'-0"	3/- AND 5/-	250
H3	SERVER RACK	4'-0"	2'-0"	6'-3"	3/- AND 5/-	1000 (V.I.F.)
H4	HVAC INTAKE	8'-6"	6'-0"	4'-3"	3/-	1000 (V.I.F.)
H5	HVAC HANDLER	5'-0"	7'-0"	4'-0"	3/-	5000 (V.I.F.)

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
I1	FAN	4'-0"	6'-0"	3'-6"	3/-	1000 (V.I.F.)
I2	HANDLER	3'-0"	7'-0"	4'-0"	3/-	5000 (V.I.F.)
I3	INTAKE	5'-0"	2'-0"	3'-2"	3/-	1000 (V.I.F.)
I4	FAN	6'-0"	6'-0"	3'-8"	3/-	1000 (V.I.F.)

DEGENKOLB ENGINEERS
235 Montgomery Street, Suite 500
San Francisco, CA 94104
415.392.6952 Phone
415.981.3157 Fax
www.degenkolb.com
80584020 00



Approved: Project Director

Location

Date	Checked	Drawn
January 31, 2012	WG	MAM/KM

Drawing Number

SS532
Dwg. 39 of 180

Department of
Veterans Affairs