



- BASEMENT PLAN LEGEND**
- (E) FULL HEIGHT STRUCTURAL CONCRETE WALL
  - (E) METAL STUD WALL WITH SOUND BATT INSULATION. WALL AND FINISHES FULL HEIGHT FROM FINISH FLOOR TO DECK ABOVE.

- BASEMENT FLOOR PLAN - REMODEL KEYNOTES**
- 1 EXISTING ELEVATOR EQUIPMENT.
  - 2 EXISTING ELEVATOR CONTROL PANEL.
  - 3 EXISTING ELEVATOR DISCONNECT.
  - 4 EXISTING IDU ABOVE (SHOWN DASHED).
  - 5 ELEVATOR EQUIPMENT. (OMIT ELEVATOR EQUIPMENT AT DEDUCTIVE ALTERNATE 1)
  - 6 ELEVATOR CONTROL PANEL. (OMIT ELEVATOR CONTROL PANEL AT DEDUCTIVE ALTERNATE 1)
  - 7 ELEVATOR DISCONNECT. (OMIT ELEVATOR DISCONNECT AT DEDUCTIVE ALTERNATE 1)
  - 8 42" x 42" CLEAR FLOOR SPACE.
  - 9 PROPOSED ROUTE OF ELEVATOR HYDRAULIC LINES. MANUFACTURER TO VERIFY. (OMIT HYDRAULIC LINES AT DEDUCTIVE ALTERNATE NO. 1)

1 BASEMENT FLOOR PLAN  
1/8" = 1'-0"

<div>Revisions</div> <table><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr></table>									<div>CONSULTANTS:</div> <table><tr><td> </td></tr><tr><td> </td></tr><tr><td> </td></tr><tr><td> </td></tr><tr><td> </td></tr><tr><td> </td></tr></table>							<div>ARCHITECT/ENGINEERS:</div> <div><div><div>REGISTERED ARCHITECT STATE OF CALIFORNIA NO. C-24897</div></div><div><div>HMC Architects</div><div>1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com</div></div></div>	<div>Drawing Title</div> <div>BASEMENT FLOOR PLAN</div> <div>Approved Project Director</div> <table><tr><td> </td></tr></table>		<div>Project Title</div> <div>BUILDING 24 SEISMIC CORRECTION AND ADDITION</div> <div>Location</div> <div>VAMC FRESNO, CA</div> <div>Date</div> <div>October 14, 2011</div> <div>Checked</div> <div>BB</div> <div>Drawn</div> <div>CLO/JH</div>	<div>Project Number</div> <div>570-215</div> <div>Building Number</div> <div>24</div> <div>Drawing Number</div> <div>AS200</div> <div>Dwg. 45 of 180</div>	<div>Office of Construction and Facilities Management</div> <div><div>Department of Veterans Affairs</div></div>