



- REFLECTED CEILING PLAN - DEMOLITION KEYNOTES
- 1 (E) SUNSCREEN TO REMAIN, U.N.O. REMOVE DEBRIS AND CLEAN VIA POWERWASH.
 - 2 REMOVE LAY-IN CEILING GRID AND TILES, TYPICAL THIS FLOOR.
 - 3 REMOVE CEILING LIGHTS, TYPICAL THIS FLOOR.
 - 4 REMOVE CEILING MOUNTED SPEAKERS, TYPICAL THIS FLOOR.
 - 5 REMOVE HVAC DIFFUSERS, TYPICAL THIS FLOOR.
 - 6 REMOVE (E) CEILING ACCESS PANEL, TYPICAL THIS FLOOR.
 - 7 REMOVE GYPSUM BOARD CEILING, EXISTING FRAMING TO REMAIN, TYPICAL THIS FLOOR.
 - 8 REMOVE CEILING MOUNTED PROJECTOR. REINSTALL IN SAME LOCATION AFTER NEW CEILING WORK IS COMPLETE.
 - 9 REMOVE (E) SUNSCREEN (SUNSCREEN TO REMAIN AT DEDUCT ALTERNATE 1).
 - 10 REMOVE PORTION OF EXISTING SUNSCREEN SHOWN DASHED.
 - 11 REMOVE (E) SUNSCREEN (SUNSCREEN TO REMAIN AT DEDUCT ALTERNATE 5).
 - 12 EXPOSED ROOF DECK TO REMAIN.

1 DEMOLITION SECOND FLOOR REFLECTED CEILING PLAN
1/8" = 1'-0"

CONSULTANTS:		ARCHITECT/ENGINEERS:		Drawing Title		Project Title		Project Number		Office of Construction and Facilities Management Department of Veterans Affairs	
		HMC Architects		DEMOLITION SECOND FLOOR REFLECTED CEILING PLAN		BUILDING 24 SEISMIC CORRECTION AND ADDITION		570-215			
		1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Approved Project Director		VAMC FRESNO, CA		Building Number 24			
						Date October 14, 2011		Checked BB			
Revisions								Drawn CLO			
Date								AD302			
								Dwg. 54 of 180			