

EXTERIOR ELEVATION - DEMOLITION KEYNOTES


- 1 REMOVE (E) EXTERIOR SUN SCREENS.
- 2 REMOVE ALL (E) EXTERIOR WINDOWS TYPICAL (EXISTING WINDOWS TO REMAIN & PROVIDE SOLAR CONTROL FILM AT DEDUCT ALT. 2)
- 3 PREPARE (E) EXTERIOR DOOR AND FRAME FOR NEW PAINT. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 4 REMOVE (E) CONCRETE PARAPET WALL. SEE STRUCTURAL DRAWINGS.
- 5 PREP ALL (E) CEMENT PLASTER FOR NEW PAINT, TYPICAL. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 6 PREP ALL (E) EXTERIOR CONCRETE WALLS FOR NEW PAINT, TYPICAL. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 7 REMOVE (E) EXTERIOR CEMENT PLASTER.
- 8 PREP ALL (E) STAIR HAND RAILS FOR NEW PAINT. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 9 PREP ALL (E) GUARD RAILS FOR NEW PAINT. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 10 PREP (E) LOUVERS FOR PAINT. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 11 REMOVE AND DISPOSE OF (E) RAILING.
- 12 PREP (E) SHIPS LADDER FOR PAINT. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 13 REMOVE (E) METAL STUD PARAPET WALL ABOVE WINDOWS
- 14 PREP ALL PARAPET CAPS & METAL FASCIAS FOR NEW PAINT, TYP. (OMIT PREP AT DEDUCTIVE ALTERNATE 3)
- 15 CORE HOLE IN (E) WALL FOR NEW OVER FLOW DRAIN, TYP. COORDINATE LOCATION WITH PLUMBING DRAWINGS.
- 16 (E) EXTERIOR SUN SCREENS TO REMAIN. REMOVE DEBRIS AND CLEAN VIA POWERWASH.
- 17 (E) REMOVE (E) WINDOWS AND (E) METAL STUD WALL BELOW
- 18 REMOVE (E) SUNSCREEN(EXISTING SUNSCREEN TO REMAIN AT DEDUCT ALT. 5)

1 EAST EXTERIOR ELEVATION  
1/8" = 1'-0"

2 NORTH EXTERIOR ELEVATION  
1/8" = 1'-0"

CONSULTANTS:

ARCHITECT/ENGINEERS:



**HMC** Architects

1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720  
T 559 322 2444 / www.hmcarchitects.com

Drawing Title  
**DEMOLITION AND PREP  
EXTERIOR ELEVATIONS**

Approved Project Director

Project Title  
**BUILDING 24  
SEISMIC CORRECTION  
AND ADDITION**

Location  
**VAMC FRESNO, CA**

Date  
**October 14, 2011**

Checked  
**BB**

Drawn  
**CLO**

Project Number  
**570-215**

Building Number  
**24**

Drawing Number

**AD502**  
Dwg. 62 of 180

Office of  
Construction  
and Facilities  
Management

