

LEGEND

NEW GYPSUM WALLBOARD. FINISH TO MATCH EXISTING WALL TEXTURE. REFER TO FINISH SCHEDULE AND FLOOR PLAN FOR ADDITIONAL INFO.

(E) GYPSUM WALLBOARD TO REMAIN. REFINISH TO MATCH EXISTING WALL TEXTURE AFTER (E) WALLCOVERING IS REMOVED. REFER TO FINISH SCHEDULE AND FLOOR PLAN FOR ADDITIONAL INFO.

(E) GYPSUM WALLBOARD TO REMAIN. REFER TO FINISH SCHEDULE AND FLOOR PLAN FOR ADDITIONAL INFO.



P1

INDICATES FINISH COLOR. REFER TO SCHEDULE FOR FINISHES (09 06 00) FINISH TYPE AND COLOR.

- ① (N) RUBBER BASE, TYP. REFER TO FINISH SCHEDULE. (MATCH EXISTING WHERE OCCURS), U.N.O.
- ② (E) BASE TO REMAIN.
- ③ (F) DOOR AND FRAME TO REMAIN. REFER TO DOOR SCHEDULE FOR PAINTING AND FINISHING.
- ④ (E) STOREFRONT SYSTEM TO REMAIN.
- ⑤ NEW ALUMINUM WINDOW AND GLAZING. SEE FLOOR PLAN FOR WINDOW TYPE.
- ⑥ NEW ALUMINUM STOREFRONT SYSTEM AND GLAZING. SEE FLOOR PLAN FOR WINDOW TYPE.
- ⑦ REINSTALL (E) BOOKCASE.
- ⑧ REINSTALL (E) PLIQUE.

9 DEAN 1A-16 - INTERIOR ELEVATIONS
1/4" = 1'-0"

10 ASSISTANT DEAN 1A-17 - INTERIOR ELEVATIONS
1/4" = 1'-0"

		CONSULTANTS:				ARCHITECT/ENGINEERS:		Drawing Title FIRST FLOOR INTERIOR ELEVATIONS		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION		Project Number 570-215		Office of Construction and Facilities Management	
								Approved Project Director		Location VAMC FRESNO, CA		Drawing Number		AS801 Dwg. 77 of 180	
Revisions:		Date								Date October 14, 2011		Checked BB		Drawn CLO	
														 Department of Veterans Affairs	