

- KEY NOTES**
- THIS AREA COVERED BY FIRST FLOOR PIPING. SEE SHEET FP2.3.
 - ALL PENDENT SPRINKLERS TO BE IN CENTERLINE OF CEILING TILE OR LIGHTING PATTERN, UN.C.

- GENERAL NOTES**
- ITEMS SHOWN ON THIS PLAN DESCRIBE GENERAL LAYOUT REQUIREMENTS, AND ARE NOT INTENDED TO SHOW A COMPLETE LAYOUT OF REQUIRED FIRE PROTECTION SYSTEM PIPING AND COMPONENTS. REFER TO ARCHITECTURAL, MECHANICAL AND PLUMBING SHEETS, FIRE PROTECTION SPECIFICATIONS, AS WELL AS OTHER PORTIONS OF THE CONTRACT DOCUMENTS FOR ADDITIONAL COORDINATION REQUIREMENTS.
 - THE LAYOUT REQUIREMENTS DESCRIBED IN THESE PLANS SHALL BE ADHERED TO AS CLOSELY AS POSSIBLE BUT SHALL NOT SUPERSEDE CODE CONSTRAINTS AND/OR REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION (A.H.J.), WHERE CODE OR A.H.J. REQUIREMENTS SUPERSEDE ITEMS SHOWN ON THIS PLAN, CONTRACTOR SHALL INCLUDE ALL ASSOCIATED PROVISIONS IN THE BID, AND SHALL MAKE THEM AT NO ADDITIONAL COST TO OWNER, PROPOSED DEVIATIONS FROM THIS PLAN SHALL BE SUBJECT TO ENGINEER OF RECORD REVIEW AND APPROVAL PRIOR TO IMPLEMENTATION.
 - ALL AREAS OF THE BUILDING NOT COVERED BY NOTES HEREIN SHALL BE FULLY SPRINKLERED IN ACCORDANCE WITH SPECIFICATIONS, NFPA 13, 2010 ED., CITY OF FRESNO FIRE DEPARTMENT REQUIREMENTS, DEPARTMENT OF VETERANS AFFAIRS FIRE PROTECTION DESIGN STANDARDS AND CODE REQUIREMENTS.
 - WHERE PLAN INDICATES EXPOSED FIRE SPRINKLER PIPING DIRECTION OF LAYOUT, ASSOCIATED CONNECTED FIRE SPRINKLER PIPING RUNNING IN PERPENDICULAR DIRECTIONS SHALL BE INSTALLED ONLY IN CONCEALED LOCATIONS UNLESS INDICATED OTHERWISE.
 - INSTALLING CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND IS RESPONSIBLE FOR PREPARING A DESIGN TO ACCOMMODATE ALL EXISTING CONDITIONS.
 - EXPOSED FIRE SPRINKLER SYSTEM PIPING SHALL BE RUN STRAIGHT AND TIGHT TO UNDERSIDE OF STRUCTURAL MEMBERS, AND SHALL NOT OFFSET VERTICALLY TO DROP BELOW BEAMS.

SYMBOLS AND DESCRIPTIONS

SYM	TYPE	FINISH	TEMP	K FACTOR	TRD	Ø IN *	MFG	MODEL	ESCUTCHION
●	SP	WHITE	155	5.6	1/2"	Ø3000	VIKING	MICROFAST	Ø811 REC.

1 SECOND FLOOR FIRE SPRINKLER REFLECTED CEILING PLAN
1/8"=1'-0"


Scale indicators on the left margin:
 A: three inches = one foot
 B: one and one half inches = one foot
 C: one inch = one foot
 D: three quarters inch = one foot
 E: one half inch = one foot
 F: three eighths inch = one foot
 G: one quarter inch = one foot
 H: one eighth inch = one foot

Revisions

No.	Date	Description

CONSULTANTS:

LP Consulting Engineers, Inc.
 895 W. Ashlan Ave., Suite 101 Clovis, CA 93612
 p 559-348-2130 - f 559-348-2131
 www.lpengineers.com
 Job #: 10-1096



ARCHITECT/ENGINEERS:

HMC Architects
 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720
 T 559 322 2444 / www.hmcarchitects.com

Drawing Title
SECOND FLOOR FIRE SPRINKLER REFLECTED CEILING PLAN

Approved Project Director

Project Title
BUILDING 24 SEISMIC CORRECTION AND ADDITION

Location
VAMC FRESNO, CA

Date
JANUARY 31, 2012

Checked
SA

Drawn
ES

Project Number
570-215

Building Number
24

Drawing Number
FP202
 Dwg 126 of 180

Office of Construction and Facilities Management
 Department of Veterans Affairs