



- ## KEY NOTES
- | | |
|---|--|
| 1 | REMOVE (E) DUCT SHOWN HATCHED. ALL DUCTWORK TO REMAIN SHALL BE CLEANED PER SPEC. SECT. 23 31 00. |
| 2 | REMOVE (E) VAV BOX WITH REHEAT COIL. |
| 3 | REMOVE (E) VAV BOX. |
| 4 | REMOVE (E) CEILING GRILLE. |
| 5 | (E) ATTIC MOUNT IN-LINE EXHAUST FAN TO REMAIN. |

1 SECOND FLOOR MECHANICAL DEMOLITION PLAN
SCALE: 1/8" = 1'-0"

[illegible]

CONSULTANTS:



LP Consulting Engineers, Inc.
895 W. Ashland Ave, Suite 101 Clovis, CA 93611
p 559-348-2130 - f 559-348-2131
www.lpengineers.com
Job #: 10-1096



ARCHITECT/ENGINEERS:

HMC Architects

1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720
T 559 322 2444 / www.hmcarchitects.com

Drawing Title
**SECOND FLOOR MECHANICAL
DEMOLITION PLAN**

Approved: Project Director

Project Title	BUILDING 24 SEISMIC CORRECTION AND ADDITION
---------------	---

Location	VAMC FRESNO, CA
----------	-----------------

Date
January 31, 2012

Check	KK
-------	----

Drawn	DN
-------	----

Project Number	570-215
Building Number	24

Drawing Number

MD102

Dwg. 133 of 180

Office of
Construction
and Facilities
Management

