



- FIRST FLOOR LIGHTING DEMO NOTES:**
- ① REMOVE EXISTING LIGHTS AND RELATED CONDUITS AND WIRING IN ROOM. VERIFY WORK REQUIRED IN FIELD.
 - ② EXISTING SWITCHES TO BE REPLACED. REMOVE EXISTING SWITCHES AND WIRING.
 - ③ REMOVE EXISTING CEILING MOUNTED PUBLIC ADDRESS SPEAKER AND RELATED BACKBOX, CONDUITS AND CABLING.
 - ④ VERIFY EXISTING LIGHTING HOMERUN IN FIELD. REMOVE EXISTING CONDUITS AND WIRING.
 - ⑤ EXISTING LIGHTS CONNECTED TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING LIGHTS, CONDUITS AND WIRING.
 - ⑥ EXISTING EXIT SIGNS CONNECTED TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING SIGNS, CONDUITS AND WIRING.
 - ⑦ EXISTING EMERGENCY LIGHTING CIRCUIT TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. EXISTING TRANSFORMER AND HOMERUN TO PANEL "E" TO REMAIN.
 - ⑧ EXISTING STAIR LIGHTS CONNECTED ON EXISTING 120V EMG PANEL "E", TO REMAIN.

① DEMOLITION FIRST FLOOR LIGHTING PLAN
1/8" = 1'-0"

CONSULTANTS: 895 W. Ashlan Ave, Suite 101 Clovis, CA 93612 p 559-432-1249 • f 559-432-1625 www.lpeengineers.com Job #: 10-1096		 ARCHITECT/ENGINEERS: 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Drawing Title DEMOLITION FIRST FLOOR LIGHTING PLAN Approved Project Director		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION Location VAMC FRESNO, CA Date January 31, 2012 Checked FK Drawn FK/LS		Project Number 570-215 Building Number 24 Drawing Number ED101 Dwg. 156 of 180		Office of Construction and Facilities Management 	
---	--	--	--	--	--	---	--	---	--	---	--

Scale: one eighth inch = one foot
one quarter inch = one foot
three eighths inch = one foot
one half inch = one foot
three quarters inch = one foot
one inch = one foot
one and one half inches = one foot
two inches = one foot
three inches = one foot
four inches = one foot
one foot = one foot