



- SECOND FLOOR ELECTRICAL DEMO NOTES:**
- EXISTING ELECTRICAL TO REMAIN.
  - EXISTING ELECTRIC DRINKING FOUNTAIN TO BE REPLACED. REMOVE EXISTING RECEPTACLE AND WIRING. PROVIDE NEW GFI RECEPTACLE WITH NEW WALL PLATE, NEW CONDUITS AND WIRING. COORDINATE WITH SUPPLIER THROUGH COTR.
  - REFER TO ARCHITECTURAL PLANS FOR EXISTING WALLS TO RECEIVE NEW WALL COVERINGS OR FINISH. CONTRACTOR SHALL VERIFY IN FIELD LOCATION OF ALL EXISTING ELECTRICAL OUTLETS, DEVICES AND EQUIPMENT IN OR ON WALL. REMOVE AND REINSTALL EXISTING DEVICE PLATES AT FLUSH OUTLETS, WITH NEW EXTENSION RING AND NEW WALL PLATE. REMOVE AND REINSTALL EXISTING SURFACE ELECTRICAL ON WALL.
  - REFER TO ARCHITECTURAL PLANS FOR EXISTING WALLS TO RECEIVE NEW WALL COVERINGS OR FINISH, AND EXISTING FLOOR COVERING TO BE REPLACED. CONTRACTOR SHALL VERIFY IN FIELD ELECTRICAL CONNECTION LOCATION AND REQUIREMENT OF ALL EXISTING ELECTRIFIED WORK STATIONS. REMOVE AND REINSTALL EXISTING ELECTRICAL TO RECONNECT WORK STATIONS.
  - EXISTING CEILING TO BE REPLACED. CONTRACTOR SHALL VERIFY IN FIELD LOCATION OF ALL EXISTING ELECTRICAL OUTLETS, DEVICES AND EQUIPMENT IN OR ON CEILING FOR EXISTING CEILING MOUNTED PROJECTOR. REMOVE AND REINSTALL EXISTING ELECTRICAL WITH NEW FACE PLATES.
  - REMOVE EXISTING ELECTRICAL OUTLETS, DEVICES AND WIRING IN EXISTING WALLS TO BE REPLACED. REINSTALL EXISTING DEVICE IN NEW OUTLET WITH NEW PLATES, CONDUITS AND WIRING.
  - EXISTING WALLS TO BE REMOVED. REMOVE EXISTING ELECTRICAL OUTLETS, DEVICES AND RELATED CONDUITS AND WIRING.
  - REMOVE EXISTING CONDUITS AND WIRING.
  - VERIFY LOCATION OF EXISTING HOMERUN IN FIELD. REMOVE EXISTING CONDUIT AND WIRING.
  - INSIDE OF ALL EXTERIOR WALLS ARE TO BE FURRED. REFER TO ARCHITECTURAL PLANS FOR INFO AND DETAILS. CONTRACTOR SHALL PROVIDE EXTENSION RINGS AND NEW WALL PLATES TO BRING EXISTING DEVICE OUT WITH THE FRONT EDGE OF THE RING FLUSH WITH FINISHED WALL SURFACE.
  - EXISTING FURNITURE PANELS HAVE OVERHEAD POWER AND TEL/DATA CONNECTION RUN IN EXISTING FURNITURE PANEL COLUMNS. EXISTING CEILING IS BEING REPLACED. EXISTING ELECTRICAL IN ATTIC SHALL REMAIN AND SHALL BE RECONNECTED.

1 DEMOLITION SECOND FLOOR ELECTRICAL PLAN  
1/8" = 1'-0"



CONSULTANTS:

**LP Consulting Engineers, Inc.**  
895 W. Ashlan Ave., Suite 101 Clovis, CA 93612  
p 559-432-1249 • f 559-432-1625  
www.lpeengineers.com  
Job #: 10-1096

ARCHITECT/ENGINEERS:

**HMC Architects**

1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720  
T 559 322 2444 / www.hmcarchitects.com

Drawing Title  
**DEMOLITION SECOND FLOOR ELECTRICAL PLAN**

Approved Project Director

Project Title  
**BUILDING 24  
SEISMIC CORRECTION  
AND ADDITION**

Location  
**VAMC FRESNO, CA**

Date  
**January 31, 2012**

Checked  
**PK**

Drawn  
**PK/LS**

Project Number  
**570-215**

Building Number  
**24**

Drawing Number  
**ED202**  
Dwg. 160 of 180

Office of  
Construction  
and Facilities  
Management

