



- THIRD FLOOR LIGHTING DEMO NOTES:**
- ① REMOVE EXISTING LIGHTS AND RELATED CONDUITS AND WIRING IN ROOM. VERIFY WORK REQUIRED IN FIELD.
  - ② REMOVE EXISTING PARAPET MOUNTED EXTERIOR LIGHTS AND RELATED CONDUITS AND WIRING. RETURN LIGHTS TO OWNER.
  - ③ EXISTING LIGHT TO BE REPLACED. REMOVE EXISTING LIGHT AND RELATED CONDUITS AND WIRING.
  - ④ EXISTING SWITCHES TO BE REPLACED. REMOVE EXISTING SWITCHES AND WIRING.
  - ⑤ REMOVE EXISTING SWITCHES AND RELATED OUTLETS, CONDUITS AND WIRING.
  - ⑥ TYPICAL: EXISTING EXIT SIGNS CONNECTED TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING SIGNS, CONDUITS AND WIRING.
  - ⑦ EXISTING LIGHTS CONNECTED TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING LIGHTS, CONDUITS AND WIRING.
  - ⑦A EXISTING EMERGENCY LIGHTING CIRCUIT TO EXISTING 120V EMG PANEL "E" VIA 120V/277V TRANSFORMER. EXISTING TRANSFORMER AND HOMERUN TO PANEL "E" TO REMAIN.
  - ⑧ REMOVE EXISTING CEILING MOUNTED PUBLIC ADDRESS SPEAKER AND RELATED BACKBOX, CONDUITS AND CABLING.
  - ⑨ VERIFY EXISTING LIGHTING HOMERUN IN FIELD. REMOVE EXISTING CONDUITS AND WIRING.
  - ⑩ EXISTING STAIR LIGHTS CONNECTED ON EXISTING 120V EMG PANEL "E", TO REMAIN.
  - ⑪ EXISTING LOW WALL IS TO BE REMOVED. REMOVE EXISTING LIGHT AND RELATED CONDUITS AND WIRING.

① DEMOLITION THIRD FLOOR LIGHTING PLAN  
1/8" = 1'-0"

three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
three eighths inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot

<b>CONSULTANTS:</b>  895 W. Ashlan Ave., Suite 101, Clovis, CA 93612 p 559-432-1249 • f 559-432-1625 www.lpengines.com Job #: 10-1096		<b>ARCHITECT/ENGINEERS:</b>  1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		<b>Drawing Title</b> DEMOLITION THIRD FLOOR LIGHTING PLAN <b>Approved: Project Director</b>		<b>Project Title</b> BUILDING 24 SEISMIC CORRECTION AND ADDITION <b>Location</b> VAMC FRESNO, CA <b>Date</b> January 31, 2012 <b>Checked</b> PK <b>Drawn</b> PK/LS		<b>Project Number</b> 570-215 <b>Building Number</b> 24 <b>Drawing Number</b> ED301 Dwg. 162 of 180		<b>Office of Construction and Facilities Management</b> 	
--	--	--	--	---	--	---	--	---	--	---	--