



- FIRST FLOOR ELECTRICAL PLAN NOTES:**
- 1 UNLESS OTHERWISE NOTED, EXISTING ELECTRICAL TO REMAIN.
 - 2 PROVIDE NEW GFI RECEPTACLE FOR NEW ELECTRIC DRINKING FOUNTAIN. VERIFY RECEPTACLE LOCATION WITH EDP SUPPLIER. PROVIDE NEW CONDUITS AND WIRING AS REQUIRED TO CONNECT NEW AND EXISTING CIRCUIT.
 - 3 PROVIDE NEW CONDUITS AND WIRING TO RECONNECT EXISTING BRANCH CIRCUIT. VERIFY WORK REQUIRED IN FIELD.
 - 4 RECONNECT EXISTING WORK STATION TO EXISTING POWER AND TEL/DATA CONNECTION. VERIFY WORK REQUIRED IN FIELD. PROVIDE NEW CONDUITS AND WIRING AS REQUIRED.
 - 5 PROVIDE NEW LIGHT AND SWITCH AND RECEPTACLE IN ELEVATOR PIT, AS DIRECTED BY ELEVATOR SUPPLIER.
 - 6 RUN 3/4" WITH 2#12 + 1#12 GROUND TO NEW PANEL "P1B". RUN IN FIRST FLOOR ATTIC. VERIFY ROUTING IN FIELD. PROVIDE ACCESSIBLE PULL BOXES AS REQUIRED.
 - 7 PROVIDE NEW PANEL SURFACE MOUNT ON WALL.
 - 8 RUN FEEDER PER LINE DIAGRAM TO EXISTING DISTRIBUTION PANEL "DP" IN SECOND FLOOR ELECTRICAL ROOM. VERIFY ROUTING IN FIELD. PROVIDE ACCESSIBLE PULL BOXES AS REQUIRED.

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot

CONSULTANTS: 895 W. Ashlan Ave., Suite 101, Clovis, CA 93612 p 559-432-1249 • f 559-432-1625 www.lpeengineers.com Job #: 10-1098		ARCHITECT/ENGINEERS: 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Drawing Title FIRST FLOOR ELECTRICAL PLAN Approved Project Director		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION Location VAMC FRESNO, CA Date January 31, 2012 Checked FK Drawn PK/LS		Project Number 570-215 Building Number 24 Drawing Number ES102 Dwg 168 of 180		Office of Construction and Facilities Management 	
---	--	--	--	---	--	---	--	--	--	---	--