



- FIRST FLOOR HVAC ELECTRICAL PLAN NOTES:**
- ① NEW VAV BOX TO REPLACE EXISTING. RECONNECT EXISTING CONTROL WIRING.
 - ② NEW AIR HANDLER MOTORS TO REPLACE EXISTING. DISCONNECT EXISTING ELECTRICAL. CONNECT NEW MOTORS TO EXISTING POWER WIRING.
 - ③ NEW FAN COIL IN ATTIC. VERIFY CONNECTION LOCATION AND REQUIREMENT IN FIELD WITH HVAC CONTRACTOR. PROVIDE NEW FUSED DISCONNECT SWITCH IN ACCESSIBLE ATTIC, AT LOCATION WITH MINIMUM 30" X 36" FRONT WORKING CLEARANCE.
 - ④ RUN 3/4" C WITH 2#12 + 1#12 GROUND TO EXISTING PANEL "P1A". PROVIDE NEW 20A/2P BREAKER IN PANEL.
 - ⑤ TYPICAL: DENOTE MECHANICAL UNIT IDENTIFICATION. REFER TO SCHEDULES ON SHEETS MH600 & MH601.

① FIRST FLOOR HVAC ELECTRICAL PLAN
1/8" = 1'-0"

② FIRST FLOOR HVAC ELECTRICAL PLAN - DEDUCTIVE ALTERNATE 1
1/8" = 1'-0"

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot

CONSULTANTS: LP Consulting Engineers, Inc. 895 W. Ashlan Ave, Suite 101 Clovis, CA 93612 p 559-432-1249 • f 559-432-1625 www.lpeengineers.com Job #: 10-1096		ARCHITECT/ENGINEERS: HMC Architects 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Drawing Title FIRST FLOOR HVAC ELECTRICAL PLAN		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION		Project Number 570-215 Building Number 24		Office of Construction and Facilities Management
Revisions Date		Approved Project Director		Location VAMC FRESNO, CA		Drawing Number ES104 Dwg 170 of 180				
				Date January 31, 2012		Checked PK	Drawn PK/LS			

VA FORM 08-6231