



- ROOF/PENTHOUSE ELECTRICAL PLAN NOTES:**
- ① EXISTING HVAC EQUIPMENT AND RELATED ELECTRICAL TO REMAIN. NO NEW WORK UNLESS OTHERWISE NOTED.
 - ② NEW AIR HANDLER MOTORS TO REPLACE EXISTING. DISCONNECT EXISTING ELECTRICAL. CONNECT NEW MOTORS TO EXISTING POWER WIRING.
 - ③ EXISTING MOTOR CONTROL PANEL, PANELS, TRANSFORMER, ETC. TO REMAIN. NO NEW WORK UNLESS OTHERWISE NOTED.
 - ④ CONNECT EXH FAN. PROVIDE WEATHERPROOF TOGGLE SWITCH AS DISCONNECT. PROVIDE CONTROL CONDUIT AND WIRING AS DIRECTED BY CONTROL CONTRACTOR.
 - ⑤ CONNECT ERV. PROVIDE WEATHERPROOF FUSED DISCONNECT SWITCH. PROVIDE CONTROL CONDUIT AND WIRING AS DIRECTED BY CONTROL CONTRACTOR.
 - ⑥ CONNECT ODU-2. PROVIDE WEATHERPROOF FUSED DISCONNECT SWITCH. PROVIDE CONTROL CONDUIT AND WIRING AS DIRECTED BY CONTROL CONTRACTOR.
 - ⑦ CONNECT ODU-1. PROVIDE WEATHERPROOF FUSED DISCONNECT SWITCH. PROVIDE CONTROL CONDUIT AND WIRING AS DIRECTED BY CONTROL CONTRACTOR.
 - ⑧ 1" C WITH 3/8" + 1/10" GROUND TO EXISTING PANEL "MP".
 - ⑨ PROVIDE NEW 45A/3P BREAKER IN EXISTING PANEL "MP" WITH NAMEPLATE.
 - ⑩ 1" C - 2#10 + 1#10 GROUND.

① PENTHOUSE AND ROOF ELECTRICAL PLAN
1/8" = 1'-0"

Scale: three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot

CONSULTANTS: LP Consulting Engineers, Inc. 895 W. Ashlan Ave., Suite 101, Clovis, CA 93612 p 559-432-1249 • f 559-432-1625 www.lpeengineers.com Job #: 10-1098		ARCHITECT/ENGINEERS: HMC Architects 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		Drawing Title PENTHOUSE AND ROOF ELECTRICAL PLAN Approved Project Director		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION Location VAMC FRESNO, CA Date January 31, 2012 Checked PK Drawn PK/LS		Project Number 570-215 Building Number 24 Drawing Number ES402 Dwg. 179 of 180		Office of Construction and Facilities Management 	
--	--	--	--	--	--	---	--	---	--	---	--