




I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR
 REPORT WAS PREPARED BY ME OR UNDER MY DIRECT
 SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT
 UNDER THE LAWS OF THE STATE OF MINNESOTA.
 PRINT NAME: **MARK A. JASMIN**
 SIGNATURE: 
 DATE: **12/9/2011** LICENSE # **18698**

1. COLOR IS A VERY IMPORTANT PART OF THIS PROJECT. ANY COLOR OR FINISH REQUESTED FROM THE ARCHITECT, SEE SECTION 00400 AND SECTION 01640.

A. PROVIDE CONSISTENT MATERIAL COLORS AND PATTERNS IN EACH ROOM OR AREA.

1. IF REQUIRED FOR CONSISTENCY, PROVIDE MATERIALS FROM SAME PRODUCTION RUN.

2. CEILING HIGHT INDICATED IN FEET-INCHES; 8 FEET - 0 INCHES.

3. WHERE ITEMS OR SURFACES ARE NOT SPECIFICALLY MENTIONED, PAINT THE SAME AS SIMILAR ADJACENT MATERIALS OR AREA. IF COLOR OR FINISH IS NOT SPECIFICALLY INDICATED, DO NOT SELECT FROM STANDARD COLORS OR FINISHES AVAILABLE.

4. UNLESS OTHERWISE INDICATED, DO NOT INCLUDE PAINTING WHEN FACTORY-FINISHING OR INSTALLER FINISHING IS SPECIFIED FOR SUCH ITEMS, BUT NOT LIMITED TO: METAL TOILET ENCLOSURE, PRE-FINISHED ALUMINUM CASES, ACOUSTIC MATERIALS, ARCHITECTURAL WOODWORK AND CABINETS, STAINLESS STEEL ELEVATOR ENTRANCE DOORS AND TRANSOMS, WALL-MOUNTED LIGHT FIXTURES, SWITCHGEAR AND DISTRIBUTION CABINETS.

5. GRILLS, DIFFUSERS, ELECTRICAL PANELS, ACCESS PANELS, ETC., WHICH ARE EXPOSED IN FINISH SPACES SHALL BE PAINTED TO MATCH THE SURFACE ON WHICH THEY OCCUR.

6. PAINT INTERIOR SURFACES OF DOORS FLAT BLACK WHERE SURFACES ARE VISIBLE THROUGH GRILLS OR DIFFUSERS.

7. UNLESS OTHERWISE INDICATED, METAL SURFACES OF ANODIZED ALUMINUM MATERIALS, STAINLESS STEEL, BRASS, CHROME PLATE, COPPER, BRONZE AND SIMILAR FINISHED MATERIALS WILL NOT REQUIRE FINISH PAINTING.

8. IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS, PROVIDE THREE SAMPLES OF EACH COLOR AND MATERIAL AS REQUIRED FOR APPROVAL. PRESERVE SAMPLES AS REQUESTED BY ARCHITECT UNTIL THE END OF COLOR AND TEXTURE IS ACHIEVED.

9. ON ACTUAL WORK SURFACES, PROVIDE THREE 4 IN X 8 IN SAMPLES OF UNPAINTED AND STAINED WOOD FINISHED. LABEL AND IDENTIFY EACH AS TO LOCATION AND APPLICATION.

10. PLASTIC LAMINATE COLORS SHALL BE VERIFIED ON ALL APPROVED MILLWORK AND DRAWINGS.

11. ALL PLASTIC LAMINATE MILLWORK SHALL BE PL-1 UNLESS NOTED OTHERWISE.

12. HOLLOW METAL DOORS AND HOLLOW METAL FRAMES SHALL BE PAINTED PINTO-1 IN ALL AREAS.

13. COORDINATE WITH CONCRETE CURING METHOD. SEE SECTION 03310.

14. PROVIDE VAPOR EMISSION CONTROL SYSTEM FOR CONCRETE WITH APPLIED FLOORING. SEE SECTION 09060.

15. ENTRANCE DOORS AND FRAMES EXCEPT THOSE THAT ARE PRE-FINISHED STAINLESS STEEL, SHALL BE PAINTED PINTO-1 IN ALL AREAS.

16. SOFFIT BOTTOMS SHALL MATCH ADJACENT WALL FINISH.

17. ALL WALL GUARDS, CORNER GUARDS, CHAIR RAILS AND HANDRAILS (SECTION 10260) SHALL BE ACRYLIC, COLOR: EGG-SHELL, UNLESS NOTED OTHERWISE.

18. ALL SOFFIT CONDITIONS SHALL BE PINTO-4.

19. ALL MILLWORK TO HAVE EDGE BANDING TO MATCH CORRESPONDING.

20. PROVIDE CORRESPONDING CT BORDER BEHIND ALL MIRRORS, PAPER TOWEL DISPENSERS, OR OTHER SURFACE MOUNTED ITEMS THAT EXTEND BEYOND THE FACE OF THE GYPSUM. SEE ELEVATIONS AND INTERIOR DETAILS.

21. ALL GYP. CEILINGS SHALL BE PNT-2, UNLESS NOTED OTHERWISE.

22. TILE TO RECEIVE EPOXY GROUT - TEC, SERIES: ACCOY COLLOR, EFX. COLOR: RIVER ROCK #890.

REMARKS:

1. PATCH TO MATCH EXISTING FINISHES AS INDICATED ON INTERIOR FINISH PLAN.

Office of
Construction
and Facilities
Management

