PLAN NOTES

1.- PROVIDE FIRE ALARM ADDRESSABLE MONITORING FOR MOBILE SPS TRAILER FIRE ALARM SYSTEM. CONNECT TO TRAILER'S RJ-45 CONNECTION. MONITOR FOR ALARM AND TROUBLE. COORDINATE ALL CONNECTIONS WITH MOBILE SPS TRAILER PROVIDER.

2.- EXISTING TELECOMMUNICATIONS ROOM "HC-15," ROOM #1B006.

3.- PROVIDE A NEW 6-STRAND, 62.5-MICRON MULTIMODE FIBER (TO MATCH EXISTING) BETWEEN TR "HC-15" AND THE TEMPORARY STERILE PROCESSING TRAILER. PROVIDE A 2" MANUFACTURED FIRE-RATED SLEEVES AT ANY FIRE-RATED WALL PENETRATIONS. TERMINATE FIBER ON BOTH ENDS IN A WALL MOUNTED FIBER PATCH PANEL WITH LC CONNECTORS. INSTALL THE WALL MOUNTED FIBER PATCH PANEL ON THE WEST WALL WITHIN "HC-15". FIELD COORDINATE THE EXACT LOCATION OF THE WALL MOUNTED FIBER PATCH PANEL WITHIN THE TRAILER WITH THE TRAILER SUPPLIER. THIS LOCATION SHALL BE WITHIN 5' OF THE NETWORK RACK SUPPLIED WITH THE TRAILER. PROVIDE THREE 10' LC TO SC CONNECTOR PATCH CORDS WITHIN TR "HC-15" AND WITHIN THE TRAILER.

4.- PROVIDE NEW FIRE ALARM DEVICES AS SHOWN. FIRE ALARM DEVICES ARE TO BE AN EXTENSION OF THE EXISTING SYSTEM.

5.- LOCATION OF EXISTING FIRE ALARM CONTROL PANEL. COORDINATE ROUTING OF CONDUIT FOR FIRE ALARM FEEDS WITH ALL EXISTING CONDITIONS.

6.- APPROXIMATE ROUTING LOCATION FOR FIRE ALARM CONNECTION TO MOBILE SPS.

7.- PROVIDE TAMPER SWITCH FOR FIRE SUPPRESSION SYSTEM EXTENSION. INTEGRATE FLOW AND TAMPER SWITCH TO THE EXISTING FIRE ALARM SYSTEM. PROVIDE ALL REQUIRED RELAYS AND EQUIPMENT FOR MONITORING OF SWITCHES BY FIRE ALARM SYSTEM.

1 / T8.01 TECHNOLOGY SITE PLAN
1/16" = 1'-0"

Revisions:	Date
BID DOCUMENTS - 100% SET REVISED	2016 11-18
BID DOCUMENTS - 100% SET	2016 05-11
CONSTRUCTION DOCUMENTS - 95% REVIEW SET	2016 03-30
DESIGN DEVELOPMENT TWO - 75% REVIEW SET	2016 02-03
DESIGN DEVELOPMENT ONE - 50% REVIEW SET	2015 11-25
SCHEMATIC DESIGN REVISIONS - 25% REVIEW SET	2015 10-21
SCHEMATIC DESIGN - 25% REVIEW SET	2015 10-07

C:\Users\mbaker\Documents\150262_TECH_Central_mbaker.rvt

CONSULTANTS:

Dynamix Engineering Ltd.
Facility Engineering Consultants
855 Grandview Avenue, 3rd Floor Columbus, OH 43215
Phone: (614) 443-1178 Fax: (614) 443-1394
Email: dynamix@dynamix-ltd.com
DEL# -

Jezerinac Geers Structural Engineering
Jezerinac Geers & Associates, Inc.
5640 Frantz Road, Dublin, OH 43017
614.766.0066, fax 614.766.1223
www.jgaeng.com

EMH&T
Engineers, Surveyors, Planners, Scientists

MACE E-50556
MONTGOMERY E-66882
GRIFFIN E-57049

ARCHITECT/ENGINEERS:

m+a
775 Yard Street, Suite 325
Columbus, Ohio 43212
p 614 764 0407
f 614 764 0237
www.ma-architects.com

BID DOCUMENTS - BID

Drawing Title: Technology Site Plan	Project Title: EXPAND LAB AND SPS DEPARTMENTS	Project Number: 757-16-101	
		Building Number: 1A	
Approved: FARID MEHR, PE CHIEF, ENGINEERING SERVICE	Location: CHALMERS P. WYLIE VA AMBULATORY CARE CENTER	Drawing Number: T8.01	
	Date: 2016-05-11 / Checked By: DEL / Drawn By: DEL		

Columbus VA
Chalmers P. Wylie Ambulatory Care Center
VA U.S. Department of Veterans Affairs