



U.S. Department
of Veterans Affairs

New York/New Jersey VA Health Care Network
Canandaigua VA Medical Center
400 Fort Hill Avenue | Canandaigua, NY 14424

www.canandaigua.va.gov

Statement of Work
Exam Tables - OBGYN

Procurement Delivery Need: Tentative April 2019

Scope: The new Rochester Outpatient Clinic is scheduled to fully open April 2019. The Rochester VA has a requirement to procure new equipment for the services as well as trade in old units where opportunities exist to maximize costs savings. For the purpose of this SOW the new Rochester Outpatient Clinic requires to outfit the Exam Rooms.

This is a "brand name or equal" request. The basis of design for the specified make/model identified below was utilized to establish room design, fit, form, and functionality. Specifications of this procurement must equal or surpass functionality and not exceed specified dimensions. The procedure table requirement is for the OB-GYN department at the new Rochester Outpatient Clinic facility

Procurement Requirement/Specifications:

- Delivery and installation must be included. Tentative delivery is scheduled for February 2019; any delay in construction must be accounted for as it may affect delivery schedules. No on site storage will be provided.
- Any packaging material must be removed from site upon completion of installation.
- Training and education shall be included in the request before clinical use.

Project Delivery Location:

Rochester VA Outpatient Clinic
260 Calkins Road
Henrietta, NY 14623

Electrical Safety Requirements: For equipment that will be used in the patient care vicinity, the resistance between the equipment chassis, or any exposed conductive surface of the equipment, and the ground pin of the attachment plug shall be less than .50 ohm. The leakage current flowing through the ground conductor of the power supply connection to ground of permanently wired equipment installed in general or critical care areas shall not exceed 10.mA (AC or DC) with all grounds lifted. Equipment must comply with standards outlined in both National Fire Protection Association "Health Care Facilities" (NFPA- 99) standard and the latest edition of The Joint Commission "Comprehensive Accreditation Manual for Hospitals."

Standard Warranty Required: All products are required to be warranty free from defects in workmanship and materials, under normal use and conditions, for a period of one year from the date of delivery. During the warranty period, any defect in material or workmanship that requires repair or exchange of a product of comparable nature will occur by seller without charge incurred by the VA.

Such repair or replacement is subject to verification and approval by the VA due to Medical Center governing policies.

Shipping: Standard freight on board "FOB" destination shipping must be included.

Brand name or equal units:

Item #	Description/Part Number	Qty
1	630-010 / MidMark HumanForm Power Procedure table, non-programmable w/electrical Receptacle-base only	4
2	002-10108-XXX / Upholstery Top - 630 28" Premium - Standard Color	4

Please note:

All proposals deemed to meet or exceed the specifications of the brand and model identified will be given full consideration. Award will be based on a lowest priced technically acceptable basis. All proposals must meet or exceed the salient characteristics listed below.

- Power height, power backrest, power Trendelenburg tilt, power footrest
- 18" low height, 40" high height
- 650 lb. lifting capacity
- Patient Transfer Position (PTP): **must have FLAT-back position at 18" for true safe patient handling** and wheelchair transfer; 72" long x 28" wide transfer area
- Chair position or flat table position at any height
- 72" - 76" long x 28" wide patient surface
- Interchangeable headrest system (no tools needed)
- Adjustable, removable 12" wide oval headrest standard
- Paper roll holder
- Quick-Chair™/Auto-return button
- Active Sensing Technology®
- Smooth-start electromechanical actuator motors
- Premium Comfort System® - elastomeric seat cutout for patient comfort
- Two UL-listed, duplex, hospital-grade electrical receptacles
- Multi-position hideaway stirrups
- Stainless steel treatment pan
- Seamless upholstery for cleaning/infection control
- Removable upholstery top system for cleaning and easy replacement (no tools needed)
- Steel-on-steel construction on all weight-bearing points for durability
- Hand and foot control standard
- Seamless/sealed foot control for cleaning/infection control
- Accessory rails standard
- Galvanized leveling feet
- Color options
- UL- listed